

RECEIVED
AUG 29 1933

A T T E N T I O N

THIS FORM IS TO BE USED ONLY WHEN WATER HAS BEEN PLACED TO BENEFICIAL USE

DIVISION OF
OIL, GAS & MINING

Form 152

BEFORE THE STATE ENGINEER OF THE STATE OF UTAH

ELECTION TO FILE WATER USER'S CLAIM

APPLICATION NO. 32773(09-281)

STATE OF ~~UTAH~~ Utah

COUNTY OF San Juan

} ss.

Phillips Petroleum Company, being first duly sworn,
says that he is the owner of the above application; that the development con-
templated under this application has been completed and the water placed to
beneficial use.

In lieu of submitting "Proof of Appropriation" or "Proof of Change"
and receiving "Certificate of Appropriation" or "Certificate of Change", the
applicant hereby elects to file a "Statement of Water User's Claim" or an
"Amended Statement of Water User's Claim" in the pending GENERAL DETERMINATION
OF WATER RIGHTS; and that the applicant requests that said statement be pre-
pared by the State Engineer and submitted for execution at an early date.

Phillips Petroleum Company

By: H. A. Kuehnert

Attorney-in-Fact

H. A. Kuehnert
APPLICANT

ROE

Subscribed and sworn to before me this 28th day of Sept

.19 33.

W. L. ...
NOTARY PUBLIC

My commission expires: 9-16-33

J. F. Denny

RECEIVED

AUG 29 1983

December 23, 1970

DIVISION OF
OIL, GAS & MINING

Mr. Kenward H. McKinney, Area Engineer
State of Utah
Department of Natural Resources
6 East Main
Price, Utah 84501

[Handwritten signature]
Herb
[Circular stamp] *JS*

Dear Mr. McKinney:

Enclosed is a completed and notarized State of Utah Form No. 152,
"Election to File Water User's Claim" for water placed in beneficial
use by Phillips Petroleum Company in the Ratherford Unit, San Juan
County, Utah.

Very truly yours,

[Handwritten signature]
H. W. Patterson
Production Director
Western District

CML:rc
Attachment

bcc: Mr. J. P. Denny (2)



RECEIVED
AUG 30 1983

INTER-OFFICE CORRESPONDENCE / SUBJECT:

Denver Legal Department

Ratherford Unit
San Juan County, Utah
Application No. 32773
Proof of Appropriation

DIVISION OF
OIL, GAS & MINING

December 2, 1970

Mr. H. W. Patterson
Denver District Office

This is in answer to your inquiry of November 20, 1970, regarding the filing of an Election to File Water Users Claim in lieu of a Proof of Appropriation in the above matter. It is my opinion that we should elect to file the Election to File Water Users Claim.

An investigation of the pertinent Utah Statutes discloses that there is no difference between the legal effect of the two procedures. The election procedure is judicial in nature and results in a court order stating precisely our rights regarding use of the water. The decision is based upon the recommendation of the State Engineer, who has the responsibility for surveying, etc. if it is necessary. In short, we will get the same benefit at little or no expense.

Thomas M. Blume
Thomas M. Blume

TMB/cjk

Ratherford Unit
San Juan County, Utah
Application No. 32773
Proof of Appropriation

1300 Security Life Building
Denver, Colorado 80202

November 20, 1970

Mr. T. M. Blume
Division Chief Attorney
Denver Legal Department

Attached is a file pertaining to Phillips Petroleum Company's application for permanent use of water from underground and subsurface flow of the San Juan River in Utah for the beneficial use of pressure maintenance and secondary recovery in the Ratherford Unit.

I would like to direct your attention to Mr. C. M. Boles' letter of November 23, 1965, for background information.

On June 16, 1966, the Utah State Engineer granted a five-year extension to our Application No. 32773 for submittal of Proof of Appropriation. This extension will have elapsed on February 26, 1971.

We are preparing to file the Proof of Appropriation, however, the Casper office has information from the Area Engineer, Division of Water Rights, Department of Natural Resources, State of Utah that the filing of Proof of Appropriation is not necessary, but that filing of an Election to File Water Users Claim is necessary for permanent use of water from subsurface flow of the San Juan River.

We will appreciate your opinion on this filing.

H. W. Patterson

CML:rc
Attachment

cc: Mr. T. A. Matthews

APPLICATION TO APPROPRIATE WATER
STATE OF UTAH

NOTE:—The information given in the following blanks should be free from explanatory matter, but when necessary, a complete supplementary statement should be made on the following page under the heading "Explanatory."

For the purpose of acquiring the right to use a portion of the unappropriated water of the State of Utah, for uses indicated by (X) in the proper box or boxes, application is hereby made to the State Engineer, based upon the following showing of facts, submitted in accordance with the requirements of the Laws of Utah.

1. Irrigation ☐ Domestic ☐ Stockwatering ☐ Municipal ☐ Power ☐ Mining ☒ Other Uses ☐
2. The name of the applicant is..... PHILLIPS PETROLEUM COMPANY
3. The Post Office address of the applicant is..... Bartlesville, Oklahoma
4. The quantity of water to be appropriated is..... -- 8 -- second-feet or..... acre-feet
5. The water is to be used for..... See Explanatory from January 1 to December 31
(Major Purpose) (Month) (Day) (Month) (Day)
other use period..... from..... to.....
(Minor Purpose) (Month) (Day) (Month) (Day)
and stored each year (if stored) from..... to.....
(Month) (Day) (Month) (Day)
6. The drainage area to which the direct source of supply belongs is..... (Leave Blank)
7. The direct source of supply is* Underground water and subsurface flow of San Juan River
(Name of stream or other source)
which is tributary to Colorado River tributary to.....
- *Note.—Where water is to be diverted from a well, a tunnel, or drain, the source should be designated as "Underground Water" in the first space and the remaining spaces should be left blank. If the source is a stream, a spring, a spring area, or a drain, so indicate in the first space, giving its name, if named, and in the remaining spaces, designate the stream channels to which it is tributary, even though the water may sink, evaporate, or be diverted before reaching said channels. If water from a spring flows in a natural surface channel before being diverted, the direct source should be designated as a stream and not a spring.
8. The point of diversion from the source is in..... San Juan..... County, situated at a point*
~~See Explanatory #1-S.1000 ft. and W. 150 ft.; #2-S.1000 ft. and W. 150 ft.; #3-S.1000 ft. and W. 750 ft.; #4-S.1000 ft. and W. 1050 ft.; #5-S.1000 ft. and W. 1350 ft.; #6-S.1000 ft. and W. 1650 ft.; #7-S.1000 ft. and W. 1950 ft.; #8-S.1000 ft. and W. 2250 ft.; #9-S.1000 ft. and W. 2550 ft.; and #10-S.1000 ft. and W. 2850 ft.; all from NE Cor. Sec. 5, T15S, R24E, SLB&M. (See letter of 7-16-61 att.)~~
- *Note.—The point of diversion must be located definitely by course and distance or by giving the distances north of south, and east or west with reference to a United States land survey corner or United States mineral monument, if within a distance of six miles of either, or if at a greater distance, to some prominent and permanent natural object. No application will be received for filing in which the point of diversion is not defined definitely.
9. The diverting and carrying works will consist of..... See Explanatory
10. If water is to be stored, give capacity of reservoir in acre-feet..... height of dam.....
area inundated in acres..... legal subdivision of area inundated.....
11. If application is for irrigation purposes, the legal subdivisions of the area irrigated are as follows:
.....
.....
..... Total..... Acres
12. Is the land owned by the applicant? Yes..... No.....
13. Is this water to be used supplementally with other water rights? Yes..... No.....
If "yes," identify other water rights under explanatory.
14. If application is for power purposes, describe type of plant, size and rated capacity.....
15. If application is for mining, the water will be used in Greater Aneth Area ~~XXXXXX~~
~~oil field~~ where the following ores are mined oil and gas
16. If application is for stockwatering purposes, number and kind of stock watered.....
17. If application is for domestic purposes, number of families to be served.....
18. If application is for municipal purposes, name of municipality.....
19. If application is for other uses, include general description of proposed uses.....
20. Give place of use by legal subdivision of the United States Land Survey for all uses described in paragraphs 14 to 19, incl..... See Explanatory
21. The use of water as set forth in this application will consume..... -- 8 -- second-feet of water
and -- 0 -- second feet will be returned to the natural stream or source at a point described as follows:

EXPLANATORY

The following additional facts are set forth in order to define more clearly the full purpose of the proposed application:

ITEM 7

The water will be pumped from the diversion area to the oil field where the water will be injected under pressure through deep wells into the petroleum-bearing formations for pressure maintenance and secondary recovery purposes.

ITEM 8

The point or points of diversion from the source will be in Section 5, T41S, R24E SIM, San Juan County, situated as follows: From that point at which the south bank of the river channel intersects the east line of Section 5, T41S, R24E, to that point at which the South bank of river channel intersects the North line of Section 5, T41S, R24E.

Diversion will be from one or more wells or infiltration galleries to be drilled in the alluvial fill and to be located as close to the South bank of the river channel as is practical within the east-west limits as above defined. Specific location and number of diversion points will be determined by a hydrographic survey and/or producing characteristics of wells to be drilled. The aggregate withdrawal, the rate of which is not to exceed that specified in this application, will be commingled in a conveyance works described in greater detail herein.

ITEM 9

The diverting and carrying works will consist of 12-1/4" diameter wells, cased with 35 to 50 feet of 8-5/8 inch outside diameter pipe to be drilled to depths of from 35 feet to 50 feet and about 13,000 feet of 10-3/4 inch conveyance pipe to places of use.

ITEM 20

Township 41 South, Range 23 East, SIM

S/2 Sec. 1; SE/4 Sec. 2; E/2 Sec. 11; All Sec. 12; All Sec. 13, E/2 Sec. 14, NE/4 Sec. 24.

Township 41 South, Range 24 East, SIM

All Sections 3, 4, 5, 6, 7, 8, 9, 10; W/2 Sec. 11, W/2 Sec. 14; All Sections 15, 16, 17, 18, 19, 20, 21; NW/4, W/2 SW/4 Sec. 22; W/2 NE/4, NE/4, W/2 SW/4 Sec. 28; All Sections 29, 30; N/2 Sec. 31; N/2 Sec. 32.

Said described lands, which are in San Juan County, Utah, constitute the Ratherford portion of the Greater Aneth Area oil field.

Continued on page 4

(Use page 4 if additional explanatory is needed.)

The quantity of water sought to be appropriated is limited to that which can be beneficially used for the purpose herein described.

PHILLIPS PETROLEUM COMPANY

By:

Signature of Applicant

VICE PRESIDENT OF PRODUCTION

*If applicant is a corporation or other organization, signature must be the name of such corporation or organization by its proper officer, or in the name of the partnership by one of the partners, and the names of the other partners shall be listed. If a corporation or partnership, the affidavit below need not be filled in. If there is more than one applicant, a power of attorney, authorizing one to act for all, should accompany the Application.

DECLARATION OF CITIZENSHIP

STATE OF UTAH, }
County of _____ } ss

On the _____ day of _____, 19____, personally appeared before me, a notary public for the State of Utah, the above-applicant who, on oath, declared that he is a citizen of the United States, or has declared his intention to become such a citizen.

My commission expires:

(SEAL)

Notary Public

FEES FOR APPLICATIONS TO APPROPRIATE WATER IN UTAH

Flow rate — c.f.s.

0.0	to	0.1	\$ 10.00
over	0.1	to	0.5 20.00
over	0.5	to	1.0 30.00
over	1.0	to	15.0 30.00 plus \$5/cfs above 1.00 cfs.
over	15.0		 100.00

Storage — acre-feet

	0	to	20	15.00
over	20	to	500	30.00
over	500	to	7500	30.00 plus \$5/500 a. f. above first 500
over	7500			100.00

(This section is not to be filled in by applicant)

STATE ENGINEER'S ENDORSEMENTS

1. Feb. 27, 1961 Application received by mail in State Engineer's office by
over counter
2. Priority of Application brought down to, on account of
3. Feb. 27, 1961 Application fee, \$ 5.50, received by Rec. No. 02265
4. Mar. 10, 1961 Application PHOTOSTATED in book 710.32 page 357, and indexed by E. T. ...
5. Mar. 10, 1961 Application platted by 11-2115-1001-2000 (2) 0001-2000 (4)
0001-2000 (6) 0001-2000 (7) 0001-2000 (8) 0001-2000 (9) 0001-2000 (10)
6. April 7, 1961 Application examined by ME
7. Application returned, or corrected by office
8. Corrected Application resubmitted over counter to State Engineer's office.
by mail
9. April 7, 1961 Application approved for advertisement by ME
10. June 16, 1961 Notice to water users prepared by R. K. H.
11. June 27, 1961 Publication began; was completed July 13, 1961
 Notice published in Salt Lake Record, Monticello, Utah
12. June 27, 1961 Proof slips checked by
13. Application protested by
14. July 25, 1961 Hearing held by
15. Field examination by
16. Sept. 11, 1961 Application designated for approval rejection
17. Sept. 11, 1961 Application copied or photostated by T.E. proofread by
18. Sept. 11, 1961 Application approved rejected
19. Conditions:
 This Application is approved, subject to prior rights, as follows:
 a. Actual construction work shall be diligently prosecuted to completion.
 b. Proof of Appropriation shall be submitted to the State Engineer's office by Feb. 28, 1963
 c.
20. Time for making Proof of Appropriation extended to
21. Proof of Appropriation submitted.
22. Certificate of Appropriation, No., issued

Wayne D. Criddle State Engineer.

Application No. 32773

EXPLANATORY CONTINUED

The use of the applied for water for the planned pressure maintenance and secondary recovery operations will permit the recovery of substantial quantities of oil and gas which would otherwise not be recovered.

NOTICE TO APPLICANT

All waters in this state, whether above or under the ground, are the property of the public, subject to all existing rights to the use thereof. No appropriation of the unappropriated public water may be made and no rights to the use thereof shall be recognized except Application for such appropriation first be made to the State Engineer.

The approval of this Application is not a Certificate of Appropriation. It is merely your authority to begin construction work, which must be prosecuted diligently to completion. To secure a Certificate of Appropriation under this Application, Proof of Appropriation must be submitted within the time limit allowed by the State Engineer. The amount of water for which Certificate will be issued will depend upon the amount of water actually put to a beneficial use, not to exceed, however, the amount of water specified in this Application. Proof of Appropriation must be made in accordance with the requirements of the law. For further information write the State Engineer.

*Review
Hawkins
file/SS*

October 13, 1961

AIRMAIL

Mr. Clair M. Senior
Senior & Senior
Attorneys at Law
10 Exchange Place
Salt Lake City, Utah

Re: Alternate or Additional Source of Water
for the Ratherford Unit, San Juan County, Utah

Dear Clair:

Herewith in triplicate is completed and signed application to the Utah State Engineer for additional and alternate points of diversion for water for water-flood purposes in the Ratherford Unit. I would appreciate it if you would handle this matter with the Water Engineer and, as diplomatically as possible, urge upon him the importance of expediting the matter as much as possible.

Having gotten these papers back from the Production Department too late to get a check for the filing fee, I would ask that you advance the fee and, upon being billed, I will send you the check.

If you need any additional information, please advise.

Very truly yours,

RMW:jd
Enclosures

R. M. Williams

cc - Mr. Shofner Smith ✓

2470497

Application for Permanent Change of Point of Diversion, Place and Nature of Use of Water STATE OF UTAH

Do not fill out this blank until you have read carefully and thoroughly understand the "Rules and Regulations" on the back hereof and all the notes in the body of it.

For the purpose of obtaining permission to permanently change the point of diversion, ~~place or nature of use of~~ (Strike out written matter not needed)

water right acquired by original Application No. 32773
(Give No. of Application, certificate of appropriation, title and date of Decree or other identification of right)
to that hereinafter described, application is hereby made to the State Engineer, based upon the following showing of facts, submitted in accordance with the requirements of the Laws of Utah.

1. The name of the applicant is Phillips Petroleum Company
2. The post-office address of the applicant is Bartlesville, Oklahoma
3. †The flow of water which ~~has been or~~ was to have been used in second-feet is 8
4. †The quantity of water which has been or was to have been used in acre-feet is XX
5. †The water ~~has been or~~ was to have been used each year from January 1 to December 31 incl.
(Month) (Day) (Month) (Day)
6. †The water has been or was to have been stored each year from XX to XX incl.
(Month) (Day) (Month) (Day)
7. The drainage area to which source of supply belongs is _____
(Leave blank)
8. The direct source of supply is Underground water and subsurface flow of San Juan River
in San Juan County.
9. †The point/s of diversion as described in the original Application ~~or the point at which the water has been diverted if~~ ^{are} situated at a point/s in Section 5, T. 41S., R. 24E as more particularly set out in the original Application No. 32773.

10. †The water involved ~~has been or~~ was to have been used for the following purposes:

Pressure maintenance and secondary recovery purposes

Total XX Acres.

NOTE—If for irrigation, give legal subdivision of land and total acreage which has been or was to have been irrigated. If for other purposes, give nature, place and extent of use or proposed use.

11. †The point at which water has been or was to have been returned to the stream channel is situated as follows: XX

NOTE—The above space is to be filled in only when all or part of the water is returned to the natural stream or channel.

The Following Changes Are Proposed

12. The flow of water to be changed in cubic feet per second is No change
13. The quantity of water to be changed in acre-feet is XX
14. The water will be used each year from January 1 to December 31 incl.
(Month) (Day) (Month) (Day)
15. The water will be stored each year from XX to XX incl.
(Month) (Day) (Month) (Day)
16. The point at which it is now proposed to divert the water is situated (See note) See explanatory

NOTE—The "point of diversion," or "point of return," must be located by course and distance or by rectangular distances with reference to some regularly established United States land corner or United States mineral monument if within a distance of six miles of either, or if a greater distance, to some prominent and permanent natural object.

17. The proposed diverting and conveying works will consist of wells and conveyance pipe as explained in original Application No. 32773

18. The cross-section of the diverting channel will be.



(Strike out ones not needed)

19. The nature of the diverting channel will be: earth, wood, iron, concrete.

(Strike out the ones not needed)

†Strike out written matter not needed.

Certified

December 2, 1965

Ratherford Unit, San Juan County, Utah -
Application No. 32773 - Request for Extension
of Time to Make Proof of Appropriation

Mr. R. M. Williams (2)
Legal Department

Phillips' Application No. 32773 to the State of Utah for appropriation of water to be used in the Ratherford Unit project was approved on September 5, 1961. One condition of the approval was that a proof of appropriation be submitted by February 28, 1963. Subsequently an extension was granted and the proof of appropriation is now due on February 28, 1966. It is not possible to determine at this time the quantity of water that will ultimately be required and this is to request your assistance in obtaining an additional extension of time before it is necessary to file the proof.

Attached is a copy of Mr. C. M. Boles' letter dated November 23, 1965, which transmits a copy of an unexecuted application for an extension of time for filing the proof from February 28, 1966, to February 28, 1971. Please examine the application as to form and, if it is acceptable, forward it to Mr. J. E. Chrisman, who will arrange for its execution. If it is your opinion that the legal firm of Senior and Senior should file the application, as was done previously, please so advise and the executed application will be returned to you.

Shofner Smith

JEC:gm
Attach.

cc: Messrs. C. W. Corbett
Attn. T. L. Osborne
C. M. Boles

12/8/65
HSC

11/11/65

2/10

Copied for
C. M. Boles
4-18-62 EFL:ml1

THE STATE OF UTAH
OFFICE OF THE STATE ENGINEER
SALT LAKE CITY

March 26, 1962

RECEIVED
APR 2 - 1962
PRODUCTION
DEPARTMENT

Phillips Petroleum Company
Bartlesville,
Oklahoma

Gentlemen:

RE: APPROVED APPLICATION NO. a-4025

Enclosed find Application No. a-4025 which has been approved by me. This approved Application is your authority to proceed with actual construction work which, under Sections 73-3-10 and 73-3-12, Utah Code Annotated 1953, as amended, must be diligently prosecuted to completion. The water shall be put to beneficial use and proof of appropriation filed with the State Engineer, as provided in the original application as amended by this approved change Application.

Failure on your part to comply with the requirements of the statutes may result in forfeiture of your Application.

Yours truly,

Wayne D. Criddle

Wayne D. Criddle

ADDRESS ALL COMMUNICATIONS TO:

STATE ENGINEER
403 STATE CAPITOL
SALT LAKE CITY, UTAH

js

Encl: Copy of approved application

CHANGE APPLICATION APPROVED

(Form for pending original Application)



Copied for
C. M. Boles
11-3-61 SS:ml1

THE STATE OF UTAH
OFFICE OF STATE ENGINEER

WAYNE D. CRIDDLE
STATE ENGINEER

SALT LAKE CITY
October 30, 1961

Issue Date: October 30, 1961
Expiration Date: April 30, 1962

Phillips Petroleum Company
c/o Senior and Senior, Attorneys
#10 Exchange Place
Salt Lake City 11, Utah

Gentlemen:

RE: APPROVED APPLICATION NO. 32773 AND
CHANGE APPLICATION NO. a-4025

This is to acknowledge receipt of your Permanent Change Application No. a-4025 which proposes to change the point of diversion of 8.0 sec.-ft. of water initiated by Application No. 32773. The water was to have been diverted from ten 12.75-inch O.D. wells located within $S\frac{1}{2}N\frac{1}{2}NE\frac{1}{4}$ and $SE\frac{1}{4}NE\frac{1}{4}NW\frac{1}{4}$ of Sec. 5, T41S, R24E, SLB&M. It is now proposed to divert the 8.0 sec.-ft. of water from a total of one well 12.75 inches O.D., between 35 and 50 ft. deep, ten of these being the same as heretofore described and thirty-one wells to be located within $NW\frac{1}{4}$ Sec. 3, $R\frac{1}{2}$ Sec. 4, $NW\frac{1}{4}$ Sec. 5, T41S, R24E, SLB&M. The water is to be used for pressure maintenance and secondary recovery purposes as heretofore.

You have requested permission to proceed immediately with the drilling of these additional 31 wells. This letter grants you that privilege with the understanding that all risks as regards water rights are being assumed by you.

If other than new standard casing is to be used in these wells, such casing must be inspected and approved by a representative from this office. All wells must be so constructed and finished that they may be readily controlled at all times, in order to prevent waste of underground water. Wells must be drilled and cased in such a manner that will prevent the infiltration of contaminated water into them.

The driller must be bonded and have a current permit from the State Engineer. Before commencing, he must give this office notice as to the day he will begin drilling. Also, within 30 days after the well has been completed or abandoned, he must file a well driller's report for each well. These reports are to contain accurate and complete information regarding the work done and become part of the files in this office pertaining to the above-numbered filings.

This is permission for a licensed driller to begin drilling your wells.

Please note that the expiration date of this letter is April 30, 1962.

Yours truly,

Wayne D. Criddle
Wayne D. Criddle
STATE ENGINEER

RECEIVED

OCT 31 1961


SENIOR AND SENIOR

ds



THE STATE OF UTAH
OFFICE OF STATE ENGINEER
SALT LAKE CITY

September 11, 1961



Phillips Petroleum Company
Bartlesville,
Oklahoma

Gentlemen:

RE: APPROVED APPLICATION NO. 32773

Enclosed find Approved Application No. 32773. This is your authority to proceed with actual construction work which, under Sections 73-3-10 and 73-3-12, Utah Code Annotated, 1953, as amended, must be diligently prosecuted to completion. The water shall be put to beneficial use and proof of appropriation made to the State Engineer on or before ~~February 28, 1961~~ otherwise the application will lapse.

Failure on your part to comply with the requirements of the statutes may result in forfeiture of this application.

Yours truly,

Wayne D. Criddle

Wayne D. Criddle
STATE ENGINEER
STATE CAPITOL BUILDING
SALT LAKE CITY, UTAH

js

Encl: Copy of approved application

APPLICATION APPROVED

NOTICE TO APPLICANT

The approval of this Application is not a certificate of change. It is merely your authority to begin construction work, which must be diligently prosecuted to completion. To secure a certificate of change under this Application proof of change must be submitted within the time limit allowed by the State Engineer. The amount of water for which certificate will be issued will depend upon the amount of water actually put to a beneficial use, not to exceed, however, the amount of water covered by the original right. For further information write the State Engineer.

RULES AND REGULATIONS

Applicants will save time and expense by familiarizing themselves with the law before making Applications.

If the reservoir is to be located on the channel of the source from which the water is to be appropriated, it should be so stated under explanatory, and—

1. The location of the impounding dam should be described in Paragraph 16.
2. The point where the released storage will be rediverted from the natural stream should be described under explanatory in accordance with the note under Paragraph 16.

When the water is to be stored in other than the natural channel of the source from which it is to be appropriated, it should be so stated under explanatory, and—

1. The point of diversion from the supplying source should be described in Paragraph 16.
2. The intersection of the longitudinal axis of impounding dam and centerline of stream channel or drainage and a similar point where the released storage will be rediverted from a natural channel should be described under explanatory in accordance with the note under Paragraph 16.

In all cases Paragraphs 17 to 27, incl., should describe the proposed diverting and carrying works, exclusive of natural channels, even if already constructed in whole or in part.

If it is proposed to collect the water of a number of springs or other sources at a common point, said point should be described as the point of collection in Paragraph 16, and the point of diversion from each source should also be described under explanatory in accordance with the note in Paragraph 16. The quantity of water sought from each source should be indicated under explanatory, the total equaling the quantity specified in Paragraphs 12 or 13. Where the source of supply is in reality a spring area, the point of diversion is the point where the water is collected; in such case the exterior boundary of the spring area must be described under explanatory by metes and bounds and located with reference to the same point as used in describing the point of collection and as outlined by the note under Paragraph 16.

No enlargement of an original water right may be made by a change Application, either as to quantity of water covered, period of use or otherwise.

When there are two or more coapplicants the Application must be accompanied by a power of attorney.

The applicant's permanent address should be given in Paragraph 2, and the State Engineer notified promptly of any change in address; otherwise applicant may lose rights initiated by Application by failing to receive notices sent from the State Engineer's office.

No Application or other paper pertaining to an Application will be marked received unless accompanied with the required filing fee.

Applications accepted and numbered by the State Engineer, when returned to applicant for correction or additions, must be amended with red ink. Erasures must not be made, but any matter may be eliminated by running a red line through it. Corrected Applications must be resubmitted to the State Engineer's office, within sixty days from the date of State Engineer's letter returning Application for correction; otherwise the priority of the right to change will be brought down to date corrected Application is resubmitted.

Applicants will be informed by the State Engineer's office when cost of publishing notice of Application is due, and must advance cost within sixty days after date of notice, otherwise Application will lapse.

Fees Required by Law Payable to State Engineer

For examining and filing Applications for change of point of diversion, place and nature of use.....	\$2.50
For approving and recording Applications for change of point of diversion, place and nature of use.....	\$2.50
For filing written proof of change.....	\$1.00
For examining maps, profiles and drawings that are part of the proof of change.....	\$5.00
For issuing certificate of change.....	\$1.00

NOTE—In addition to the above fees applicants must pay the cost of publication of "Notice to Water Users" concerning the proposed change.

20. The length of the diverting channel, exclusive of laterals, will be 15,000 feet
(If an existing channel is used give only the length of that part used under this Application)
21. The top width of the diverting channel will be (if a ditch) XX feet
22. The bottom width of the diverting channel will be (if a ditch) XX feet
23. The depth of water in the diverting channel will be (if a ditch) XX feet
24. The width of diverting channel will be (if a flume) XX feet
25. The depth of water in the diverting channel will be (if a flume) XX feet
26. The diameter of the diverting channel will be (if a pipe) 62.75 inches C.D. inches
27. The grade of the diverting channel will be 21.4 feet per thousand
28. The point at which it is proposed to return the water is situated (See note under 16) _____

29. The water is to be used.....for the same purposes as specified in the
original Application No. 32773

Total.....XX.....ACTES.

NOTE—If for irrigation, give legal subdivisions of land to be irrigated. If for other purposes, give place and extent of proposed use. If for power give number, size and make of wheels, head under which they will operate, total H. P. to be developed and place where power will be used.

30. The character of the soil to be irrigated is.....XX.....; subsoil.....XX.....

NOTE—Number 30 is to be filled in only when proposed change is for irrigation.

31. If paragraph 12 designates that only part of the right described in paragraph 1 to 11 inclusive is to be changed, designate the status of the water so affected by this change as to its being abandoned or used as heretofore.

EXPLANATORY

NOTE—Paragraph 13 on page 1 must not be used except when storage is contemplated; in such case Paragraph 14 should indicate the time in each year during which the water will be released and used. The lands to be inundated by the reservoir must be described in the space below this note as nearly as may be and by government subdivisions if upon surveyed land, and the area of the reservoir when at full stage should be given in acres; the height of the impounding dam must also be specified.

The following additional facts are set forth in order to define more clearly the full purpose of the proposed change:

The original Application No. 32773 specified _____ points of diversion situate in Section 5, T. 41S., R. 24E., San Juan County, Utah, and bears the following notation: "Diversion will be from one or more or all of the above diversion points. Water from the several diversion points will be commingled in conveyance works or in use. The applicant proposes to divert water from the San Juan River partly or wholly by means of infiltration wells, pits or horizontal galleries, dug in the alluvial fill within the stream valley. The exact number, depth, diameter, spacing and yield of such wells, pits or galleries will be determined during the project construction; however, the aggregate withdrawal rate will not exceed that specified." The purpose of this Change Application is to secure approval of additional alternative points of diversion as hereinafter specified without waiver of any rights under the original Application and without increase in the quantity of water applied for or the ultimate objective and purpose of the original Application.

See "Explanatory" continued on attached sheet.

PHILLIPS PETROLEUM COMPANY

.....
Signature of Applicant.

BY Vice-President of Production

EXPLANATORY - contd. from printed form.

The additional alternative points of diversion from the source are in Section 3, T. 41S., R. 24E., San Juan County, Utah, situate at points as follows:

<u>Diversion Point</u>	<u>From West Line</u>	<u>From North Line</u>	<u>Subdivision</u>
1	100'	1780'	SW $\frac{1}{2}$ NW $\frac{1}{4}$
2	365'	1780'	"
3	630'	1770'	"
4	900'	1620'	"
5	1170'	1620'	"
6	1400'	1600'	SE $\frac{1}{2}$ NW $\frac{1}{4}$
7	1530'	1600'	"
8	1900'	1600'	"
9	2150'	1620'	"
10	2400'	1700'	"
11	2640'	1750'	"
12	2900'	1810'	SW $\frac{1}{2}$ NE $\frac{1}{4}$
13	3180'	1900'	"
14	3400'	1950'	"
15	3650'	2050'	"
16	3870'	2225'	"
17	4100'	2450'	SE $\frac{1}{2}$ NE $\frac{1}{4}$
18	4250'	2700'	NE $\frac{1}{2}$ SE $\frac{1}{4}$
19	4380'	2975'	"
20	4420'	3250'	"

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK

DRILL ☒DEEPEN ☐PLUG BACK ☐

b. TYPE OF WELL

OIL
WELL ☒GAS
WELL ☐

OTHER

SINGLE
ZONE ☐MULTIPLE
ZONE ☐

2. NAME OF OPERATOR

Phillips Petroleum Company

3. ADDRESS OF OPERATOR

P.O. Box 2920, Casper, Wyoming 82602

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.*)

At surface

1860' FSL, 1820' FEL (NW, SE) ✓

At proposed prod. zone

Same

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

Approximately 6 miles south of Montezuma Creek, Utah

15. DISTANCE FROM PROPOSED* 1820' West of Rather-
LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT. ford Unit lease line
(Also to nearest drig. unit line, if any)18. DISTANCE FROM PROPOSED LOCATION*
TO NEAREST WELL, DRILLING, COMPLETED, 1080' north
OR APPLIED FOR, ON THIS LEASE, FT. of #29-3416. NO. OF ACRES IN LEASE
1904 Acres

19. PROPOSED DEPTH

5700' *Desert Creek*17. NO. OF ACRES ASSIGNED
TO THIS WELL

40 acres

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

4902' ungraded ground

22. APPROX. DATE WORK WILL START*

Sept. 1983

23.

PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	QUANTITY OF CEMENT
17 1/2"	13 3/8"	48#	100'	150 sx Class B (to surface)
12 1/4"	9 5/8"	36#	1600'	400 sx HLC- & 400 sx Class B (sur- face)
8 1/2"	7"	20#, 23#, & 26#	5700' ✓ 1,	000 sx est T.O.C. approx 2000 ft.)

Approval is requested to drill Ratherford Unit #29-33, a ✓ Desert Creek Development oil well,
to increase the ultimate recovery from the Ratherford Unit.

BOP equipment will be operated daily and tested weekly.

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING
DATE: 8/31/83
BY: [Signature]

RECEIVED
SEP 03 1983
DIVISION OF
OIL, GAS & MINING

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM. If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED

A. E. Stuart

TITLE

Area Manager

DATE August 31, 1983

(This space for Federal or State office use)

PERMIT NO.

APPROVAL DATE

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

5-BLM, Farmington, N.M.

2-Utah O&G CC-S.L.C., Utah ✓

1-J.L. Whitmire (r) T.C. Doughty

1-G.W. Berk

1-T.M. Isaacs

*See Instructions On Reverse Side

Form 9-331C & Location Plat only - Barbara Conner

Form 9-331C & Location Plat only- R. M. Coffelt


COMPANY PHILLIPS PETROLEUM COMPANY

LEASE RATHERFORD UNIT WELL NO. 29-33

SEC. 29, T. 41S, R. 24E
SAN JUAN COUNTY, UTAH

LOCATION 1860' FSL 1820' FEL


ELEVATION 4902 ungraded ground



SCALE—4 INCHES EQUALS 1 MILE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM
FIELD NOTE OF ACTUAL SURVEYS MADE BY ME UNDER MY SUPER-
VISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE
BEST OF MY KNOWLEDGE AND BELIEF.

SEAL:



SURVEYED August 8, 1983




Figure 7-10. Standard Hydraulic Blowout Preventer Assembly
(2 M or 3 M Working Pressure) Alternative 3 (without Drilling Spool)

Well Control 4
January/83

PHILLIPS PETROLEUM COMPANY



Page 251
Section II

BLOWOUT PREVENTER TESTING PROCEDURE

A. INITIAL INSTALLATION TEST FOR INSTALLATIONS AS SHOWN ON FIGURE NO. 7 - TWO RAM UNITS

After all blowout preventers, regular choke lines, valves, bell nipples, and flow lines are rigged up, the following steps are to be carried out with no exceptions: (Emergency choke and kill lines are not to be connected below the bottom preventer at this time.)

Preparations
for Test
Steps 1-9.

1. Inspect all flanges to see if all bolts are in place and tight.
2. Check all opening and closing lines to preventers to see if they are correctly placed, hooked up, and tight.
3. Check to see that all control valves are properly marked.
4. Open bradenhead valves and wash inside of preventers with water from the top. No lines are to be connected to the bradenhead at this time.
5. Connect water into suction of mud pump and pump water through kill line and out bradenhead valves until water clears up.
6. Connect test line in place of kill line.

A. INITIAL INSTALLATION TEST FOR INSTALLATIONS AS SHOWN ON FIGURE NO. 7
TWO RAM UNITS (Contd.)

7. Connect kill line to one bradenhead valve and open valve.
8. Close other bradenhead valve.
9. Fill preventers with water.
10. Close blind rams with 1,500 psi.
11. Check closing line and preventer for leaks.
12. Pressure up casing with mud pump to pressure required to test casing using water. Hold for 10 minutes.
13. Check bradenhead, bradenhead valve flanges, and blind rams for leaks.
14. Install a pressure gauge on the bradenhead valve opposite where the kill line is tied on.
15. Open bradenhead valve to read casing pressure.
16. Close bradenhead valve on side where kill line is tied on.
17. Release pressure on kill line.
18. Disconnect kill line from bradenhead valve.
19. Check bradenhead valve for leaks on the side where the kill line was disconnected. See that casing pressure has not dropped below the required test pressure.
20. Remove pressure gauge and bleed down casing.
21. Close bradenhead valve(s).
22. Open blind rams with 1,500 psi.
23. Check opening line and preventer for leaks.
24. Disconnect kill line from bradenhead valve and open both bradenhead valves.
25. Run test plug in on a joint of drill pipe, set in seat.

NOTE: Test plug to be fabricated so that there will be enough clearance between plug and pipe rams to clear tool joint when closed on joint of drill pipe made up in plug. The plug must be drilled so there is communication between inside of drill pipe and top of plug above seal surface.

Casing
Blind Ram
and Braden-
head Test
Steps 10-24

BOP Stack
and Choke
Line Test
Steps 25-38

A. INITIAL INSTALLATION TEST FOR INSTALLATIONS AS SHOWN ON FIGURE NO. 7
TWO RAM UNITS (Contd.)

26. Install safety valve and kelly on top of drill pipe.
27. Fill preventers with water.
28. Open all valves on choke lines and check to see that water is flowing through each outlet. Let run until clear. Open valves on kill line side of spool.
29. Close outside valves on choke lines making sure they are full of water and have no trapped air.
30. Refill preventers if necessary.
31. If Hydril is used in place of upper ram type preventer, close 1" plug valve on closing line. Test to 1,500 psi. Inspect valve for leaks. Release pressure. Open valve.
32. Close pipe rams or Hydril with 1,500 psi.
33. Check closing line and preventer for leaks.
34. Open stand pipe valve, kelly cock, and safety valve, and fill kelly with water.
35. Close kelly cock.
36. If Hydril is used, reduce closing pressure to that recommended on page 56. Closing pressure may be increased as required to effect a seal up to a maximum of 1,500 psi.
37. Pressure up to working pressure of preventers through test line. For maximum Hydril packing unit life, as the test pressure builds up, reduce the closing pressure and later apply opening pressure per applicable schedule starting on page 57, provided a schedule is listed for the Hydril in use. Hold test pressure for 10 minutes.
38. Check all valves, flanges, and seals that are under pressure for leaks and tighten if necessary. Check test plug for leak.
39. Close second valve from hole on choke line. Open outside valve on full opening line. Hold pressure for one minute.
40. Check to see if valve leaks.
41. Close inside valve on choke line. Open second valve out on choke line. Hold pressure for one minute.
42. Check to see if valve leaks.

Choke and
Kill Valve
Tests
Steps 39-55

A. INITIAL INSTALLATION TEST FOR INSTALLATIONS AS SHOWN ON FIGURE NO. 7
TWO RAM UNITS (Contd.)

43. Close safety valve and open kelly cock.
44. Check safety valve for leaks.
45. Close inside valve on kill line side. Open inside valve on choke line side. Hold pressure for one minute.
46. Check to see if valve leaks.
47. Close second valve out on kill line. Open inside valve on kill line. Hold pressure for one minute.
48. Check to see if valve leaks.
49. Open second valve out on kill line. Close inside valves on kill line and choke line.
50. Disconnect test line; connect kill line.
51. Open pipe rams (or Hydril) with 1,500 psi.
52. Check opening line and preventer for leaks.
53. Pull plug out of hole.
54. Close bradenhead valves.
55. Record test on drilling report.

B. RAM CHANGE TEST FOR INSTALLATIONS AS SHOWN ON FIGURE NO. 7 OR 8 -
TWO RAM UNITS

If Hydril is used in place of upper ram type preventer, ram change test is not required since no change will be made in preventer assembly to run casing.

Preparations
Steps 1-2

1. After getting out of hole, open choke line valves and drain mud out of preventers. No lines are to be connected to Figure 7 bradenhead valves at this time.

2. Wash inside of preventers from top with water.

Ram Change
Steps 3-9

3. Close blind rams.
4. Open bonnets or doors on upper ram type preventer.
5. Remove drill pipe rams.
6. Install rams to fit casing.

B. RAM CHANGE TEST FOR INSTALLATIONS AS SHOWN ON FIGURE NO. 7 OR 8 -
TWO RAM UNITS (contd.)

7. Close bonnets or doors, checking all seals and "O" rings.
8. Tighten up all bolts and inspect preventer to see that bonnets or doors are closed, steel to steel.
9. Open blind rams.

Casing Ram Test
Steps 10-22

10. Install test plug and test line on extra joint of casing the same size that is to be run. Casing joint used must be of sufficient strength to withstand test pressures. The crossover connections used to get from casing joint to test plug must be short enough to permit the casing rams to close against casing.
11. Set test plug in casing spool.
12. Fill preventers with water.
13. Close casing rams.
14. Purge air from casing joint.
15. Pressure up through casing joint to working pressure of preventers. Hold for 10 minutes.
16. Check for leaks in all flanges and seals that hold pressure, especially bonnet or door seals on preventer changed.
17. Release pressure.
18. Open casing rams.
19. Pull test plug out of hole.
20. Close choke line valve.
21. Change sign on valve on blowout preventer closing manifold that controls casing rams to indicate casing rams instead of drill pipe rams.
22. Record test and ram changes in drilling report.

C. WEEKLY TEST PROCEDURE FOR INSTALLATIONS AS SHOWN ON FIGURE 7 - TWO
RAM UNITS

Preparations
for Test
Steps 1-10

1. Inspect all flanges to see if all bolts are in place and tight.
2. Check all opening and closing lines to preventers to see if they are correctly placed, hooked up, and tight.

C. WEEKLY TEST PROCEDURE FOR INSTALLATIONS AS SHOWN ON FIGURE 7 - TWO
RAM UNITS (contd.)

3. Remove kill line and install test line in flange outside of second valve on the kill line side of the drilling spool.
4. Open valves on bradenhead and wash inside of preventers with water from the top. No lines are to be connected to the bradenhead at this time.
5. Run test plug in on a joint of drill pipe and set in seat.
6. Install safety valve and kelly on top of drill pipe.
7. Fill preventers with water.
8. Open all valves on choke lines and check to see that water is flowing through each choke line and full opening line. Let run until it clears up.
9. Close all outside valves on choke line, making sure they are full of water and do not have air trapped in them.
10. Refill preventers if necessary.
11. Close pipe rams (or Hydril, if used in place of upper ram type preventer).
12. Check closing line and preventer for leaks.
13. Open stand pipe valve, kelly cock, and safety valve, and fill kelly with water.
14. Close kelly cock.
15. If Hydril is used, reduce closing pressure to that listed on page 56. This may be increased as required up to a maximum of 1,500 psi.
16. Pressure up to 1/2 working pressure of preventers. For maximum Hydril packing unit life, as the test pressure builds up, reduce the closing pressure and later apply opening pressure per applicable schedule starting on page 57, provided a schedule is listed for the Hydril in use. Hold test pressure for 10 minutes.
17. Check for leaks.
18. Close safety valve and open kelly cock.
19. Check safety valve for leaks.

BOP Stack and
Kelly Cock Test
Steps 11-17

Safety Valve
Test
Steps 18-24

C. WEEKLY TEST PROCEDURE FOR INSTALLATIONS AS SHOWN ON FIGURE 7 -
RAM UNITS (Contd.)

20. Release pressure.
21. Open pipe rams (or Hydril)
22. Pull plug out of hole.
23. Close bradenhead valves.
24. Record test on drilling report.

BLOWOUT PREVENTER TESTING PROCEDURE

A. INITIAL INSTALLATION TEST FOR INSTALLATIONS AS SHOWN ON FIGURE NO. 8
TWO RAM UNITS - LOW SUBSTRUCTURE

After all blowout preventers, choke lines, valves, bell nipples, and flow lines are rigged up, the following steps are to be carried out with no exceptions:

1. Inspect all flanges to see if all bolts are in place and tight.
2. Check all opening and closing lines to preventers to see if they are correctly placed, hooked up, and tight.
3. Check to see that all control valves are properly marked.
4. Remove kill line and open all valves on bradenhead.
5. Open all valves on choke manifold and wash inside of preventers with water from the top. Check to see that water is flowing through each choke line and kill line.
6. Close outside valves on kill line side and on choke lines.
7. Install test line in flange on outside of second valve on kill line side of bradenhead.
8. Fill preventers.
9. Open outside valve on kill line side and pump through test line until all air is purged.
10. Close inside valve on kill line side.
11. Pressure up to working pressure of preventers. Hold for one minute.
12. Check for leaks.

Preparations
Steps 1-10

Kill Line
Outlet
Valves
Test
Steps 10-16

RU 1-B



FORM 31-B

STATE OF UTAH

DEPARTMENT OF NATURAL RESOURCES

DIVISION OF WATER RIGHTS

DEE C. HANSEN
STATE ENGINEER

JOHN BENE
DEPUTY

442 STATE CAPITOL
SALT LAKE CITY, UTAH 84114

(801) 328-6071

May 28, 1974

DIRECTING ENGINEERS
HAROLD D. DONALDSON
DONALD C. NORSETH
~~XXXXXXXXXXXX~~
Stanley Green

Phillips sent w. s. w. c.

Phillips Petroleum Company
Box 2920
Casper, Wyoming 82601

Gentlemen:

RE: Change Appl. No. a-7804 (09-281)

Enclosed is Change Application No. a-7804 (09-281) which has been approved. The approved change application is amendatory and serves only to affect a correction to Application No. 32773 a-4025 on which an election to file a water user's claim has been submitted.

As soon as possible, engineers of this office will make the necessary field investigations and will prepare a water user's claim which will be entered in the adjudication of water rights in your area.

Yours truly,

Dee C. Hansen
State Engineer

jb

Enc.: Copy of Approved Application

CHANGE APPLICATION APPROVED

(Form for Pending Original Application)

PHILLIPS PETROLEUM CO. CASPER AREA E & P DEPT.		
Recd: JUN 3 1974		
Send to	DATE	INIT.
Supr.		
Super. Supr.		
Dist. Engr.		
Dist. Asst.		
Engr.		
Supr. Asst.		
Secy		
Copy		
to		

Quinn Eade 09-2-81

Application for Permanent Change of Point of Diversion

Place and Nature of Use of Water

STATE OF UTAH

Please clearly and correctly complete the information requested below which defines the right or rights being changed. (Type or clearly print.)

For the purpose of obtaining permission to permanently change: the point of diversion ☒, place ☐, or nature of use ☐, of water rights acquired by Application No. 32773 (09-281)
(Give Number of Application, certificate of appropriation, title and date of Decree or other identification of right.)

If the right described has been amended by a previous approved change application, give the number of such change application. No. a-4025

- The name of the applicant is Phillips Petroleum Company
- The post-office address of the applicant is Box 2920, Casper, Wyoming 82601
- The flow of water which has been or was to have been used in second-feet is 8.0
- The quantity of water which has been or was to have been used in acre-feet is _____
- The water has been or was to have been used for and during periods as follows:

Oil Field Pressure Maintenance and	from _____	to _____	incl.
(purpose)	(month) (day)	(month) (day)	
Secondary Recovery Uses	from <u>January 1</u>	to <u>December 31</u>	incl.
(purpose)	(month) (day)	(month) (day)	
and stored each year (if stored)	from _____	to _____	incl.
	(month) (day)	(month) (day)	
- The direct source of supply is 41 Wells in San Juan County.
(well, spring, stream, drain, river; if other explain)
- The point or points of diversion See Separate Sheet

(Must be the same as that of right being changed unless a previous change has been filed and approved. Then use the point or points approved in the previous change.)

8. Diversion works:

If a well give diameter and depth 12 3/4" diameter wells, 35-50 ft. deep

If a dam and reservoir give height, capacity, and area inundated _____

If other give type of diversion facility _____

- The water involved has been or was to have been used for the following purposes in the following described legal subdivisions: (If used for irrigation, state sole or supplemental supply, and describe other supplemental rights.)

Irrigation _____

Total acres to be irrigated _____

Stockwatering (number and kind) _____

Domestic (number of families and/or persons, etc.) _____

Other See Separate Sheet

- The point at which water has been or was to have been returned to the stream channel is situated as follows: (Please describe method of return.) _____

Note: Paragraph 10 is to be completed only when all or part of the water is returned to the natural stream or channel.

The Following Changes Are Proposed

- The flow of water to be changed in cubic feet per second is Same as heretofore
- The quantity of water to be changed in acre-feet is _____

4

13. The water will be used each year for:

Same as heretofore

from to incl.
(purpose) (month) (day) (month) (day)

from to incl.
(purpose) (month) (day) (month) (day)

and stored each year (if stored) from to incl.
(month) (day) (month) (day)

14. It is now proposed to divert the water from 23 Wells
(i.e., spring, spring area, stream, river, drain, well, etc.)

at a point(s) as follows: See Separate Sheet

NOTE: The "point of diversion," or "point of return," must be located by course and distance or by rectangular distances with reference to some regularly established United States land corner or United States mineral monument if within a distance of six miles of either, or if a greater distance to some prominent and permanent natural object. A spring area must also be described by metes and bounds.

15. The proposed diverting and conveying works will consist of: (if a well, state diameter and depth thereof)
20 - 16-inch diameter wells, 35-50 ft. deep

16. If water is to be stored, give capacity of reservoir in acre-feet height of dam
area inundated in acres legal subdivisions of area inundated

17. The water is to be used for the following purposes in the following described legal subdivisions: (if used for irrigation, state sole or supplemental supply, and describe other supplemental rights.)

Irrigation

..... Total acres to be irrigated

but limited to the sole irrigation supply of acres.

Stockwatering (number and kind)


Domestic (number of families and/or persons, etc.)

Other Same as heretofore

18. If paragraphs 11 and 12 designate that only part of the right described in paragraphs 1 to 10 inclusive is to be changed, designate the status of the water so affected by this change as to its being abandoned or used as heretofore.

EXPLANATORY

The following additional facts are set forth in order to define more clearly and completely the full purpose of the proposed change: This is an Amendatory Change Application filed to
correct the location of the points of diversion.



The undersigned hereby acknowledges that even though he may have been assisted in the preparation of the above-numbered application through the courtesy of the employees of the State Engineer's Office, all responsibility for the accuracy of the information contained therein, at the time of filing, rests with the applicant.

Forest E. Morgan
Signature of Applicant

Item 7 - Points of Diversion

Well No.	Point of Diversion	Well No.	Well Location
1	S. 1000 ft. & W. 150 ft.	22	S. 1550 ft. & E. 1850 ft.
2	S. 1000 ft. & W. 450 ft.	all from NW	Cor. Sec. 3, T41S, R24E.
3	S. 1000 ft. & W. 750 ft.	23	S. 960 ft. & E. 150 ft.
4	S. 1000 ft. & W. 1050 ft.	24	S. 950 ft. & E. 450 ft.
5	S. 1000 ft. & W. 1350 ft.	25	S. 925 ft. & E. 750 ft.
6	S. 1000 ft. & W. 1650 ft.	26	S. 910 ft. & E. 1050 ft.
7	S. 1000 ft. & W. 1950 ft.	27	S. 900 ft. & E. 1350 ft.
8	S. 1000 ft. & W. 2250 ft.	28	S. 890 ft. & E. 1650 ft.
9	S. 1000 ft. & W. 2550 ft.	29	S. 850 ft. & E. 1950 ft.
10	S. 1000 ft. & W. 2850 ft.	30	S. 825 ft. & E. 2250 ft.
11	S. 900 ft. & W. 3125 ft.	31	S. 895 ft. & E. 2540 ft.
12	S. 800 ft. & W. 3400 ft.	32	S. 1000 ft. & E. 2795 ft. DELETE FC
13	S. 700 ft. & W. 3700 ft.	33	S. 1210 ft. & E. 3000 ft.
14	S. 610 ft. & W. 3995 ft.	34	S. 1420 ft. & E. 3200 ft.
15	S. 500 ft. & W. 4280 ft.	35	S. 1620 ft. & E. 3410 ft.
all from NE	Cor. Sec. 5, T41S, R24E	36	S. 1710 ft. & E. 3710 ft.
16	S. 1700 ft. & E. 50 ft.	37	S. 1760 ft. & E. 4000 ft.
17	S. 1675 ft. & E. 350 ft.	38	S. 1800 ft. & E. 4300 ft.
18	S. 1650 ft. & E. 650 ft.	39	S. 1780 ft. & E. 4600 ft.
19	S. 1610 ft. & E. 950 ft.	40	S. 1740 ft. & E. 4900 ft.
20	S. 1590 ft. & E. 1250 ft.	41	S. 1720 ft. & E. 5200 ft.
21	S. 1575 ft. & E. 1550 ft.	all from NW	Cor. Sec. 4, T41S, R24E.

Item 9 - Place of Use: Ratherford Unit Greater Aneth Oil Field; S $\frac{1}{2}$ Sec. 1; SE $\frac{1}{4}$ Sec. 2; E $\frac{1}{2}$ Sec. 11; Sec. 12; Sec. 13; E $\frac{1}{2}$ Sec. 14; NE $\frac{1}{4}$ Sec. 24, T41S, R23E, SLB&M. Secs. 3-10; W $\frac{1}{2}$ Sec. 11; W $\frac{1}{2}$ Sec. 14; Secs. 15-21; NW $\frac{1}{2}$ & W $\frac{1}{2}$ SW $\frac{1}{4}$ Sec. 22; W $\frac{1}{2}$ NE $\frac{1}{2}$, NW $\frac{1}{2}$, W $\frac{1}{2}$ SW $\frac{1}{4}$ Sec. 28; Secs. 29-30; N $\frac{1}{2}$ Sec. 31; N $\frac{1}{2}$ Sec. 32, T41S, R24E, SLB&M.


Item 14 - New Points of Diversion

Well No.

1	S. 950 ft. & W. 148 ft. from NE Cor. Sec. 5, T41S, R24E, SLB&M. (D-41-24) 5aad
2	S. 1014 ft. & W. 442 ft. from NE Cor. Sec. 5, T41S, R24E, SLB&M. (D-41-24) 5aad
3	S. 1007 ft. & W. 741 ft. from NE Cor. Sec. 5, T41S, R24E, SLB&M. (D-41-24) 5aac
4	S. 1010 ft. & W. 592 ft. from NE Cor. Sec. 5, T41S, R24E, SLB&M. (D-41-24) 5aad
5	S. 982 ft. & W. 294 ft. from NE Cor. Sec. 5, T41S, R24E, SLB&M. (D-41-24) 5aad
6	S. 887 ft. & W. 2 ft. from NE Cor. Sec. 5, T41S, R24E, SLB&M. (D-41-24) 5aad
7	S. 863 ft. & E. 145 ft. from NW Cor. Sec. 4, T41S, R24E, SLB&M. (D-41-24) 5aad
8	S. 843 ft. & E. 293 ft. from NW Cor. Sec. 4, T41S, R24E, SLB&M. (D-41-24) 5aad
9	S. 818 ft. & E. 440 ft. from NW Cor. Sec. 4, T41S, R24E, SLB&M. (D-41-24) 5aad
10	S. 803 ft. & E. 590 ft. from NW Cor. Sec. 4, T41S, R24E, SLB&M. (D-41-24) 5aad
11	S. 789 ft. & E. 739 ft. from NW Cor. Sec. 4, T41S, R24E, SLB&M. (D-41-24) 5aac
12	S. 777 ft. & E. 939 ft. from NW Cor. Sec. 4, T41S, R24E, SLB&M. DELETE FC
13	S. 803 ft. & E. 1137 ft. from NW Cor. Sec. 4, T41S, R24E, SLB&M. (D-41-24) 5
14	S. 802 ft. & E. 1334 ft. from NW Cor. Sec. 4, T41S, R24E, SLB&M.
15	S. 759 ft. & E. 1529 ft. from NW Cor. Sec. 4, T41S, R24E, SLB&M.
16	S. 715 ft. & E. 1725 ft. from NW Cor. Sec. 4, T41S, R24E, SLB&M.
17	S. 672 ft. & E. 1920 ft. from NW Cor. Sec. 4, T41S, R24E, SLB&M.
18	NO WELL
19	S. 1792 ft. & W. 352 ft. from NE Cor. Sec. 4, T41S, R24E, SLB&M.
20	S. 1792 ft. & W. 952 ft. from NE Cor. Sec. 4, T41S, R24E, SLB&M.
21	NO WELL
22	S. 1792 ft. & W. 652 ft. from NE Cor. Sec. 4, T41S, R24E, SLB&M.
23	S. 1714 ft. & W. 1545 ft. from NE Cor. Sec. 4, T41S, R24E, SLB&M.

(This page not to be filled in by applicant)

STATE ENGINEER'S ENDORSEMENT



1. MAR. 8, 1974 Change Application received over counter by mail in State Engineer's office by WCK
2. _____ Priority of right to make change brought down to, on account of _____
3. MAR 2, 1974 Fee for filing Application \$ 65.00, received by WCK, Receipt No. 20906
4. MARCH 18, 1974 Application microfilmed by _____ Roll No. 709 and indexed by WCK
5. 4/16/74 Application platted by WCK See following page for location
6. MAR. 8, 1974 Application examined by WCK
7. _____ Application returned, with letter, to _____ for correction
8. _____ Corrected application resubmitted over counter by mail to State Engineer's Office
9. MAR 8, 1974 Application approved for advertisement by WCK
10. MAR 28 1974 Notice to water users prepared by dph & SL
11. APR 4 1974 Publication began, was completed APR 18 1974
12. APR 3 1974 Notice published in San Juan Record
13. _____ Proof slips checked by dph & SL
14. April 24, 1974 Change Application protested by Full paid - 1447
15. NOV. 16, 1971 Field Examined by WCK & LG
16. MAY 20, 1974 Application designated for approval by WCK SL
17. 5-28-74 Change Application copied jb proofread by _____
18. 5-28-74 Change Application approved and returned to applicant

This application is approved on the following conditions:

1. Actual construction work necessitated by proposed change shall be diligently prosecuted to completion.
2. Proof of change shall be submitted to the State Engineer's office by under 32773
3. This change is subject to all conditions imposed on the approval of the original application or right

Dee C. Hansen

Dee C. Hansen, State Engineer

18. _____ Time for making proof of change extended to _____
19. _____ Proof of change submitted.
20. _____ Certificate of change No. _____, issued.

I hereby certify that the foregoing is a true copy of the Application by _____ to change the point of diversion, place and nature of use of water as shown, with endorsements thereon, on the records of my office on the date given below.

Salt Lake City, Utah _____, 19____

State Engineer

Change Application No. 9-7804

OPERATOR Phillips Petroleum Co DATE 9/7/83
WELL NAME Rutherford Unit #2933
SEC NWSE 29 T 41S R 24E COUNTY San Juan

43-037-30932
API NUMBER

Indian
TYPE OF LEASE

POSTING CHECK OFF:

☐

INDEX

☐

MAP

☐

HL

☐

NID

☐☐

PI

PROCESSING COMMENTS:

Unit Well

Water &

✓ CHIEF PETROLEUM ENGINEER REVIEW:

9/7/83 Unit

APPROVAL LETTER:

SPACING:

☒

A-3

Rutherford Unit
UNIT

☐

c-3-a

CAUSE NO. & DATE

☐

c-3-b

☐

c-3-c

SPECIAL LANGUAGE:

☒ RECONCILE WELL NAME AND LOCATION ON APD AGAINST SAME DATA ON PLAT MAP.

☒ AUTHENTICATE LEASE AND OPERATOR INFORMATION

☒ VERIFY ADEQUATE AND PROPER BONDING

☒ AUTHENTICATE IF SITE IS IN A NAMED FIELD, ETC.

☐ APPLY SPACING CONSIDERATION

☐ ORDER _____

☒ UNIT Rutherford

☐ c-3-b

☐ c-3-c

☒ CHECK DISTANCE TO NEAREST WELL.

☒ CHECK OUTSTANDING OR OVERDUE REPORTS FOR OPERATOR'S OTHER WELLS.

☒ IF POTASH DESIGNATED AREA, SPECIAL LANGUAGE ON APPROVAL LETTER

☒ IF IN OIL SHALE DESIGNATED AREA, SPECIAL APPROVAL LANGUAGE.

September 7, 1983

Phillips Petroleum Company
P. O. Box 2920
Casper, Wyoming 82602

RE: Well No. Rutherford Unit 29-33
NWSE Sec. 29, T. 41S, R. 24E
1860' FSL, 1820' FEL
San Juan County, Utah

Gentlemen:

Insofar as this office is concerned, approval to drill the above referred to oil well is hereby granted in accordance with Section 40-6-11, Utah Code Annotated 1953; and predicated on Rule A-3, General Rules and Regulations and Rules of Practice and Procedure.

Should you determine that it will be necessary to plug and abandon this well, you are hereby requested to immediately notify the following:


RONALD J. FIRTH - Chief Petroleum Engineer
Office: 533-5771
Home: 571-6068

Enclosed please find Form OCC-8-X, which is to be completed whether or not water sands (aquifers) are encountered during drilling. Your cooperation in completing this form will be appreciated.

Further, it is requested that this Division be notified within 24 hours after drilling operations commence, and that the drilling contractor and rig number be identified.

The API number assigned to this well is 43-037-30932.

Sincerely,


R. J. Firth
Chief Petroleum Engineer

RJF/as
cc: Branch of Fluid Minerals (2)
BIA
Enc1.

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ well gas ☐ well other ☒ leadline
2. NAME OF OPERATOR
Phillips Petroleum Company
3. ADDRESS OF OPERATOR
P.O. Box 2920, Casper, WY 82602
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1860' FSL, 1820' FEL (NW SE)
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO: SUBSEQUENT REPORT OF:

TEST WATER SHUT-OFF	<input type="checkbox"/>	<input type="checkbox"/>
FRACTURE TREAT	<input type="checkbox"/>	<input type="checkbox"/>
SHOOT OR ACIDIZE	<input type="checkbox"/>	<input type="checkbox"/>
REPAIR WELL	<input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING	<input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE	<input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES	<input type="checkbox"/>	<input type="checkbox"/>
ABANDON*	<input type="checkbox"/>	<input type="checkbox"/>

(other) Install leadline

5. LEASE
14-20-603-407
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
Navajo
7. UNIT AGREEMENT NAME
SW-I-4192
8. FARM OR LEASE NAME
Ratherford Unit
9. WELL NO.
29-33
10. FIELD OR WILDCAT NAME
Greater Aneth
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec. 29-T41S-R24E
12. COUNTY OR PARISH
San Juan
13. STATE
Utah
14. API NO.
43-037-30932
15. ELEVATIONS (SHOW DF, KDB, AND WD)

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Approval is requested, contingent on securing Archaeological clearance, to install a leadline as shown on the attached plat A-1A. The leadline will connect Ratherford Unit #29-33 well to Satellite 20. This proposed leadline routing is a revision from that shown in the approved APD.

RECEIVED
NOV 15 1983DIVISION OF
OIL, GAS & MINING

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct


SIGNED A. E. Stuart TITLE Area Manager DATE November 10, 1983



(This space for Federal or State office use)


APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:



5-BLM-Farmington 1-File
✓ Utah O&G CC SLC Utah
1-J.L. Whitmire (r) T.C. Doughty
1-G. W. Berk
1-T.M. Isaacs


*See Instructions on Reverse Side





NO.	REVISION	BY	DATE	CHKD	APP'D
FOR BIDS	 PHILLIPS PETROLEUM COMPANY 			J.A. NO.	FILE CODE
FOR APPR	BARTLESVILLE, OKLAHOMA			AFE NO.	SCALE
FOR CONST	RATHERFORD UNIT WELL 29-33 TOPOMAP NWSE SEC. 29 T41S-R24E SAN JUAN CO., UTAH			2" = 1 mi	
DRAWN	CJW			DWG NO.	
CHECKED				SH NO.	
APP'D					



ROUTING OF LEADLINE CHANGED		BJM		11/7/83					
REVISION		BY		DATE		CHKD APP'D			
DR BIDS		<div style="display: flex; justify-content: space-between; align-items: center;"> <div style="text-align: center;">  <p>PHILLIPS PETROLEUM COMPANY</p> <p>BARTLESVILLE, OKLAHOMA</p> </div> <div style="text-align: center;">  </div> </div>				JA NO.		FILE CODE	
DR APPR						AFE NO.		SCALE 2 1/4" = 1 mi	
DR CONST		<div style="text-align: center;"> <p>RATHERFORD UNIT WELL 29-33</p> <p>PROPOSED LEADLINE</p> <p>NWSE SEC 29 T41S-R24E</p> <p>SAN JUAN CO., UTAH</p> </div>				DWG NO.			
DRAWN						SH NO.			
CHECKED						A-1A			
P.D.									



NO.	REVISION	BY	DATE	CHKD	APP'D
FOR BIDS	<div style="display: flex; justify-content: space-between; align-items: center;"> <div style="text-align: center;">  <p>PHILLIPS PETROLEUM COMPANY</p> <p>BARTLESVILLE, OKLAHOMA</p> </div> <div style="text-align: center;">  </div> </div>			JA NO.	FILE CODE
FOR APPR				AFE NO.	SCALE 2 1/4" = 1 mi
FOR CONST				DWG NO.	SH NO.
DRAWN	<p>RATHERFORD UNIT WELL 29-33</p> <p>ROAD PLAT</p> <p>NWSE SEC. 29 T41S-R24E</p> <p>SAN JUAN CO., UTAH</p>				
CHECKED					
APP'D					

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☐ gas ☐ other ☒ Lease Road
well well

2. NAME OF OPERATOR

Phillips Petroleum Company

3. ADDRESS OF OPERATOR

P. O. Box 2920 Casper, WY 82602

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)

AT SURFACE:

AT TOP PROD. INTERVAL:

AT TOTAL DEPTH:

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

SUBSEQUENT REPORT OF:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐PULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐CHANGE ZONES ☐ABANDON* ☐(other) road construction ☒

5. CASE 14-20-603-353

14-20-603-407

6. IF INDIAN, ALLOTTEE OR TRIBE NAME
Navajo7. UNIT AGREEMENT NAME
SW-I-41928. FARM OR LEASE NAME
Ratherford Unit

9. WELL NO.

10. FIELD OR WILDCAT NAME
Greater Aneth11. SEC., T., R., M., OR BLK. AND SURVEY OR
AREA Sec 20 and 29, T41S-R24E12. COUNTY OR PARISH | 13. STATE
San Juan | Utah

14. API NO.

15. ELEVATIONS (SHOW DF, KDB, AND WD)

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Approval is requested, contingent on securing Archaeological clearance and residents approval, to construct an access road as shown on the attached Plat A-1A. Approximately 660' of new lease road will be built. The road construction will be of native soil, approximately 20' wide.

RECEIVED
NOV 15 1983

DIVISION OF

OIL, GAS & MINING

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED

A. E. Stuart

TITLE

Area Manager

DATE

November 10, 1983

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

5- BLM Farmington

1- Utah O&G CC SLC, Utah


1- J. L. Whitmire (r) T.C. Doughty



*See Instructions on Reverse Side


1- G. W. Berk

1- T. M. Isaacs

1- File



NO.	REVISION	BY	DATE	CHKD	APP
FOR BIDS	 PHILLIPS PETROLEUM COMPANY 			JA NO.	FILE CO
FOR APPR				AFE NO.	SCALE 1"=24' MIN
FOR CONST.				DWG NO.	
DRAWN	RATHERFORD UNIT PROPOSED ROAD T4IS-R24E SAN JUAN CO. UTAH			SH NO.	
CHECKED					
APP'D					



REVISION		BY	DATE	CHKD	APP'D
R BIOS		PHILLIPS PETROLEUM COMPANY		JA NO.	
R APPR		BARTLESVILLE, OKLAHOMA		FILE CODE	
I CONST		RATHERFORD UNIT		AFE NO.	
OWN		PROPOSED ROAD		SCALE	
CKED		T 41S-R24E		2 1/4" = 1 mi	
D		SAN JUAN CO., UTAH		DWG. NO.	
				SH NO. A-1A	

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well <input checked="" type="checkbox"/> gas well <input type="checkbox"/> other <input type="checkbox"/>
2. NAME OF OPERATOR Phillips Oil Company
3. ADDRESS OF OPERATOR P.O. Box 2920, Casper, WY 82602
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.) AT SURFACE: AT TOP PROD. INTERVAL: AT TOTAL DEPTH:
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:	SUBSEQUENT REPORT OF:
TEST WATER SHUT-OFF <input type="checkbox"/>	<input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	<input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	<input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING <input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE <input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES <input type="checkbox"/>	<input type="checkbox"/>
ABANDON* <input type="checkbox"/>	<input type="checkbox"/>
(other) <u>Change of Operator</u>	

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details; and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Effective December 1, 1983, Phillips Oil Company assumed operations from Phillips Petroleum Company. The following wells had Applications for Permits to Drill submitted under Phillips Petroleum Company:

Ratherford Unit #19-42, 20-13, 20-44, 20-22, 20-24, 20-33, 21-13, 29-42, 29-32, & 29-33. + 29-31

DIVISION OF
OIL, GAS & MINING

Subsurface Safety Valve, Manu. and Type _____

18. I hereby certify that the foregoing is true and correct

SIGNED

A. E. Stuart

TITLE

Area Manager

DATE

1/13/84

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☒ well ☐ gas well ☐ other
2. NAME OF OPERATOR
Phillips Oil Company
3. ADDRESS OF OPERATOR
8055 E. Tufts Ave. Pkwy., Denver CO 80237
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1860 FSL & 1820 FEL (NW/SE)
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:
TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐
(other) _____

SUBSEQUENT REPORT OF

☐
☐
☐
☐
☐
☐
☐
☐
☐
☐**RECEIVED**
FEB 1 1984

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

DIVISION OF
OIL, GAS & MINING

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*
- Spudded well Dec. 26, 1984, with Four Corners Rig #8.
Drilled 12-1/4" hole to 1600'. Ran 1630' 9-5/8" 36# K-55, set at 1600.
Cemented with 720 ft³ (300 sx) Class B w/20% Diacel D tailed with 360 ft³ (300 sx) Class B. Cement circulated, job complete 12-28-83.
Drilled 8-3/4" hole to 5800'. Ran 5800' 7" 23 & 26# K-55 casing.
Set at 5800'. Cemented with 960 ft³ (400 sx) Class B w/20% Diacel D tailed with 360 ft³ (300 sx) Class B w/18% salt. Pressure test casing to 1500 psi, job complete 1-8-84. TOC @ 2992'.

Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED David C. Burk TITLE RMR Drilling Mgr DATE January 1984

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

Form 8-329 Rev. Feb 76
OMB 42-RO356

MONTHLY REPORT
OF
OPERATIONS

Lease No. 1 4603-407
Communitization Agreement No. NA
Field Name Greater Aneth
Unit Name Ratherford Unit (SW-I-4192)
Participating Area Paradox
County San Juan State Utah
Operator Phillips Petroleum Company

☐ Amended Report

The following is a correct report of operations and production (including status of all unplugged wells) for the month of
December, 19 83

(See Reverse of Form for Instructions)

This report is required by law (30 U.S.C. 189, 30 U.S.C. 359, 25 U.S.C. 396 d), regulation (30 CFR 221.60), and the terms of the lease. Failure to report can result in the assessment of liquidated damages (30 CFR 221.54 (j)), shutting down operations, or basis for recommendation to cancel the lease and forfeit the bond (30 CFR 221.53).

Well No.	Sec. & 1/4 of 1/4	TWP	RNG	Well Status	Days Prod.	Barrels of Oil	MCF of Gas	Barrels of Water	Remarks
29-33	Sec. 29 NW SE	41S	24E	DRG			INITIAL REPORT		
						Present Operation as of January 1, 1984 - Drld at 4238'. MI & RU dry hole digger. Drld 18" hole to 178'. Ran 3 jts 13-3/8" K-55 48# 8 round ST&C csg. Cmdt w/150 sx Class B cmt, 31 bbls slurry displaced w/17.5 bbls wtr leaving 1 bbl cmt in csg. Had cmt returns, 2 gallons, but slowly fell back. MI & RU Four Corners, Rig #8, 12/25/83. Spudded 12-1/4" surface hole at 6:00 pm, 12/26/83 and drld to 1600'. Ran 1629.77 of 9-5/8" 36# K-55 8Rd csg set at 1600'. Cmdt w/300 sx Class B cmt w/20% Diacel-D w/1/4#/sx Celloflakes, 2% CaCl2, followed w/300 sx Class B cmt w/1/4#/sx Celloflakes, 2% CaCl2. Displd w/122.8 BW w/good returns. 1500 psi test pressure on plug, released press, plug held. RD Hydrill, cut csg. Weld on 9-5/8" Bradenhead. Test well to 3000 psi. Top off cmt in annulus w/25 sx Class B cmt w/3% CaCl2. NU BOP's. Test to 300 & 3000 psi. Tag cmt at 1559'. Test 9-5/8" csg to 1500 psi. Drld FC, 40' cmt, shoe & drld 8-3/4" hole to 4238'. Mud 9.4, Vis 32, WL 13.6.			

*If none, so state.

Disposition of production (Lease, Participating Area, or Communitized Area basis)

Oil & Condensate
(BBLs)

Gas
(MCF)

Water
(BBLs)

*On hand, Start of Month
*Produced
*Sold
*Spilled or Lost
*Flared or Vented
*Used on Lease
*Injected
*Surface Pits
*Other (Identify)
*On hand, End of Month
*API Gravity/BTU Content

Authorized Signature: A. E. Stuart

Address: P.O. Box 2920, Casper, WY 82602

Title: Area Manager

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUBMIT IN DUPLICATE

(See other instructions on reverse side)

Form approved.
Budget Bureau No. 42-R355.5.

WELL COMPLETION OR RECOMPLETION REPORT AND LOG *

1a. TYPE OF WELL:		OIL WELL <input checked="" type="checkbox"/>	GAS WELL <input type="checkbox"/>	DRY <input type="checkbox"/>	Other <input type="checkbox"/>		
b. TYPE OF COMPLETION:		NEW WELL <input checked="" type="checkbox"/>	WORK OVER <input type="checkbox"/>	DEEP-EN <input type="checkbox"/>	PLUG BACK <input type="checkbox"/>	DIFF. RESVR. <input type="checkbox"/>	Other <input type="checkbox"/>
2. NAME OF OPERATOR Phillips Oil Company						5. LEASE DESIGNATION AND SERIAL NO. 14-20-603-407	
3. ADDRESS OF OPERATOR P.O. Box 2920, Casper, WY 82602						6. IF INDIAN, ALLOTTEE OR TRIBE NAME Navajo	
4. LOCATION OF WELL (Report location clearly and in accordance with State requirements)* At surface 1860' FSL & 1820' FEL, NW SE At top prod. interval reported below At total depth						7. UNIT AGREEMENT NAME SW-1-4192	
14. PERMIT NO. OIL, GAS & MINING						8. FARM OR LEASE NAME Ratherford Unit	
15. DATE SPUDDED 12/26/83						9. WELL NO. #29-33	
16. DATE T.D. REACHED 1/7/84						10. FIELD AND POOL, OR WILDCAT Greater Aneth	
17. DATE COMPL. (Ready to prod.) 1/25/84						11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA Sec. 29-T41S-R24E	
18. ELEVATIONS (DF, RKB, RT, GR, ETC.)* GR 4915', RKB 4927'						12. COUNTY OR PARISH San Juan	
19. ELEV. CASINGHEAD --						13. STATE Utah	
20. TOTAL DEPTH, MD & TVD 5800'		21. PLUG. BACK T.D., MD & TVD 5744'		22. IF MULTIPLE COMPL., HOW MANY* --		23. INTERVALS DRILLED BY ROTARY TOOLS 0 - 5800'	
24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)* 5606' - 5696' Desert Creek Zone 1 & Ismay						25. WAS DIRECTIONAL SURVEY MADE No	
26. TYPE ELECTRIC AND OTHER LOGS RUN DLL-MSFL-GR-CAL, FDC-CNL						27. WAS WELL CORED No	
28. CASING RECORD (Report all strings set in well)							
CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD		AMOUNT PULLED	
13-3/8"	48#	118'	18"	180 ft ³ Class B		--	
9-5/8"	36#	1600'	12-1/4"	1080 ft ³ Class B		--	
7"	23 & 26#	5800'	8-3/4"	1320 ft ³ Class B		--	
29. LINER RECORD							
SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACER SET (MD)
--	--	--	--	--	2-7/8"	5634'	5634'
30. PERFORATION RECORD (Indicate, etc. gas number)							
31. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.				32. DEPTH INTERVAL (MD)			
SEE ATTACHMENT				SEE ATTACHMENT			
33. PRODUCTION							
DATE FIRST PRODUCTION 1/25/84		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump) Presently running pump & rods, will resubmit when test obtained.				WELL STATUS (Producing or shut-in)	
DATE OF TEST	HOURS TESTED	CHORE SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL.	GAS—MCF.	WATER—BBL.	GAS-OIL RATIO
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BBL.	GAS—MCF.	WATER—BBL.	OIL GRAVITY-API (CORR.)	
34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)						TEST WITNESSED BY	
35. LIST OF ATTACHMENTS Acid, Shot, Fracture, Cement Squeeze and Perforation Record							
36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records							

SIGNED

A. E. Stuart

TITLE

Area Manager

DATE 2/8/84

4 - BLM, Farmington (See Instructions and Spaces for Additional Data on Reverse Side) API #43-037-30932
2 - Utah O&G CC, SLC, Utah 1 - B. Conner, B'Ville 1 - Coffelt, Denver
1 - BIA, Shiprock, NM 1 - Whitmire, Denver 1 - W.I. Owners
1 - Navajo Nation 1 - Poling, Denver 1 - File

INSTRUCTIONS

General: This form is designed for submitting a complete and correct well completion report and log on all types of lands and leases to either a Federal agency or a State agency, or both, pursuant to applicable Federal and/or State laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office. See instructions on items 22 and 24, and 33, below regarding separate reports for separate completions.

If not filed prior to the time this summary record is submitted, copies of all currently available logs (drillers, geologists, sample and core analysis, all types electric, etc.), formation and pressure tests, and directional surveys, should be attached hereto, to the extent required by applicable Federal and/or State laws and regulations. All attachments should be listed on this form, see item 35.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 18: Indicate which elevation is used as reference (where not otherwise shown) for depth measurements given in other spaces on this form and in any attachments. **Items 22 and 24:** If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) (if any) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

Item 29: "Sacks Cement": Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool.

Item 33: Submit a separate completion report on this form for each interval to be separately produced. (See instruction for items 22 and 24 above.)

37. SUMMARY OF POROUS ZONES:

SHOW ALL IMPORTANT ZONES OF POROSITY AND CONTENTS THEREOF; CORED INTERVALS; AND ALL DRILL-STEM TESTS, INCLUDING DEPTH INTERVAL TESTED, CUSHION USED, TIME TOOL OPEN, FLOWING AND SHUT-IN PRESSURES, AND RECOVERIES

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	38. GEOLOGIC MARKERS	
				MEAS. DEPTH	TRUE VERT. DEPTH
NO CORES OR DST'S RUN.				LOG TOPS	
				Shinarump	2440'
				DeChelly	2740'
				Hermosa	4750'
				Paradox	5520'

Attachment to Form 9-330
Ratherford Unit #29-33

ACID, SHOT, FRACTURE, CEMENT SQUEEZE & PERFORATION RECORD

- 5708½-5726½' - 2 SPF, 4" hollow steel carrier gun
Shot did not fire at 5718½', 35 shots.
- 5706-5708½' - 2 SPF, 4" hollow steel carrier gun
Shot did not fire at 5708', 4 shots.
- 5706-5726½' - Spotted 250 gal 28% HCL w/2 gal/1000 NAI-166, 5
gal/1000 NNE-257N, 50#/1000 NIS-546 & 5 gal/1000
NFS-282N. Pumped 2450 gal acid. Dropped 82, 1.3
sp grav., ball sealers throughout. Displd w/41
bbls lse wtr.
- Set BP at 5701' to perforate upper interval.
- 5640 - 5644' - 2 SPF, 4" hollow steel carrier gun
5674 - 5696' - 2 SPF, 4" hollow steel carrier gun
54 holes total
- 5640 - 5696' - Acidized w/4000 gal 28% FE acid w/2 gal/1000 NAI-50,
1 gal/1000 NC-2 & 3 gal/1000 Lo-Surf 259. Cleared
tbg of all acid & pumped 30 bbls down annulus.
- Pulled BP at 5701'. WIH, set pkr at 5634'.

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY
(FORM 9-329)
(12/76)
OMB 42-RO 356

MONTHLY REPORT
OF
OPERATIONS

Lease No. 14 J-603-407
Communitization Agreement No. NA
Field Name Greater Aneth
Unit Name Ratherford Unit (SW-I-4192)
Participating Area Paradox
County San Juan State Utah
Operator Phillips Oil Company
☐ Amended Report

The following is a correct report of operations and production (including status of all unplugged wells) for the month of January, 19 84

(See Reverse of Form for Instructions)

This report is required by law (30 U.S.C. 189, 30 U.S.C. 359, 25 U.S.C. 396 d), regulation (30 CFR 221.60), and the terms of the lease. Failure to report can result in the assessment of liquidated damages (30 CFR 221.54 (j)), shutting down operations, or basis for recommendation to cancel the lease and forfeit the bond (30 CFR 221.53).

Well No.	Sec. & 1/4 of 1/4	TWP	RNG	Well Status	Days Prod.	*Barrels of Oil	*MCF of Gas	*Barrels of Water	Remarks
29-33	Sec. 29 NW SE	41S	24E	DRG		Present Operation as of February 1, 1984, preparing to perforate.			
						SEE ATTACHMENT FOR DETAILS			

*If none, so state.

DISPOSITION OF PRODUCTION (Lease, Participating Area, or Communitized Area basis)

	Oil & Condensate (BBLS)	Gas (MCF)	Water (BBLS)
*On hand, Start of Month		XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
*Produced			
*Sold			XXXXXXXXXXXXXXXXXXXX
*Spilled or Lost		XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
*Flared or Vented	XXXXXXXXXXXXXXXXXXXX		XXXXXXXXXXXXXXXXXXXX
*Used on Lease			XXXXXXXXXXXXXXXXXXXX
*Injected			
*Surface Pits	XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX	
*Other (Identify)			
*On hand, End of Month		XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
*API Gravity/BTU Content			XXXXXXXXXXXXXXXXXXXX

Authorized Signature: A. E. Stuart Address: P.O. Box 2920, Casper, WY 82602
Title: Area Manager Page 1 of 1

DAILY REPORT DETAILED

LEASE RATHERFORD UNITWELL NO. 29-33SHEET NO. 2DATE 1983
TOTAL DEPTH
NATURE OF WORK PERFORMED

12/28/83 AFE: U863

TD 1600. WOC. 12/26/83 - MI & RU FOUR CORNERS. RIG #8.
12/25/83. 12/27/83 - SPUDDED 12-1/4" SURFACE HOLE
AT 6:00 PM. 12/26/83 AND DRLD TO 1018'. 900'.
SURVEYS - 1-1/4 DEG AT 191'. 1 DEG AT 326'. 3/4 DEG
AT 418' & 512'. 1-3/4 DEG AT 761'. 1-1/2 DEG AT 885'
. 12/28/83 - DRLD 12-1/4" HOLE TO 1600'. 582'.
RU & RUN 1629.77' OF 9-5/8" 36# K-55 8rd CSG SET AT
1600'. CIRC FLOSAL FILL. VIS 47. MUT 9 PPG. CMTD
W/300 SX CLASS B CMT W/20% DIACEL-D W/1/4#/SX
CELLOFLAKES. 2% CaCL2. 12.4 PPG. FOLLOWED W/300 SX
CLASS B CMT W/1/4#/SX CELLOFLAKES. 2% CaCL2. 15.6
PPG. DISPLD W/122.8 BW W/GOOD RETURNS. 1500 PSI
TEST PRESSURE ON PLUG. RELEASED PRESSURE. PLUG HELD
. NOW WOC. SURVEYS - 1-1/4 DEG AT 978'. 3/4 DEG
AT 1105' & 1326'. 1 DEG AT 1576'..

12/29/83 AFE: U863

D 2353. WOC. RD HYDRILL. CUT CSG. WELD ON 9-5/8" BRADEN-
HEAD. TEST WELL TO 3000 PSI. TOP OFF CMT IN
ANNULUS W/25 SX CLASS B CMT W/3% CaCL2. NU BOP'S.
TEST TO 300 & 3000 PSI. WIH. TAG CMT AT 1559'.
TEST 9-5/8" CSG TO 1500 PSI. DRLD FC. 40' CMT. SHOE
& 10' FORMATION. PERFORMED LEAK-OFF TEST. (LEAKED
OFF AT 13.7 PPG MUD EQUIVALENT). DRLD TO 2353'.
753'. SURVEY - 3/4 DEG AT 2098'..

12/30/83 AFE: U863

D 3240. DRLD TO 3240'. 887'. DRLD TO 3240'. 887'. SURVEY -
3/4 DEG AT 2603'. MUD 9.5, VIS 35, WL 12.2.

01/03/84 AFE: U863

D 4976. 12/31/83 - DRLD TO 3800'. 560'. SURVEY - 1 DEG AT
3481'. MUD 9.5, VIS 33, WL 14. 1/1/84 - DRLD TO
4238'. 438'. SURVEY - 3/4 DEG AT 3982'. MUD 9.4,
VIS 32, WL 13.6. 1/2/84 - DRLD TO 4632'. 394'.
SURVEY - 3/4 DEG AT 4480'. MUD 9.5, VIS 37, WL 8.2.
1/3/84 - DRLD TO 4976'. 344'. MUD 9.5, VIS 33, WL
12.0..

01/04/84 AFE: U863

D 5205. DRLD TO 5205'. 229'. SURVEY - 1/2 DEG AT 5011'. MUD
9.6, VIS VIS 33, WL 10.4..

01/05/84 AFE: U863

D 5428. DRLD TO 5428'. 223'. MUD 10.4, VIS 39, WL 8..

01/06/84 AFE: U863

D 5613. DRLD TO 5613'. 185'. SURVEY - 3/4 DEG AT 5513'.
MUD 10.6, VIS 46, WL 8.0.

DAILY REPORT DETAILED

LEASE RATHERFORD UNITWELL NO. 29-33SHEET NO. 3

1984

DATE
NATURE OF WORK PERFORMEDTOTAL
DEPTH

01/09/84 AFE: U863

TD 5800, PBTD 5751. RDRT. 1/7/84 - DRLD TO TD 5785', 1/6/84. MADE SHORT TRIP, OK. CIRC & COND HOLE FOR LOGGING. SLM OOH. SURVEY - 1/2 DEG AT 5764'. RU LOGGERS. MUD 10.6, VIS 47. 1/8/84 - FIN RU GEARHART. RUN DLL-MSFL-GR-CAL FROM TD TO SURF SHOE. FDC-CNL-GR-CAL FROM TD TO 4300'. DROPPED ALUMINUM PROTECTOR OFF SONDE IN HOLE. WIH W/BIT & JUNK SUB. WORKED ON JUNK & DRLD ADDITIONAL 15' TO FINAL TD 5800', 1/7/84. CIRC & COND HOLE. COOH. LDDP. CHG RAMS & RU CSG CREW. RUN 140 JTS 7" 23# & 26# K-55 CSG SET AT 5800', FC AT 5751' PBTD. RU TO RECIPROCATE. MUD 10.6, VIS 47. 1/9/84 - CIRC & RECIPROCATE 7" CSG. CMTD AS FOLLOWS - 20 BBL PREFLUSH, FOLLOWED W/400 SX CLASS B W/20% DIACEL D, 10% SALT, 10#/SX KOLITE & 1/4#/SX CELLOFLAKE, WT 12.2 PPG, TAILED IN W/300 SX CLASS B W/.75% D-59, 18% SALT & 1/4#/SX CELLOFLAKE, WT 15.8 PPG. DISPLD W/225 BW. PD AT 9:30 AM, 1/8/84. BUMPED PLUG W/1500 PSI, OK. FLOATS HELD. ND BOP. SET SLIPS. CUT OFF CSG. RELEASED RIG AT 11:30 AM, 1/8/84. NOW RDRT..

01/10/84 AFE: U863

PBTD 5751. FIN RDRT. NOW WO COMPLETION UNIT..

01/11/84 AFE: U863

PBTD 5751. WO COMPLETION UNIT..

01/12/84 AFE: U863

PBTD 5751. WO COMPLETION UNIT..

01/13/84 AFE: U863

PBTD 5751. WO COMPLETION UNIT..

01/16/84 AFE: U863

PBTD 5751. 1/14/84 THRU 1/16/84 - WO COMPLETION UNIT..

01/17/84 AFE: U863

PBTD 5751. WO COMPLETION UNIT..

01/18/84 AFE: U863

PBTD 5751. WO COMPLETION UNIT..

01/19/84 AFE: U863

PBTD 5751. WO COMPLETION UNIT..

01/20/84 AFE: U863

PBTD 5751. WO COMPLETION UIT.

DAILY REPORT DETAILED

LEASE RATHERFORD UNITWELL NO. 29-33SHEET NO. 4

1984

DATE
NATURE OF WORK PERFORMEDTOTAL
DEPTH
PERFORMED

01/23/84 AFE: U863

PBTD 5744. 1/22/84 - MI & RU COMPLETION UNIT 1/21/84. HELD SAFETY MEETING. NU 6" 3000 PSI BOP'S. PRESS TSTD BOP'S TO PPCD STANDARDS. PU 4-1/8" BIT & 7" SCRAPER. WIH, TAG CMT AT 5734'. RU POWER SWIVEL & CIRC EQUIPMENT. WASHED CMT TO NEW PBTD 5744'. CMT HAD NOT SET UP. CIRC BTMS UP AND LEFT BIT AT 5713'. SDON. 1/23/84 - ROLLED HOLE W/220 BBLs LSE WTR. PRESS TEST CSG TO 1500 PSI. COOH W/BIT & SCRAPER. RU GEOSOURCE. RUN CBL, VDL, GR LOG 5745-2790' (TOP OF CMT AT 2922'). TWO TOOL FAILURES ON LOGGING. RU LUBRICATOR. TESTED TO 1500 PSI. WIH W/4" HOLLOW STEEL CARRIER GUN. PERFORATED 5708-1/2 TO 5726-1/2' 2 SPF, 35 SHOTS (SHOT DID NOT FIRE AT 5718-1/2', GUN LOADED WRONG). NO PRESSURE BUILD-UP. LOADED ANOTHER GUN. PERFORATED 5706 - 5708-1/2'. 2 SPF, 4 SHOTS (NO HOLE AT 5708' BECAUSE OF MISFIRE). TOTAL 39 SHOTS. HAD 4 PSI AFTER PULLING GUN FROM HOLE. SHUT WELL IN OVERNIGHT. WELL FLOWING 3 BBLs/HR. THIS AM - TP 950 PSI..

01/24/84 AFE: U863

PBTD 5744. SWABBING WELL. PU 7" BAKER R-3 PKR, WIH & SET AT 5592'. FLWD WELL 2 HRS. REC 1-1/2 BW. MADE 4 SWAB RUNS. REC 2 BO & 24.2 BW. FL AT 4900'. WAIT 30 MIN AND SWABBED .7 BO & .7 BW. 300' ENTRY. SHUT DOWN 1 HR. REC 1-1/2 BO & 1-1/2 BW. 600' ENTRY. SDON..

01/25/84 AFE: U863

PBTD 5744. THIS AM - WELLHEAD PRESS 350 PSI. OPENED WELL TO FRAC TANK, WELL FLWD 13-1/2 BO IN 30 MIN, THEN DIED. SWBD WELL, REC 3 BO. SHUT DOWN 2 HRS. MADE 1 SWAB RUN FROM 4900', REC 1.6 BO. SHUT DOWN 2 HRS. MADE 1 SWAB RUN FROM 4900', REC 1.3 BO. NO BOP'S. NU WELLHEAD, WIH W/BHP BOMB. HANG OFF BOMB AT 5580' SHUT WELL IN OVERNIGHT. TOTAL RECOVERY - 19.4 BO..

01/26/84 AFE: U863

PBTD 5744. SWAB TSTG WELL. COOH W/BHP BOMB. AFTER 16 HRS, PRESS 1452 PSI AND STILL INCREASING. RU NOWSCO. HELD SAFETY MEETING. PRESS TEST LINES TO 4000 PSI. ATTEMPT TO PUMP INTO WELL AT 3300 PSI. UNSEAT PKR AND ROLL HOLE W/LSE WTR. RAN PKR TO 5724'. SPOTTED 250 GAL 28% HCL W/2 GAL/1000 NAI-166. 5 GAL/1000 NNE-257N. 50#/1000 NIS-546 AND 5 GAL/1000 NFS-282N. RESET PKR AT 5558'. BROKE DOWN WELL AT 1-1/2 BPM AT 3100 PSI. PUMPED 2450 GAL ACID. AVG 2 BPM AT 3000 PSI. DROPPED 82, 1.3 SF GRAY. BALL SEALERS THROUGH-OUT-JOB. BALLED OFF TWICE. DISPLD W/41 BBLs LSE WTR. ISIP 2500 PSI, 5 MIN 630 PSI, 10 MIN 400 PSI, 15 MIN 100 PSI. RD NOWSCO. TOTAL LOAD TO REC 98 BBLs. SWBD. WELL. FLWD 4 HRS AND DIED, REC 48 BO & 60 BW. 38 BBLs LOAD TO REC..

01/27/84 AFE: U863

PBTD 5744. SWAB & FLOW TESTING WELL. WELL FLOWS FOR 20 TO 30 MIN AFTER EACH SWAB RUN AND DIES. FL AT 2500'. TOTAL RECOVERY - 104 BO & 26 BW. 12 BW TO REC. LEFT WELL OPEN TO TANK.

DAILY REPORT DETAILED

LEASE RATHERFORD UNIT

WELL NO. 29-33

SHEET NO. 5

1984 DATE TOTAL
NATURE OF WORK DEPTH
PERFORMED

01/30/84 AFE: U863

PBTD 5744. PREP TO PULL BHP BOMB. 1/28/84 - SWABBED & FLWD
 4-1/2 HRS. REC 60 BO & 14 BW. RU TEFTLER. RUN
 PRESS BOMB. SHUT-IN WELL AT 12:30 PM, 1/27/84.
 1/29/84 & 1/30/84 - SI FOR BHP TEST..

01/31/84 AFE: U863

PBTD 5744. PREPARING TO PERF. COOH W/WL PRESS BOMB. HAD 39
 HR INTERVAL READINGS, STARTING AT 585 PSI AND END-
 ING AT 952 PSI. COOH W/TBG. WITH W/HALLIB COLLAR
 LOCATOR AND BP. SET BP AT 5701'. 5' ABOVE PERFS.
 TESTED TO 1500 PSI FOR 15 MIN. OK. SDON..

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well ☒ gas well ☐ other ☐
2. NAME OF OPERATOR
Phillips Petroleum Company
3. ADDRESS OF OPERATOR
8055 E. Tufts Ave. Pkwy./Denver, CO. 80237
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 1860 FSL & 1820 FEL (NW SE)
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE.
REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:

TEST WATER SHUT-OFF ☐
FRACTURE TREAT ☐
SHOOT OR ACIDIZE ☐
REPAIR WELL ☐
PULL OR ALTER CASING ☐
MULTIPLE COMPLETE ☐
CHANGE ZONES ☐
ABANDON* ☐
(other) ☐

SUBSEQUENT REPORT OF:


☐
☐
☐
☐
☐
☐
☐
☐
☐
☐

5. LEASE
14-20-603-407
6. IF INDIAN, ALLOTTEE OR TRIBE NAME
Navajo
7. UNIT AGREEMENT NAME
SW-I-4192
8. FARM OR LEASE NAME
Ratherford Unit
9. WELL NO.
29-33
10. FIELD OR WILDCAT NAME
Greater Aneth
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Sec 29-T41S-R24E
12. COUNTY OR PARISH
San Juan
13. STATE
Utah
14. API NO.
43-037-30932
15. ELEVATIONS (SHOW DF, KDB, AND WD)
4927 RKB

(NOTE: Report results of multiple completion or zone change on Form 9-330.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Drilled 18" conductor hole to 118 ft. Ran 118 ft., 13-3/8" 54.5# K-55 conductor casing. Set casing at 118 ft. cemented with 180 ft³ (150 sx) class 'B' cement circulated to surface. Finished job and moved out rathole driller 12-12-83. Moved in drilling rig to spud well. See Sundry Notice dated January, 1984. Reached TD of 5800' 1-7-84. Plug back total depth is 5744 ft.



Subsurface Safety Valve: Manu. and Type _____ Set @ _____ Ft.

18. I hereby certify that the foregoing is true and correct

SIGNED Walter R. Beck TITLE Drilling Manager DATE 2-2-84

(This space for Federal or State office use)

APPROVED BY _____
CONDITIONS OF APPROVAL, IF ANY:

TITLE _____

DATE _____

- 6 - BLM Farmington, NM.
2 - Utah Oil & Gas CC Salt Lake City
1 - File - RC
1 - Casper
1 - T. M. Issacs

*See Instructions on Reverse Side

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

Form 8-329 Rev. Feb 76
OMB 42-RO356

MONTHLY REPORT
OF
OPERATIONS

Lease No. 14-603-407

Communitization Agreement No. NA
Field Name Greater Aneth
Unit Name Ratherford Unit (SW-I-4192)
Participating Area Paradox
County San Juan State Utah
Operator Phillips Oil Company

☐ Amended Report

The following is a correct report of operations and production (including status of all unplugged wells) for the month of
February, 1984

(See Reverse of Form for Instructions)

This report is required by law (30 U.S.C. 189, 30 U.S.C. 359, 25 U.S.C. 396 d), regulation (30 CFR 221.60), and the terms of the lease. Failure to report can result in the assessment of liquidated damages (30 CFR 221.54 (j)), shutting down operations, or basis for recommendation to cancel the lease and forfeit the bond (30 CFR 221.53).

Well No.	Sec. & 1/4 of 1/4	TWP	RNG	Well Status	Days Prod.	Barrels of Oil	1000 cu ft of Gas	Barrels of Water	Remarks
29-33	Sec. 29 NW SE	41S	24E	DRG		PBTD 5744. Present operation as of March 1, 1984, pmpg to production, installing new pump.			43-037-30932✓
SEE ATTACHED FOR DETAILS									

RECEIVED
MAR 12 1984
DIVISION OF
OIL, GAS & MINING

RECEIVED
MAR 12 1984
DIV. OF OIL, GAS & MINING

*If none, so state.

Disposition of production (Lease, Participating Area, or Communitized Area basis)

	Oil & Condensate (BBLs)	Gas (MCF)	Water (BBLs)
On hand, Start of Month		XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
Produced			
Sold			XXXXXXXXXXXXXXXXXXXX
Spilled or Lost		XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
Flared or Vented	XXXXXXXXXXXXXXXXXXXX		XXXXXXXXXXXXXXXXXXXX
Used on Lease			XXXXXXXXXXXXXXXXXXXX
Injected			
Surface Pits	XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX	
Other (Identify)			
On hand, End of Month		XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
API Gravity/BTU Content			XXXXXXXXXXXXXXXXXXXX

Authorized Signature: A. E. Stuart

Address: P.O. Box 2920, Casper, WY 82602

Title: Area Manager

DAILY REPORT DETAILED

LEASE RATHERFORD UNITWELL NO. 29-33SHEET NO. 5

1984

DATE
NATURE OF WORK PERFORMEDTOTAL
DEPTHJanuary
28-30

01/30/84 AFE: U863

PBTD 5744. PREP TO PULL BHP BOMB. 1/28/84 - SWABBED & FLWD 4-1/2 HRS. REC 60 BO & 14 BW. RU TEFTELER. RUN PRESS BOMB. SHUT-IN WELL AT 12:30 PM, 1/27/84. 1/29/84 & 1/30/84 - SI FOR BHP TEST..

31

01/31/84 AFE: U863

PBTD 5744. PREPARING TO PERF. COOH W/WL PRESS BOMB. HAD 39 HR INTERVAL READINGS. STARTING AT 585 PSI AND ENDING AT 952 PSI. COOH W/TBG. WIH W/HALLIB COLLAR LOCATOR AND BP. SET BP AT 5701'. 5' ABOVE PERFS. TESTED TO 1500 PSI FOR 15 MIN. OK. SDON..

February
1

02/01/84 AFE: U863

PBTD 5744. PREP TO ACIDIZE. RU BASIN PERFORATORS. TESTED LUBRICATOR TO 1000 PSI. PERFORATED FROM 5640-5644' & 5674-5696'. 2 SPF. ALL SHOTS FIRED. TOTAL 54 HOLES. COOH. RD BASIN PERFORATORS. RU & WIH W/HOWCO PPI PKR TOOL (PIN PT INJECTION). SPACED OUT TO STRADDLE FRAC. 1' AT A TIME. SDON..

012

02/02/84 AFE: U863

PBTD 5744. PULLING FLUID PLUG. RU HOWCO. HELD SAFETY MEETING. TESTED SURF LINES TO 4000 PSI. SET PKR BETWEEN THE TWO SETS OF PERFS. TESTED TBG TO 3000 PSI. STARTED INJECTING AT 2:00 PM. 150 GAL FOR EACH FT.. STARTING W/LOWER PERFS AT 5695-96'. 26 SETTINGS. TOTAL ACID INJECTED - 4000 GAL 28% FE ACID W/2 GAL/1000 NAI-50. 1 GAL/1000 HC-2. & 3 GAL/1000 LO-SURF 259. THE FIRST 10' INJECTED AT 2500 TO 2900 PSI AT 1 BPM. HAD 50 PSI ON ANNULUS. THE REMAINING INTERVALS INJECTED AT 2500 TO 2100 PSI AT 1 BPM. NO PRESS ON ANNULUS. AFTER COMPLETING INJ. NO PRESS ON ANNULUS OR TBG. CLEARED TBG OF ALL ACID AND PMPD 30 BBLs DOWN ANNULUS. MADE TRIP W/SAND LINE AND PULLED RFC VALVE IN TOP OF PKR. SDON..

3

02/03/84 AFE: U863

PBTD 5744. SWABBING WELL. WELL HAD 5 PSI ON ANNULUS & 20 PSI ON TBG. COOH W/PPI PKR. WIH W/BAKER R-3 PKR. SET PKR AT 5610'. REMOVED BOP & INSTLD WELLHEAD. MADE 12 SWAB RUNS. REC 55 BO & 55 BW. WELL STARTED FLOWING FOR SHORT PERIOD AFTER #6 SWAB RUN. SDON..

02/06/84 AFE: U863

PBTD 5744. 2/4/84 - TP 300 PSI. CP 0 PSI. BLEED GAS FOR 18 MIN. PROD 18 BO BEFORE IT DIED. MADE 19 SWAB RUNS. WELL WOULD FLOW FOR A SHORT PERIOD BUT DIE AFTER EACH RUN. TOP OF FLUID 2500'. INITIALLY MADE 70% WTR. 30% OIL. AT END OF SWBG. MADE 90% OIL. 10% WTR. MADE TOTAL OF 109 BO & 55 BW. 2/5/84 - TP 250 PSI. CP 0 PSI. NO TREE. NU BOP'S. PUMPED 85 BBLs DOWN ANNULUS. LOWERED PKR TO BP AT 5701'. COOH W/BP & PKR. WIH W/PKR SET AT 5634'. NO BOP'S. NU TREE. BEGAN SWBG WELL. MADE 5 RUNS. REC 55 BW & 2% OIL. 2/6/84 - TP 230 PSI. ANNULUS 0 PSI. MADE 18 SWAB RUNS. REC 87 BO & 85 BW. FL BETWEEN 3300-2500'. FIRST RUN 100% OIL. 2ND RUN ALMOST NO OIL (0.08%). 18TH RUN REC 90% OIL..

4-6

DAILY REPORT DETAILED

LEASE RATHERFORD UNITWELL NO. 29-33SHEET NO. 6

1984

DATE
NATURE OF WORK PERFORMEDTOTAL
DEPTH

February

02/07/84 AFE: U863

PBTD 5744. PREP TO RUN PUMP & RODS. TP 235 PSI. 0 PSI ON ANNULUS. OPENED WELL - GAS ONLY. RELEASED PKR. LD PKR. WITH W/SEATING NIPPLE. 2 JTS TBG & TBG ANCHOR. REMOVED BOP & NU TBG HANGER. SET ANCHOR & PULLED 20# OF TENSION. SET TBG AS LOW AS POSSIBLE IN HANGER. SN 5536'. TURNED WELL OVER TO PRODUCTION. SDON..

02/08/84 AFE: U863

PBTD 5744. TEFTLER RAN STATIC BOTTOM HOLE PRESSURE. STARTED IH W/RODS & PUMP..

02/09/84 AFE: U863

PBTD 5744. WO ELECTRICAL HOOK-UP. PUMPING ASSEMBLY - 60% COMPLETE..

02/10/84 AFE: U863

PBTD 5744. WO ELECTRICAL HOOK-UP. PUMPING UNIT ASSEMBLY - 25% COMPLETE..

02/13/84 AFE: U863

PBTD 5744. 2/11/84 - PMPG UNIT ASSEMBLE COMPLETED. STARTED PUMPING AT 10:30 AM. 2/10/84. 1-3/4" PLUMP. 74" STROKE. 9.7 SPM AT 5536'. 2/12/84 & 2/13/84 - PMPG TO PRODUCTION. NO TESTS..

02/14/84 AFE: U863

PBTD 5744. PMPG TO PROD. NO TEST..

02/15/84 AFE: U863

PBTD 5744. PMPD TO PROD. NO TEST..

02/16/84 AFE: U863

PBTD 5744. PMPD TO PROD. NO TEST..

02/17/84 AFE: U863

PBTD 5744. DOWN 24 HRS, HIGH FLOW LINE PRESSURE.

02/21/84 AFE: U863

PBTD 5744. 2/18/84 THRU 2/21/84 - DOWN - FLOWLINE FROZEN..

02/22/84 AFE: U863

PBTD 5744. PMPG TO PRODUCTION, NO TEST..

02/23/84 AFE: U863

PBTD 5744. PMPG TO PRODUCTION, NO TEST..

02/24/84 AFE: U862

PBTD 5744. PMPD TO PROD. NO TEST..

02/27/84 AFE: U863

PBTD 5744. 2/25/84 THRU 2/27/84 - PMPD TO PROD 72 HRS, NO TESTS..

DAILY REPORT DETAILED

LEASE RATHERFORD UNITWELL NO. 29-33SHEET NO. 7

1984	DATE NATURE OF WORK	TOTAL DEPTH PERFORMED
------	------------------------	-----------------------------

*February**28*02/28/84 AFE: U863PBTD 5744. SHUT-IN DUE TO PROBLEMS W/PUMP. PMPD 23 HRS TO
PRODUCTION, NO TEST..*29*02/29/84 AFE: U863PBTD 5744. SHUT-IN DUE TO PROBLEMS W/PUMP..*March**1*03/01/84 AFE: U863PBTD 5744. SHUT-IN, INSTALLED PUMP STRAINER..

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUBMIT IN DUPLICATE

(See other in-
structions on
reverse side)Form approved.
Budget Bureau No. 42-R355.5.

WELL COMPLETION OR RECOMPLETION REPORT AND LOG *

1a. TYPE OF WELL: OIL WELL ☒ GAS WELL ☐ DRY ☐ Other ☐

b. TYPE OF COMPLETION:

NEW WELL ☒ WORK OVER ☐ DEEP-EN ☐ PLUG BACK ☐ DIFF. RESVR. ☐ Other ☐

2. NAME OF OPERATOR

Phillips Oil Company

3. ADDRESS OF OPERATOR

P.O. Box 2920, Casper, WY 82602

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)

At surface 1860' FSL & 1820' FEL, NW SE

At top prod. interval reported below

At total depth

14. PERMIT NO.

DATE ISSUED

API #43-037-30932

43-037-30932

15. DATE SPUDDED 12/26/83 16. DATE T.D. REACHED 1/7/84 17. DATE COMPL. (Ready to prod.) 1/25/84 18. ELEVATIONS (DF, RKB, RT, GR, ETC.) GR 4915', RKB 4927'

20. TOTAL DEPTH, MD & TVD 5800' 21. PLUG, BACK T.D., MD & TVD 5744' 22. IF MULTIPLE COMPL., HOW MANY? -- 23. INTERVALS DRILLED BY -- 24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD)* 5640' - 5726½' Desert Creek Zone I & Ismay

26. TYPE ELECTRIC AND OTHER LOGS RUN

DLI-MSEI-GR-CAL, EDC-CNL, CBL

27. WAS WELL CORED

No

28. CASING RECORD (Report all strings set in well)

CASING SIZE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	CEMENTING RECORD	AMOUNT PULLED
13-3/8"	48#	118'	18"	180 ft ³ Class B	
9-5/8"	36#	1600'	12-1/4"	1080 ft ³ Class B	
7"	23# & 26#	5800'	8-3/4"	1320 ft ³ Class B	

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
--	---	--	--	--	2-7/8"	5536'	

31. PERFORATION RECORD (Interval, size and number)

SEE ATTACHMENT

32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
	SEE ATTACHMENT

33.* PRODUCTION

DATE FIRST PRODUCTION		PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump)				WELL STATUS (Producing or shut-in)	
1/25/84		Pumping		1-3/4" pump		Producing	
DATE OF TEST	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD	OIL—BBL.	GAS—MCF.	WATER—BBL.	GAS-OIL RATIO
3/18/84	24	--	→	94	43	27	457
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL—BBL.	GAS—MCF.	WATER—BBL.	OIL GRAVITY-API (CORR.)	
--	--	→	94	43	27	40.0	

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

Sold

TEST WITNESSED BY

35. LIST OF ATTACHMENTS

Acid, Shot, Fracture, Cement Squeeze and Perforation Record

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records

SIGNED

A. E. Stuart

TITLE

Area Manager

DATE

3/20/84

4 - BLM, Farmington* (See Instructions and Spaces for Additional Data on Reverse Side)

2 - Utah O&G CC, SLC, Utah

1 - BIA, Shiprock, NM

1 - Navajo Nation

1 - B. Conner, B'Ville

1 - Whitmire, Denver

1 - Poling, Denver

1 - Coffelt, Denver

1 - W.I. Owners

1 - Fraser, Denver 1 - File -R0

INSTRUCTIONS

General: This form is designed for submitting a complete and correct well completion report and log on all types of lands and leases to either a Federal agency or a State agency, or both, pursuant to applicable Federal and/or State laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office. See instructions on items 22 and 24, and 83, below regarding separate reports for separate completions. If not filed prior to the time this summary record is submitted, copies of all currently available logs (drillers, geologists, sample and core analysis, all types electric, etc.), formation and pressure tests, and directional surveys, should be attached hereto, to the extent required by applicable Federal and/or State laws and regulations. All attachments should be listed on this form, see item 35.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 18: Indicate which elevation is used as reference (where not otherwise shown) for depth measurements given in other spaces on this form and in any attachments. **Items 22 and 24:** If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22, and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) (if any) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

Item 29: "Sacks Cement": Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool.

Item 33: Submit a separate completion report on this form for each interval to be separately produced. (See instruction for items 22 and 24 above.)

37. SUMMARY OF POROUS ZONES:

SHOW ALL IMPORTANT ZONES OF POROSITY AND CONTENTS THEREOF; CORED INTERVALS; AND ALL DRILL-STEM TESTS, INCLUDING DEPTH INTERVAL TESTED, CUSHION USED, TIME TOOL OPEN, FLOWING AND SHUT-IN PRESSURES, AND RECOVERIES

FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	MEAS. DEPTH	TOP	TRUE VERT. DEPTH
				Shinarump DeChelly Hermosa Paradox	LOG TOPS		2440' 2740' 4750' 5520'

38. GEOLOGIC MARKERS

Attachment to Form 9-330
Ratherford Unit #29-33

ACID, SHOT, FRACTURE, CEMENT SQUEEZE & PERFORATION RECORD

- 5708½-5726½' - 2 SPF, 4" hollow steel carrier gun
Shot did not fire at 5718½', 35 shots.
- 5706-5708½' - 2 SPF, 4" hollow steel carrier gun
Shot did not fire at 5708', 4 shots.
- 5706-5726½' - Spotted 250 gal 28% HCL w/2 gal/1000 NAI-166, 5
gal/1000 NNE-257N, 50#/1000 NIS-546 & 5 gal/1000
NFS-282N. Pumped 2450 gal acid. Dropped 82, 1.3
sp grav., ball sealers throughout. Displd w/41
bbls lse wtr.

Set BP at 5701' to perforate upper interval.

- 5640 - 5644' - 2 SPF, 4" hollow steel carrier gun
5674 - 5696' - 2 SPF, 4" hollow steel carrier gun
54 holes total
- 5640 - 5696' - Acidized w/4000 gal 28% FE acid w/2 gal/1000 NAI-50,
1 gal/1000 NC-2 & 3 gal/1000 Lo-Surf 259. Cleared
tbg of all acid & pumped 30 bbls down annulus.

Pulled BP at 5701'. WIH, set pkr at 5634'.

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

Form 9-329 Rev. Feb 76
OMB 42-RO356

MONTHLY REPORT
OF
OPERATIONS

Lease No. 10 0-603-407
Communitization Agreement No. NA
Field Name Greater Aneth
Unit Name Ratherford Unit (SW-I-4192)
Participating Area Paradox
County San Juan State Utah
Operator Phillips Oil Company

☐ Amended Report

The following is a correct report of operations and production (including status of all unplugged wells) for the month of March, 19 84

(See Reverse of Form for Instructions)

APR 6 1984

This report is required by law (30 U.S.C. 189, 30 U.S.C. 359, 25 U.S.C. 396 d), regulation (30 CFR 221.60), and the terms of the lease. Failure to report can result in the assessment of liquidated damages (30 CFR 221.54 (1)), shutting down operations, or basis for recommendation to cancel the lease and forfeit the bond (30 CFR 221.53).

Well No.	Sec. & 1/4 of 1/4	T&P	R&G	Well Status	Days Prod.	*Barrels of Oil	*MCF of Gas	*Barrels of Water	Remarks
29-33	Sec. 29 NW SE	41S	24E	DRG					
<div style="text-align: center;"> RECEIVED APR 9 1984 DIVISION OF OIL, GAS & MINING </div>									
<div style="text-align: center;"> FINAL REPORT PBTD 5744. Completed as a pmpg oil well 1/25/84 from Desert Creek Zone I & Ismay perfs 5640-5726½', with a test run 3/18/84 of 94 BOPD, 43 MCFGPD, 27 BWPB, GOR 457. </div>									

*If none, so state.

Disposition of production (Lease, Participating Area, or Communitized Area basis)

	Oil & Condensate (BBLS)	Gas (MCF)	Water (BBLS)
*On hand, Start of Month		XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
*Produced			XXXXXXXXXXXXXXXXXXXX
*Sold		XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
*Spilled or Lost		XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
*Flared or Vented	XXXXXXXXXXXXXXXXXXXX		XXXXXXXXXXXXXXXXXXXX
*Used on Lease			XXXXXXXXXXXXXXXXXXXX
*Injected		XXXXXXXXXXXXXXXXXXXX	
*Surface Pits	XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX	
*Other (Identify)		XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
*On hand, End of Month		XXXXXXXXXXXXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
*API Gravity/BTU Content			XXXXXXXXXXXXXXXXXXXX

Authorized Signature: A. E. Stuart Address: P.O. Box 2920, Casper, WY 82602

Title: Area Manager

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN TRIPLICATE*
(Other instructions on re-
verse side)

Budget Bureau No. 1004-0135
Expires August 31, 1985

5. LEASE DESIGNATION AND SERIAL NO.

14-20-603-407

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

Navajo

7. UNIT AGREEMENT NAME

SW-I-4192

8. FARM OR LEASE NAME

Ratherford Unit

9. WELL NO.

29-33

10. FIELD AND POOL, OR WILDCAT

Greater Aneth

11. SEC., T., R., M., OR BLK. AND
SURVEY OR AREA

Sec. 29-T41S-R24E

12. COUNTY OR PARISH

San Juan

13. STATE

Utah

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1.

OIL WELL ☒ GAS WELL ☐ OTHER ☐

2. NAME OF OPERATOR

Phillips Oil Company

3. ADDRESS OF OPERATOR

P. O. Box 2920 Casper, WY 82602

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.*
See also space 17 below.)

At surface

1860' FSL & 1820' FEL, NW SE

14. PERMIT NO.

API #43-037-30932

15. ELEVATIONS (Show whether DF, RT, OR, etc.)

4927' RKB

16.

Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

FRACTURE TREAT

SHOOT OR ACIDIZE

REPAIR WELL

(Other)

PULL OR ALTER CASING

MULTIPLE COMPLETE

ABANDON*

CHANGE PLANS

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

FRACTURE TREATMENT

SHOOTING OR ACIDIZING

(Other)

REPAIRING WELL

ALTERING CASING

ABANDONMENT*

(NOTE: Report results of multiple completion on Well
Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

It is proposed to acidize Ratherford Unit #29-33 with 500 gals. 28% HCL and 6000 gals. Super X Emulsion (Dowell Product, 70% - 28% HCL and 30% Diesel mixture). Existing perforations are 5640'-44', 5674'-96', and 5706'-24'. A small pit will be required on location during the workover. Upon completion, the pit will be dried and recovered.

5- BLM Farmington, NM

2- Utah O&GCC, Salt Lake City, Utah

1- P.J. Adamson

1- C. M. Anderson

1- B. Conner 318 - B-TRW

1- J. R. Weichbrodt

1- File

18. I hereby certify that the foregoing is true and correct

SIGNED

TITLE Area Manager

DATE November 26, 1984

(This space for Federal or State office use)

APPROVED BY

TITLE

CONDITIONS OF APPROVAL, IF ANY:

Federal approval of this action
is required before commencing
operations.

*See Instructions on Reverse Side

DATE

BY: John R. Dyer

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN TRIPLICATE
(Other instructions on reverse side)

Form approved
Budget Bureau No. 1004-0135
Expires August 31, 1985

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		3. LEASE DESIGNATION AND SERIAL NO. 14-20-603-407	
2. NAME OF OPERATOR Phillips Oil Company		4. IF INDIAN, ALLOTTEE OR TRIBE NAME Navajo	
5. ADDRESS OF OPERATOR P.O. Box 2920, Casper, Wyoming 82602		7. UNIT AGREEMENT NAME SW-I-4192	
6. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 1860' FSL & 1820' FEL, NW SE		8. FARM OR LEASE NAME Ratherford Unit	
14. PERMIT NO. 43-037-30932		9. WELL NO. 29-33	
15. ELEVATIONS (Show whether DF, ST, OR, etc.) RKB 4972'		10. FIELD AND POOL, OR WILDCAT Greater Aneth	
		11. SEC., T., R., N., OR BLK. AND SURVEY OR AREA Sec. 29-T41S-R24E	
		12. COUNTY OR PARISH San Juan	13. STATE Utah

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETE <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON* <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>
(Other) <input type="checkbox"/>	

SUBSEQUENT REPORT OF:

WATER SHUT-OFF <input type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOTING OR ACIDIZING <input checked="" type="checkbox"/>	ABANDONMENT* <input type="checkbox"/>
(Other) <input type="checkbox"/>	

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

February 2, 1985 through February 9, 1985

PBTD 5744. Acidized w/500 gals 28% MSR100 & 6000 gals Super X Emulsion. Returned to pumping 2/6/85 from Desert Creek Zone I perfs with a final test of 21 BOPD, 7 MCFGPD est., 36 BWPd.

4 - BLM, Farmington, NM
2 - Utah O&GCC, Salt Lake City, Utah
1 - B. A. Conner, B'Ville
1 - File (RC)

18. I hereby certify that the foregoing is true and correct

SIGNED A. E. Stuart TITLE Area Manager DATE 5/13/85

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY:

*See Instructions on Reverse Side

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

Routing:

1	VLC/47-94
2	DTG/58-414
3	VLC
4	RJF
5	DEC
6	PL

Attach all documentation received by the division regarding this change.
 Initial each listed item when completed. Write N/A if item is not applicable.

- ☒ Change of Operator (well sold) ☐ Designation of Agent
☐ Designation of Operator ☐ Operator Name Change Only

The operator of the well(s) listed below has changed (EFFECTIVE DATE: 7-1-93)

TO (new operator)	<u>M E P N A</u>	FROM (former operator)	<u>PHILLIPS PETROLEUM COMPANY</u>
(address)	<u>PO DRAWER G</u>	(address)	<u>5525 HWY 64 NBU 3004</u>
	<u>CORTEZ, CO 81321</u>		<u>FARMINGTON, NM 87401</u>
	<u>GLEN COX (915)688-2114</u>		<u>PAT KONKEL</u>
	<u>phone (303) 565-2212</u>		<u>phone (505) 599-3452</u>
	<u>account no. N7370</u>		<u>account no. N0772(A)</u>

Well(s) (attach additional page if needed):

***RATHERFORD UNIT (NAVAJO)**

Name: **SEE ATTACHED**	API: <u>43-037-30932</u>	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____

OPERATOR CHANGE DOCUMENTATION

- See 1. (Rule R615-8-10) Sundry or other legal documentation has been received from former operator (Attach to this form). *(Reg. 8-20-93) (6/93 Prod. Rpt. 8-16-93)*
- See 2. (Rule R615-8-10) Sundry or other legal documentation has been received from new operator (Attach to this form). *(Reg. 8-31-93) (Rec'd 9-14-93)*
- N/A 3. The Department of Commerce has been contacted if the new operator above is not currently operating any wells in Utah. Is company registered with the state? (yes/no) _____ If yes, show company file number: _____.
- See 4. (For Indian and Federal Wells ONLY) The BLM has been contacted regarding this change (attach Telephone Documentation Form to this report). Make note of BLM status in comments section of this form. Management review of Federal and Indian well operator changes should take place prior to completion of steps 5 through 9 below.
- See 5. Changes have been entered in the Oil and Gas Information System (Wang/IBM) for each well listed above. *(O&G wells 10-6-93) (Wiw's 10-26-93)*
- See 6. Cardex file has been updated for each well listed above. *(O&G wells 10-6-93) (Wiw's 10-26-93)*
- See 7. Well file labels have been updated for each well listed above. *(O&G wells 10-6-93) (Wiw's 10-26-93)*
- See 8. Changes have been included on the monthly "Operator, Address, and Account Changes" memo for distribution to State Lands and the Tax Commission. *(10-6-93)*
- See 9. A folder has been set up for the Operator Change file, and a copy of this page has been placed there for reference during routing and processing of the original documents.

ENTITY REVIEW

- Lee 1. (Rule R615-8-7) Entity assignments have been reviewed for all wells listed above. Were entity changes made? (yes/no) no (If entity assignments were changed, attach copies of Form 6, Entity Action Form).
- N/A 2. State Lands and the Tax Commission have been notified through normal procedures of entity changes.

BOND VERIFICATION (Fee wells only)

- Lee 1. (Rule R615-3-1) The new operator of any fee lease well listed above has furnished a proper bond.
- N/A 2. A copy of this form has been placed in the new and former operators' bond files.
3. The former operator has requested a release of liability from their bond (yes/no) . Today's date 19 . If yes, division response was made by letter dated 19 .

LEASE INTEREST OWNER NOTIFICATION RESPONSIBILITY

- Lee 1. (Rule R615-2-10) The former operator/lessee of any fee lease well listed above has been notified by letter dated 19 , of their responsibility to notify any person with an interest in such lease of the change of operator. Documentation of such notification has been requested.
- N/A 2. Copies of documents have been sent to State Lands for changes involving State leases.

FILMING

- ✓ 1. All attachments to this form have been microfilmed. Date: 11/17 1993.

FILING

- Lee 1. Copies of all attachments to this form have been filed in each well file.
- Lee 2. The original of this form and the original attachments have been filed in the Operator Change file.

COMMENTS

931006 BIA/Bhm Approved 7-9-93.

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

Page 1 of 10

MONTHLY OIL AND GAS PRODUCTION REPORT

OPERATOR NAME AND ADDRESS:

P J KONKEL
PHILLIPS PETROLEUM COMPANY
5525 HWY 64 NBU 3004
FARMINGTON NM 87401

RECEIVED

AUG 16 1993

ACCOUNT NUMBER: N0772

REPORT PERIOD (MONTH/YEAR):

6 / 93

DIVISION OF
OIL, GAS & MININGAMENDED REPORT ☐ (Highlight Changes)

Well Name					Producing Zone	Well Status	Days Oper	Production Volumes		
API Number	Entity	Location						OIL(BBL)	GAS(MCF)	WATER(BBL)
#21-23					DSCR	POW	29	1374	883	58
4303713754	06280	41S	24E	21						
#3-44					DSCR	POW	30	111	94	2905
4303715031	06280	41S	24E	3						
#3-14					DSCR	POW	30	67	23	302
4303715124	06280	41S	24E	3						
#9-12					DSCR	POW	30	112	654	17363
4303715126	06280	41S	24E	9						
#9-14					DSCR	POW	30	201	315	423
4303715127	06280	41S	24E	9						
#28-12					PRDX	POW	29	112	47	2428
4303715336	06280	41S	24E	28						
#29-12					PRDX	POW	29	56	0	672
4303715337	06280	41S	24E	29						
#29-32					DSCR	POW	29	1402	287	2224
4303715339	06280	41S	24E	29						
#29-34					DSCR	POW	29	757	48	0
4303715340	06280	41S	24E	29						
#30-32					DSCR	POW	29	588	1049	3744
4303715342	06280	41S	24E	30						
#3-12					DSCR	POW	30	268	11	363
4303715620	06280	41S	24E	3						
#9-34					DSCR	POW	30	45	46	9800
4303715711	06280	41S	24E	9						
#10-12					DSCR	POW	30	45	23	1088
4303715712	06280	41S	24E	10						
TOTALS								5138	3480	41370

COMMENTS: Effective July 1, 1993, Phillips Petroleum Company has sold its interest in the
 Ratherford Unit to Mobil Exploration and Producing U.S., Incorporated, P. O. Box
 633, Midland, Texas 79702. Mobil assumed operations on July 1, 1993.

I hereby certify that this report is true and complete to the best of my knowledge:

Date: 8/11/93

Name and Signature: PAT KONKEL

Pat Konkell

Telephone Number: 505 599-3452

✓ 19W-21	43-037-15741	14-20-603-353	SEC. 19, T41S, R24E	NE/NW 660' FNL 1860' FWL
✓ 19-22	43-037-31046	14-20-603-353	SEC. 19, T41S, R24E	SE/NW 1840' FNL; 1980' FWL
✓ 19W-23	43-037-15742	14-20-603-353	SEC. 19, T41S, R24E	NE/SW 2080' FSL; 1860' FWL
✓ 19-31	43-037-31047	14-20-603-353	SEC. 19, T41S, R24E	NW/NE 510' FNL; 1980' FEL
✓ 19-32	43-037-15743	14-20-603-353	SEC. 19, T41S, R24E	SW/NE 1980' FNL; 1980' FEL
✓ 19-33	43-037-31048	14-20-603-353	SEC. 19, T41S, R24E	NW/SE 1980' FSL; 1980' FEL
✓ 19-34	43-037-15744	14-20-603-353	SEC. 19, T41S, R24E	SW/SE 660' FSL; 1980' FEL
✓ 19W-41	43-037-15745	14-20-603-353	SEC. 19, T41S, R24E	NE/NE 660' FNL; 660' FEL
✓ 19-42	43-037-30916	14-20-603-353	SEC. 19, T41S, R24E	SE/NE 1880' FNL, 660' FEL
✓ 19W-43	43-037-16420	14-20-603-353	SEC. 19, T41S, R24E	NE/SE 1980' FSL; 760' FEL
✓ 19-44	43-037-31081	14-20-603-353	SEC. 19, T41S, R24E	SE/SE 660' FSL; 660' FEL
✓ 19-97	43-037-31596	14-20-603-353	SEC. 19, T41S, R24E	2562' FNL, 30' FEL
✓ 20-11	43-037-31049	14-20-603-353	SEC. 20, T41S, R24E	NW/NW 500' FNL; 660' FWL
✓ 20-12	43-037-15746	14-20-603-353	SEC. 20, T41S, R24E	1980' FNL, 660' FWL
✓ 20-13	43-037-30917	14-20-603-353	SEC. 20, T41S, R24E	NW/SW 2140' FSL, 500' FWL
✓ 20-14	43-037-15747	14-20-603-353	SEC. 20, T41S, R24E	660' FSL; 660' FWL
✓ 20W-21	43-037-16423	14-20-603-353	SEC. 20, T41S, R24E	660' FNL; 1880' FWL
✓ 20-22	43-037-30930	14-20-603-353	SEC. 20, T41S, R24E	SE/NW 2020' FNL; 2090' FWL
✓ 20W-23	43-037-15748	14-20-603-353	SEC. 20, T41S, R24E	NW/SW 2080; 2120' FWL
✓ 20-24	43-037-30918	14-20-603-353	SEC. 20, T41S, R24E	SE/SW 820' FSL; 1820' FWL
✓ 20-31	43-037-31050	14-20-603-353	SEC. 20, T41S, R24E	NW/NE 660' FNL; 1880' FEL
✓ 20-32	43-037-15749	14-20-603-353	SEC. 20, T41S, R24E	SW/NE 1980' FNL, 1980' FEL
✓ 20-33	43-037-30931	14-20-603-353	SEC. 20, T41S, R24E	NW/SE 1910' FSL; 2140' FEL
✓ 20-34	43-037-15750	14-20-603-353	SEC. 20, T41S, R24E	660' FSL; 1850' FEL
✓ 20W-41	43-037-15751	14-20-603-353	SEC. 20, T41S, R24E	NE/NE 660' FNL; 660' FEL
✓ 20-42	43-037-31051	14-20-603-353	SEC. 20, T41S, R24E	SE/NE 1980' FNL; 660' FEL
✓ 20W-43	43-037-16424	14-20-603-353	SEC. 20, T41S, R24E	2070' FSL; 810' FEL
✓ 20-44	43-037-30915	14-20-603-353	SEC. 20, T41S, R24E	SE/SE 620' FSL; 760' FEL
✓ 20-66	43-037-31592	14-20-603-353	SEC. 20, T41S, R24E	SW/NW 1221' FWL; 1369' FNL
✓ 21-11	43-037-31052	14-20-603-355	SEC. 21, T41S, R24E	NW/NW 660' FNL; 660' FWL
✓ 21-12	43-037-15752	14-20-603-355	SEC. 21, T41S, R24E	2080' FNL; 660' FWL
✓ 21-13	43-037-30921	14-20-603-355	SEC. 21, T41S, R24E	NW/SW 2030' FSL; 515' FWL
✓ 21-14	43-037-15753	14-20-603-355	SEC. 21, T41S, R24E	SW/SW 660' FSL; 460' FWL
✓ 21W-21	43-037-16425	14-20-603-355	SEC. 21, T41S, R24E	NE/NW 660' FNL; 2030' FWL
✓ 21-32	43-037-15755	14-20-603-355	SEC. 21, T41S, R24E	SW/NE 1880' FNL; 1980' FEL
✓ 21-33	NA	14-20-603-355	SEC. 21, T41S, R24E	2000' FSL; 1860' FEL
✓ 21-34	43-037-15756	14-20-603-355	SEC. 21, T41S, R24E	SW/SE 660' FSL; 1980' FEL
✓ 21W-41	43-037-16426	14-20-603-355	SEC. 21, T41S, R24E	660' FNL; 810' FEL
✓ 21W-43	43-037-16427	14-20-603-355	SEC. 21, T41S, R24E	NE/NE 1980' FSL; 660' FEL
✓ 24-11	43-037-15861	14-20-603-247A	SEC. 24, T41S, R24E	510' FNL; 810' FWL
✓ 24W-21	43-037-16429	14-20-603-247	SEC. 24, T41S, R24E	4695' FSL; 3300' FEL
✓ 24W-43	43-037-16430	14-20-603-247	SEC. 24, T41S, R24E	2080' FSL; 660' FEL
✓ 24-31W	43-037-15862	14-20-603-247A	SEC. 24, T41S, R24E	NW/NE 560' FNL; 1830' FEL
✓ 24-32	43-037-31593	14-20-603-247A	SEC. 24, T41S, R24E	SW/NE 2121' FNL; 1846' FEL
✓ 24-41	43-037-31132	14-20-603-247A	SEC. 24, T41S, R24E	NE/NE 660' FNL; 710' FEL
✓ 24W-42	43-037-15863	14-20-603-247A	SEC. 24, T41S, R24E	660' FSL; 1980' FNL
✓ 28-11	43-037-30446	14-20-603-409	SEC. 28, T41S, R24E	NW/NW 520' FNL; 620' FWL
✓ 28-12	43-037-15336	14-20-603-409B	SEC. 28, T41S, R24E	SW/SE/NW 2121' FNL; 623' FWL
✓ 29-11	43-037-31053	14-20-603-407	SEC. 29, T41S, R24E	NW/NW 770' FNL; 585' FWL
✓ 29W-21	43-037-16432	14-20-603-407	SEC. 29, T41S, R24E	NE/NW 667' FNL; 2122' FWL
✓ 29-22	43-037-31082	14-20-603-407	SEC. 29, T41S, R24E	SE/NW 2130' FNL; 1370' FWL
✓ 29W-23	43-037-15338	14-20-603-407	SEC. 29, T41S, R24E	NE/SW 1846' FSL; 1832' FWL
✓ 29-31	43-037-30914	14-20-603-407	SEC. 29, T41S, R24E	NW/NE 700' FNL; 2140' FEL
✓ 29-32	43-037-15339	14-20-603-407	SEC. 29, T41S, R24E	1951' FNL; 1755' FEL
* 29-33	43-037-30932	14-20-603-407	SEC. 29, T41S, R24E	NW/SE 1860' FSL; 1820' FEL
✓ 29-34	43-037-15340	14-20-603-407	SEC. 29, T41S, R24E	817' FSL; 2096' FEL
✓ 29W-41	43-037-16433	14-20-603-407	SEC. 29, T41S, R24E	557' FNL; 591' FEL
✓ 29W-42	43-037-30937	14-20-603-407	SEC. 29, T41S, R24E	SE/NE 1850' FNL; 660' FEL
✓ 29W-43	43-037-16434	14-20-603-407	SEC. 29, T41S, R24E	NE/SE 1980' FSL; 660' FEL
✓ 30-21W	43-037-16435	14-20-603-407	SEC. 30, T41S, R24E	660' FNL; 1920' FWL
✓ 30-32	43-037-15342	14-20-603-407	SEC. 30, T41S, R24E	SW/NE 1975' FNL; 2010' FEL
✓ 30W-41	43-037-15343	14-20-603-407	SEC. 30, T41S, R24E	NE/NE 660' FNL; 660' FEL
✓ 9-34	NA 4303715711	NA 14206034043	NA SEC. 9, T. 41S, R. 24E	NA SWSE 660' FSL 1980' FEL
✓ 12-43	43-307-31202	14-20-603-246	SEC. 12, T41S, R23E	2100' FSL; 660' FEL
✓ 12W31	43-037-15847	14-20-603-246	SEC. 12, T41S, R23E	661' FNL; 1981' FEL
✓ 13W24	43-037-15853	14-20-603-247	SEC. 13, T41S, R23E	SE/SW 660' FSL; 3300' FEL
✓ 15W23	43-037-16412	14-20-603-355	SEC. 15, T41S, R24E	2140' FSL; 1820' FWL
✓ 17-24	43-037-31044	14-20-603-353	SEC. 17, T41S, R24E	SE/SW 720' FSL; 1980' FWL
✓ 18-13	43-037-15734	14-20-603-353	SEC. 18, T41S, R24E	NW/NW 1980' FSL; 500' FWL
✓ 18W32	43-037-15736	14-20-603-353	SEC. 18, T41S, R24E	SW/NE 2140' FNL; 1830' FEL
✓ 20-68	43-037-31591	14-20-603-353	SEC. 20, T41S, R24E	NW/SW 1276' FWL; 1615' FSL
✓ 21-23	43-037-13754	14-20-603-355	SEC. 21, T41S, R24E	NE/SW 1740' FSL 1740' FWL
✓ 28W21	43-037-16431	14-20-603-409	SEC. 29, T41S, R24E	660' FNL; 2022' FWL

PAID

PAID

PAID

PAID

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

<p align="center">SUNDRY NOTICES AND REPORTS ON WELLS</p> <p align="center">(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT—" for such proposals.)</p>		5. LEASE DESIGNATION & SERIAL NO.	
		6. IF INDIAN ALLOTTEE OR TRIBE NAME NAVAJO TRIBAL	
1. OIL WELL <input type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		7. UNIT AGREEMENT NAME RATHERFORD UNIT	
2. NAME OF OPERATOR MOBIL OIL CORPORATION		8. FARM OR LEASE NAME	
3. ADDRESS OF OPERATOR P. O. BOX 633 MIDLAND, TX 79702		9. WELL NO.	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.) At surface At proposed prod. zone		10. FIELD AND POOL, OR WILDCAT GREATER ANETH	
11. SEC., T., R., N., OR BLK. AND SURVEY OR AREA		12. COUNTY SAN JUAN	
13. STATE UTAH		14. API NO.	
15. ELEVATIONS (Show whether DF, RT, GR, etc.)		16. COUNTY SAN JUAN	

16. Check Appropriate Box To Indicate Nature of Notice, Report or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐

FRACTURE TREAT ☐

SHOOT OR ACIDIZE ☐

REPAIR WELL ☐

(Other) ☐

PULL OR ALTER CASING ☐

MULTIPLE COMPLETE ☐

ABANDON ☐

CHANGE PLANS ☐

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐

FRACTURE TREATMENT ☐

SHOOTING OR ACIDIZING ☐

(Other) CHANGE OF OPERATOR ☐

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

REPAIRING WELL ☐

ALTERING CASING ☐

ABANDONMENT* ☐

APPROX. DATE WORK WILL START _____

DATE OF COMPLETION _____

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

* Must be accompanied by a cement verification report.

AS OF JULY1, 1993, MOBIL OIL CORPORATION IS THE OPERATOR OF THE RATHERFORD UNIT.
ATTACHED ARE THE INDIVIDUAL WELLS.

18. I hereby certify that the foregoing is true and correct

SIGNED

Shirley Todd

TITLE

ENV. & REG TECHNICIAN

DATE

9-8-93

(This space for Federal or State office use)

APPROVED BY _____

TITLE _____

DATE _____

CONDITIONS OF APPROVAL, IF ANY:

See Instructions On Reverse Side

MONTHLY OIL AND GAS DISPOSITION REPORT

OPERATOR NAME AND ADDRESS:

L B Sheffield~~BRIAN BERRY~~~~M E P N A MOBIL~~~~POB 249031 1807A RENTWY~~ *P.O. DRAWER 6*~~DALLAS TX 75221-9031~~ *CORTEZ, Co. 81321*UTAH ACCOUNT NUMBER: N7370REPORT PERIOD (MONTH/YEAR): 7 / 93AMENDED REPORT ☐ (Highlight Changes)**931006 updated.
Jee*

ENTITY NUMBER	PRODUCT	GRAVITY	BEGINNING INVENTORY	VOLUME PRODUCED	DISPOSITIONS				ENDING INVENTORY
		BTU			TRANSPORTED	USED ON SITE	FLARED/VENTED	OTHER	
05980	OIL			177609	177609	0			
	GAS			72101	66216	5885			
11174	OIL								
	GAS								
	OIL								
	GAS								
	OIL								
	GAS								
	OIL								
	GAS								
	OIL								
	GAS								
	OIL								
	GAS								
TOTALS				249710	243825	5885			

COMMENTS: *PLEASE NOTE Address change. Mobil ASGO PRODUCTION REPORTS
Will be compiled and sent from the Cortez, Co. office
IN THE FUTURE.*

I hereby certify that this report is true and complete to the best of my knowledge.

Name and Signature:

L B Sheffield

Date:

9/5/93

Telephone Number

*303.565.2212
244.658.2528*

Sept 29, 1993

TO: Lisha Cordova - Utah Mining
Oil & Gas

FROM: Janice Easley
BLM Farmington, NM
505 599-6355

Here is copy of Rutherford Unit
Successor Operator.

4 pages including this one.

File Ratherford Unit (GC)

RECEIVED
BLM

JUL 27 AM 11:44

Navajo Area Office
P. O. Box 1060
Gallup, New Mexico 87305-1060

070 FARMINGTON, NM

ARES/543

JUL 28 1993


Mr. G. D. Cox
Mobil Exploration and
Producing North America, Inc.
P. O. Box 633
Midland, Texas 79702

Dear Mr. Cox:

Enclosed for your information and use is the approved Designation of Operator between the Phillips Petroleum Company and Mobil Exploration and Producing North America, Inc. for the Ratherford Unit.

Please note that all other concerned parties will be furnished their copy of the approved document.

Sincerely,



ACTING Area Director

Enclosure

cc: Bureau of Land Management, Farmington District Office w/enc.
TNN, Director, Minerals Department w/enc.

MINERAL	DATE
NO. 1	93
FILED	
3	
2	
FILED	
ALL COPY	
FILED	

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF INDIAN AFFAIRS

DESIGNATION OF OPERATOR

RECEIVED
BLM

Phillips Petroleum Company is, on the records of the Bureau of Indian Affairs, operator of the Ratherford Unit,

AREA OFFICE: Window Rock, Arizona
LEASE NO: Attached hereto as Exhibit "A"

070 FARMINGTON, NM

and, pursuant to the terms of the Ratherford Unit Agreement, is resigning as Unit Operator effective July 1, 1993, and hereby designates

NAME: Mobil Exploration and Producing North America Inc., duly elected pursuant to the terms of the Ratherford Unit Agreement,

ADDRESS: P. O. Box 633, Midland, Texas 79702
Attn: G. D. Cox

as Operator and local agent, with full authority to act on behalf of the Ratherford Unit lessees in complying with the terms of all leases and regulations applicable thereto and on whom the authorized officer may serve written or oral instructions in securing compliance with the Operating Regulations (43 CFR 3160 and 25 CFR 211 and 212) with respect to (described acreage to which this designation is applicable):

Attached hereto as Exhibit "A"

Bond coverage under 25 CFR 211, 212 or 225 for lease activities conducted by the above named designated operator is under Bond Number 05202782 (attach copy). Evidence of bonding is required prior to the commencement of operations.

It is understood that this designation of operator does not relieve any lessee of responsibility for compliance with the terms of the leases and the Operating Regulations. It is also understood that this designation of operator does not constitute an assignment of any interest in the leases.

In case of default on the part of the designated operator, the lessees will make full and prompt compliance with all regulations, lease terms, stipulations, or orders of the Secretary of the Interior or his representative.

Attached is the appropriate documentation relevant to this document.

The designated operator agrees to promptly notify the authorized officer of any change in the operatorship of said Ratherford Unit.

Phillips Petroleum Company

June 17, 1993

By: M. B. [Signature]
Attorney-in-Fact

Mobil Exploration and Producing
North America Inc.

June 11, 1993

By: B. D. Martiny
Attorney-in-Fact B.D. MARTINY

[Signature]
APPROVED BY

ACTING AREA DIRECTOR
TITLE

7/9/93
DATE

APPROVED PURSUANT, TO SECRETARIAL REDELEGATION ORDER 209 DM 8 AND 230 DM 3.

This form does not constitute an information collection as defined by 44 U.S.C. 3502 and therefore does not require OMB approval.

EXHIBIT "A"

ATTACHED TO AND MADE A PART OF DESIGNATION OF SUCCESSOR OPERATOR, RATHERFORD UNIT

EXHIBIT "C"

Revised as of September 29, 1992
SCHEDULE OF TRACT PERCENTAGE PARTICIPATION

<u>Tract Number</u>	<u>Description of Land</u>	<u>Serial Number and Effective Date of Lease</u>	<u>Tract Percentage Participation</u>
1	S/2 Sec. 1, E/2 SE/4 Sec. 2, E/4 Sec. 11, and all of Sec. 12, T-41-S, R-23-E, S.L.M. San Juan County, Utah	14-20-603-246-A Oct. 5, 1953	11.0652565
2	SE/4 and W/2 SW/4 Sec. 5, the irregular SW/4 Sec. 6, and all of Sec. 7 and 8, T-41-S, R-24-E, San Juan County, Utah	14-20-603-368 Oct. 26, 1953	14.4159942
3	SW/4 of Sec. 4, T-41-S, R-24-E, San Juan County, Utah	14-20-603-5446 Sept. 1, 1959	.5763826
4	SE/4 Sec. 4, and NE/4 Sec. 9, T-41-S, R-24-E, San Juan County, Utah	14-20-603-4035 March 3, 1958	1.2587779
5	SW/4 of Sec. 3, T-41-S, R-24-E, S.L.M., San Juan County, Utah	14-20-603-5445 Sept. 3, 1959	.4667669
6	NW/4 of Sec. 9, T-41-S, R-24-E, S.L.M., San Juan County, Utah	14-20-603-5045 Feb. 4, 1959	1.0187043
7	NW/4, W/2 NE/4, and SW/4 Sec. 10, SE/4 Sec. 9, T-41-S, R-24-E, San Juan County, Utah	14-20-603-4043 Feb. 18, 1958	3.5097575
8	SW/4 Sec. 9, T-41-S, R-24-E, S.L.M. San Juan County, Utah	14-20-603-5046 Feb. 4, 1959	1.1141679
9	SE/4 Sec. 10 and S/2 SW/4 Sec. 11 T-41-S, R-24-E, San Juan County, Utah	14-20-603-4037 Feb. 14, 1958	2.6186804
10	All of Sec. 13, E/2 Sec. 14, and E/2 SE/4 and N/2 Sec. 24, T-41-S, R-23-E, S.L.M., San Juan County, Utah	14-20-603-247-A Oct. 5, 1953	10.3108861
11	Sections 17, 18, 19 and 20, T-41-S, R-24-E, San Juan County Utah	14-20-603-353 Oct. 27, 1953	27.3389265
12	Sections 15, 16, 21, and NW/4, and W/2 SW/4 Sec. 22, T-41-S, R-24-E, San Juan County, Utah	14-20-603-355 Oct. 27, 1953	14.2819339
13	W/2 Section 14, T-41-S, R-24-E, San Juan County, Utah	14-20-603-370 Oct. 26, 1953	1.8500847
14	N/2 and SE/4, and E/2 SW/4 Sec. 29, NE/4 and E/2 SE/4 and E/2 W/2 irregular Sec. 30, and E/2 NE/4 Sec. 32, T-41-S, R-24-E, San Juan County, Utah	14-20-603-407 Dec. 10, 1953	6.9924969
15	NW/4 Sec. 28, T-41-S, R24-E San Juan County, Utah	14-20-603-409 Dec. 10, 1953	.9416393
16	SE/4 Sec. 3, T-41-S, R-24-E San Juan County, Utah	14-20-0603-6504 July 11, 1961	.5750254
17	NE/4 Sec. 3, T-41-S, R-24-E San Juan County, Utah	14-20-0603-6505 July 11, 1961	.5449292
18	NW/4 Sec. 3, T-41-S, R-24-E San Juan County, Utah	14-20-0603-6506 July 11, 1961	.5482788
19	NE/4 Sec. 4, T-41-S, R24-E San Juan County, Utah	14-20-0603-7171 June 11, 1962	.4720628
20	E/2 NW/4 Sec. 4, T-41-S, R-24-E San Juan County, Utah	14-20-0603-7172 June 11, 1962	.0992482
100%	Indian Lands	TOTAL 12,909.74	100.0000000

Division of Oil, Gas and Mining
PHONE CONVERSATION DOCUMENTATION FORM

Route original/copy to:

☐ Well File _____

☐ Suspense
(Return Date) _____
(To - Initials) _____

☒ Other
OPERATOR CHANGE

(Location) Sec _____ Twp _____ Rng _____
(API No.) _____

1. Date of Phone Call: 10-6-93 : Time: 9:30

2. DOGM Employee (name) L. CORDOVA (Initiated Call ☒
Talked to:

Name GLEN COX (Initiated Call ☐ - Phone No. (915) 688-2114

of (Company/Organization) MOBIL

3. Topic of Conversation: OPERATOR CHANGE FROM PHILLIPS TO MOBIL "RATHERFORD UNIT".
(NEED TO CONFIRM HOW OPERATOR WANTS THE WELLS SET UP - MEPNA AS PER BIA APPROVAL
OR MOBIL OIL CORPORATION AS PER SUNDRY DATED 9-8-93?)

4. Highlights of Conversation: _____
MR. COX CONFIRMED THAT THE WELLS SHOULD BE SET UNDER ACCOUNT N7370/MEPNA AS
PER BIA APPROVAL, ALSO CONFIRMED THAT PRODUCTION & DISPOSITION REPORTS WILL NOW
BE HANDLED OUT OF THEIR CORTEZ OFFICE RATHER THAN DALLAS.

MEPNA-

PO DRAWER G

CORTEZ, CO 81321

(303) 565-2212

*ADDRESS CHANGE AFFECTS ALL WELLS CURRENTLY OPERATED BY MEPNA, CURRENTLY
REPORTED OUT OF DALLAS (MCELMO CREEK).

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

Routing:

1-LEC	7-PL
2-LWP	8-SJ
3-DES	9-FILE
4-VLC	
5-RJF	
6-LWP	

Attach all documentation received by the division regarding this change.
 Initial each listed item when completed. Write N/A if item is not applicable.

- ☐ Change of Operator (well sold) ☐ Designation of Agent
☐ Designation of Operator ☒ Operator Name Change Only

The operator of the well(s) listed below has changed (EFFECTIVE DATE: 8-2-95)

TO (new operator) MOBIL EXPLOR & PROD
 (address) C/O MOBIL OIL CORP
PO DRAWER G
CORTEZ CO 81321
 phone (303) 564-5212
 account no. N7370

FROM (former operator) M E P N A
 (address) C/O MOBIL OIL CORP
PO DRAWER G
CORTEZ CO 81321
 phone (303) 564-5212
 account no. N7370

Well(s) (attach additional page if needed):

Name: ** SEE ATTACHED **	API: <u>037 30932</u>	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____
Name: _____	API: _____	Entity: _____	Sec _____	Twp _____	Rng _____	Lease Type: _____

OPERATOR CHANGE DOCUMENTATION

- N/A 1. (Rule R615-8-10) Sundry or other legal documentation has been received from former operator (Attach to this form).
- N/A 2. (Rule R615-8-10) Sundry or other legal documentation has been received from new operator (Attach to this form).
- N/A 3. The Department of Commerce has been contacted if the new operator above is not currently operating any wells in Utah. Is company registered with the state? (yes/no) ____ If yes, show company file number: _____.
- N/A 4. (For Indian and Federal Wells ONLY) The BLM has been contacted regarding this change (attach Telephone Documentation Form to this report). Make note of BLM status in comments section of this form. Management review of Federal and Indian well operator changes should take place prior to completion of steps 5 through 9 below.
- Le 5. Changes have been entered in the Oil and Gas Information System (Wang/IBM) for each well listed above. (8-3-95)
- LWP 6. Cardex file has been updated for each well listed above. 8-21-95
- LWP 7. Well file labels have been updated for each well listed above. 9-28-95
- Le 8. Changes have been included on the monthly "Operator, Address, and Account Changes" memo for distribution to State Lands and the Tax Commission. (8-3-95)
- Le 9. A folder has been set up for the Operator Change file, and a copy of this page has been placed there for reference during routing and processing of the original documents.

ENTITY REVIEW

- Lee* 1. (Rule R615-8-7) Entity assignments have been reviewed for all wells listed above. Were entity changes made? (yes/no) no (If entity assignments were changed, attach copies of Form 6, Entity Action Form).
- N/A* 2. State Lands and the Tax Commission have been notified through normal procedures of entity changes.

BOND VERIFICATION (Fee wells only)

** No Fee Lease Wells at this time!*

- N/A Lee* 1. (Rule R615-3-1) The new operator of any fee lease well listed above has furnished a proper bond.
- ___ 2. A copy of this form has been placed in the new and former operators' bond files.
- ___ 3. The former operator has requested a release of liability from their bond (yes/no) _____. Today's date _____ 19____. If yes, division response was made by letter dated _____ 19____.

LEASE INTEREST OWNER NOTIFICATION RESPONSIBILITY

- N/A* 1. (Rule R615-2-10) The former operator/lessee of any **fee lease** well listed above has been notified by letter dated _____ 19____, of their responsibility to notify any person with an interest in such lease of the change of operator. Documentation of such notification has been requested.
- OTS 8/5/95*
- N/A* 2. Copies of documents have been sent to State Lands for changes involving State leases.

FILMING

- ✓* 1. All attachments to this form have been microfilmed. Date: October 6 1995.

FILING

- ___ 1. Copies of all attachments to this form have been filed in each well file.
- ___ 2. The original of this form and the original attachments have been filed in the Operator Change file.

COMMENTS

950803 UIC F5/Not necessary!

STATE OF UTAH

DIVISION OF OIL, GAS AND MINING

355 West North Temple, 3 Triad, Suite 350, Salt Lake City, UT 84180-1203

Page 18 of 22

MONTHLY OIL AND GAS PRODUCTION REPORT

OPERATOR NAME AND ADDRESS:

C/O MOBIL OIL CORP
M E P N A
PO DRAWER G
CORTEZ CO 81321

UTAH ACCOUNT NUMBER: N7370

REPORT PERIOD (MONTH/YEAR): 6 / 95

AMENDED REPORT ☐ (Highlight Changes)

Well Name			Producing Zone	Well Status	Days Oper	Production Volumes		
API Number	Entity	Location				OIL(BBL)	GAS(MCF)	WATER(BBL)
#20-13								
4303730917	06280	41S 24E 20	DSCR					
#20-24								
4303730918	06280	41S 24E 20	DSCR					
#21-13								
4303730921	06280	41S 24E 21	DSCR					
#20-22								
4303730930	06280	41S 24E 20	DSCR					
RATHERFORD UNIT 20-33								
4303730931	06280	41S 24E 20	DSCR					
#29-33								
4303730932	06280	41S 24E 29	IS-DC					
RATHERFORD UNIT 29-42								
4303730937	06280	41S 24E 29	DSCR					
RATHERFORD UNIT 17-24								
4303731044	06280	41S 24E 17	DSCR					
RATHERFORD UNIT 18-44								
4303731045	06280	41S 24E 18	DSCR					
RATHERFORD UNIT 19-22								
4303731046	06280	41S 24E 19	DSCR					
RATHERFORD UNIT 19-31								
4303731047	06280	41S 24E 19	DSCR					
RATHERFORD UNIT 19-33								
4303731048	06280	41S 24E 19	DSCR					
RATHERFORD UNIT 20-11								
4303731049	06280	41S 24E 20	DSCR					
TOTALS								

COMMENTS:

I hereby certify that this report is true and complete to the best of my knowledge.

Date: _____

Name and Signature: _____

Telephone Number: _____

PHONE CONVERSATION DOCUMENTATION FORM

Route original/copy to:

☐ **Well File** _____

☐ **Suspense**
(Return Date) _____

☒ **Other**
OPER NM CHG _____

(Location) Sec _____ Twp _____ Rng _____

(To - Initials) _____

(API No.) _____

1. Date of Phone Call: 8-3-95 Time: _____

2. DOGM Employee (name) L. CORDOVA (Initiated Call ☐)
Talked to:

Name R. J. FIRTH (Initiated Call ☒) - Phone No. () _____

of (Company/Organization) _____

3. Topic of Conversation: M E P N A / N7370

4. Highlights of Conversation: _____

OPERATOR NAME IS BEING CHANGED FROM M E P N A (MOBIL EXPLORATION AND PRODUCING

NORTH AMERICA INC) TO MOBIL EXPLOR & PROD. THE NAME CHANGE IS BEING DONE AT

THIS TIME TO ALLEVIATE CONFUSION, BOTH IN HOUSE AND AMONGST THE GENERAL PUBLIC.

*SUPERIOR OIL COMPANY MERGED INTO M E P N A 4-24-86 (SEE ATTACHED).

Mobil Oil Corporation

P.O. BOX 5444
DENVER, COLORADO 80217-5444

May 14, 1986

RECEIVED
MAY 16 1986

Utah Board of Oil, Gas and Mining
355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203

Attn: R. J. Firth
Associate Director

DIVISION OF
OIL, GAS & MINING

SUPERIOR OIL COMPANY MERGER

Dear Mr. Firth:

On September 20, 1984, The Superior Oil Company (Superior) became a wholly owned subsidiary of Mobil Corporation. Since January 1, 1985, Mobil Oil Corporation (MOC), another wholly owned subsidiary of Mobil Corporation, has acted as agent for Superior and has operated the Superior-owned properties.

On April 24, 1986, Superior was merged with Mobil Exploration and Producing North America Inc. (MEPNA), which is also a wholly owned subsidiary of Mobil Corporation. MEPNA is the surviving company of the merger.

This letter is to advise you that all properties held in the name of Superior will now be held in the name of MEPNA; and that these properties will continue to be operated by MOC as agent for MEPNA.

Attached is a listing of all wells and a separate listing of injection-disposal wells, Designation of Agent and an organization chart illustrating the relationships of the various companies. If you have any questions or require additional documentation of this merger, please feel free to contact me at the above address or (303) 298-2577.

Very truly yours,



CNE/rd
CNE8661

R. D. Baker
Environmental Regulatory Manager

3. FILE

Designation of Agent

Merger

FROM: (Old Operator):

MOBIL EXPLORATION & PRODUCTION

Address: P O BOX DRAWER "G"

CORTEZ, CO 81321

Phone: 1-(970)-564-5212

Account No. N7370

TO: (New Operator):

EXXONMOBIL OIL CORPORATION

Address: U S WEST P O BOX 4358

HOUSTON, TX 77210-4358

Phone: 1-(713)-431-1010

Account No.	N1855
-------------	-------

CA No.

Unit: RATHERFORD

WELL(S)

[illegible]

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 06/29/2001
2. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 06/29/2001
3. The new company has been checked through the **Department of Commerce, Division of Corporations Database** on: 04/09/2002
4. Is the new operator registered in the State of Utah: YES Business Number: 579865-0143
5. If **NO**, the operator was contacted contacted on: N/A

6. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BIA-06/01/01

7. **Federal and Indian Units:**

The BLM or BIA has approved the successor of unit operator for wells listed on: 06/01/2001

8. **Federal and Indian Communization Agreements ("CA"):**

The BLM or BIA has approved the operator for all wells listed within a CA on: N/A

9. **Underground Injection Control ("UIC")**

The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

DATA ENTRY:

1. Changes entered in the **Oil and Gas Database** on: 04/15/2002

2. Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 04/15/2002

3. Bond information entered in RBDMS on: N/A

4. Fee wells attached to bond in RBDMS on: N/A

STATE WELL(S) BOND VERIFICATION:

1. State well(s) covered by Bond Number: N/A

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: N/A

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: 80273197

FEE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number N/A

2. The **FORMER** operator has requested a release of liability from their bond on: N/A
The Division sent response by letter on: N/A

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: N/A

COMMENTS:

ExxonMobil Production Comp
U.S. West
P.O. Box 4358
Houston, Texas 77210-4358

June 27, 2001

ExxonMobil
Production

Mr. Jim Thompson
State of Utah, Division of Oil, Gas and Mining
1549 West North Temple
Suite 1210
Salt Lake City, UT 84114-5801

Change of Name – Mobil Oil Corporation to
ExxonMobil Oil Corporation

Dear Mr. Thompson

Effective June 1, 2001, Mobil Oil Corporation (MOC) changed its name to ExxonMobil Oil Corporation (EMOC). This was a name change only; EMOC is the same corporation as Mobil Oil Corporation, but with a new name. No facility or other asset was transferred from one corporation to another by virtue of the name change. Specifically, EMOC will remain the owner and operator of its existing exploration and production oil and gas properties and facilities, as well as relevant permits.

There is no change to the name of Exxon Mobil Corporation, the ultimate shareholder of EMOC.


Please note the change of name of MOC to ExxonMobil Oil Corporation in your records pertaining to any MOC permits.

The Federal Identification Number for MOC (13-5401570) will remain the same for EMOC.

A copy of the Certification, Bond Rider and a list of wells are attached.

If you have any questions please feel free to call Joel Talavera at 713-431-1010

Very truly yours,



Charlotte H. Harper
Permitting Supervisor

ExxonMobil Production Company
a division of Exxon Mobil Corporation,
acting for ExxonMobil Oil Corporation

RECEIVED

JUN 29 2001

DIVISION OF
OIL GAS AND MINING



IN REPLY REFER TO:

United States Department of the Interior

BUREAU OF INDIAN AFFAIRS

Navajo Area Office

~~XXXXXXXXXXXX~~

NAVAJO REGION

P.O. Box 1060

Gallup, New Mexico 87305-1060

AUG 30 2001

RRES/543

CERTIFIED MAIL - RETURN RECEIPT REQUESTED

Charlotte H. Harper, Permitting Supervisor
 Exxon Mobil Production Company
 U. S. West
 P. O. Box 4358
 Houston, TX 77210-4358

Dear Ms. Harper:

This is to acknowledge receipt of your company's name change from Mobil Oil Corporation to ExxonMobil Oil Corporation effective June 1, 2001. The receipt of documents includes the Name Change Certification, current listing of Officers and Directors, Listing of Leases, Financial Statement, filing fees of \$75.00 and a copy of the Rider for Bond Number 8027 31 97. There are no other changes.

Please note that we will provide copies of these documents to other concerned parties. If you need further assistance, you may contact Ms. Bertha Spencer, Realty Specialist, at (928) 871-5938.

Sincerely,

DENNETSONE

Regional Realty Officer

cc: BLM, Farmington Field Office w/enclosures ✓
 Navajo Nation Minerals Office, Attn: Mr. Akhtar Zaman, Director/w enclosures

MINERAL RESOURCES	
ADM 1	<i>267MC</i>
NATV AM MIN COORD	
SOLID MIN TEAM	
PETRO MIN TEAM	<i>2</i>
O & G INSPECT TEAM	
ALL TEAM LEADERS	
LAND RESOURCES	
ENVIRONMENT	
FILES	

ExxonMobil Production Company
U.S. West
P.O. Box 4358
Houston, Texas 77210-4358


Box 7/1 2/2001
SN
543
File

June 27, 2001

ExxonMobil
Production

Certified Mail
Return Receipt Requested

Ms. Genni Denetsone
United States Department of the Interior
Bureau of Indian Affairs, Navajo Region
Real Estate Services
P. O. Box 1060
Gallup, New Mexico 87305-1060
Mail Code 543



Change of Name -
Mobil Oil Corporation to
ExxonMobil Oil Corporation

Dear Ms. Denetsone:

Effective June 1, 2001, Mobil Oil Corporation (MOC) changed its name to ExxonMobil Oil Corporation (EMOC). This was a name change only; EMOC is the same corporation as Mobil Oil Corporation, but with a new name. No facility or other asset was transferred from one corporation to another by virtue of the name change. Specifically, EMOC will remain the owner and operator of its existing exploration and production oil and gas properties and facilities, as well as relevant permits.

There is no change to the name of Exxon Mobil Corporation, the ultimate shareholder of EMOC.

Please note the change of name of MOC to ExxonMobil Oil Corporation in your records pertaining to any MOC permits.

The Federal Identification Number for MOC (13-5401570) will remain the same for EMOC.

Attached is the Name Change Certification, Current listing of Officers and Directors, Filing Fee of \$75/-. Listing of Leases, Financial Statement and a copy of the Rider for Bond number 8027 31 97. The original Bond Rider has been sent to Ms. Barbar Davis at your Washington Office.


If you have any questions, please contact Alex Correa at (713) 431-1012.

Very truly yours,

Charlotte H. Harper

Charlotte H. Harper
Permitting Supervisor

Attachments



ExxonMobil Production Company
a division of Exxon Mobil Corporation,
acting for ExxonMobil Oil Corporation

NOTE: Check forwarded to Ella Isaac

Bureau of Indian Affairs
Navajo Region Office
Attn: RRES - Mineral and Mining Section
P.O. Box 1060
Gallup, New Mexico 87305-1060

Gentlemen:

The current listing of officers and director of ExxonMobil Oil Corporation (Name of Corporation), of New York (State) is as follows:

OFFICERS

President	<u>F.A. Risch</u>	Address <u>5959 Las Colinas Blvd. Irving, TX 75039</u>
Vice President	<u>K.T. Koonce</u>	Address <u>800 Bell Street Houston, TX 77002</u>
Secretary	<u>F.L. Reid</u>	Address <u>5959 Las Colinas Blvd. Irving, TX 75039</u>
Treasure	<u>B.A. Maher</u>	Address <u>5959 Las Colinas Blvd. Irving, TX 75039</u>

DIRECTORS


Name	<u>D.D. Humphreys</u>	Address <u>5959 Las Colinas Blvd. Irving, TX 75039</u>
Name	<u>P.A. Hanson</u>	Address <u>5959 Las Colinas Blvd. Irving, TX 75039</u>
Name	<u>T.P. Townsend</u>	Address <u>5959 Las Colinas Blvd. Irving, TX 75039</u>
Name	<u>B.A. Maher</u>	Address <u>5959 Las Colinas Blvd. Irving, TX 75039</u>
Name	<u>F.A. Risch</u>	Address <u>5959 Las Colinas Blvd. Irving, TX 75039</u>

Sincerely,



Alex Correa

This is to certify that the above information pertaining to ExxonMobil Oil Corporation (Corporation) is true and correct as evidenced by the records and accounts covering business for the State of Utah and in the custody of Corporation Service Company (Agent), Phone: 1 (800) 927-9800, whose business address is One Utah Center, 201 South Main Street, Salt Lake City, Utah 84111-2218



Signature

AGENT AND ATTORNEY IN FACT

Title

SAL

CERTIFICATION

I, the undersigned Assistant Secretary of ExxonMobil Oil Corporation. (formerly Mobil Oil Corporation), a corporation organized and existing under the laws of the State of New York, United States of America, DO HEREBY CERTIFY, That, the following is a true and exact copy of the resolutions adopted by the Board of Directors on May 22, 2001:

CHANGE OF COMPANY NAME

WHEREAS, the undersigned Directors of the Corporation deem it to be in the best interest of the Corporation to amend the Certificate of Incorporation of the Corporation to change the name and principal office of the Corporation:

NOW THEREFORE BE IT RESOLVED, That Article 1st relating to the corporate name is hereby amended to read as follows:


"1st The corporate name of said Company shall be,

ExxonMobil Oil Corporation",

FURTHER RESOLVED, That the amendment of the Corporation's Certificate of Incorporation referred to in the preceding resolutions be submitted to the sole shareholder of the Corporation entitled to vote thereon for its approval and, if such shareholder gives its written consent, pursuant to Section 803 of the Business Corporation Law of the State of New York, approving such amendment, the proper officers of the Corporation be, and they hereby are, authorized to execute in the name of the Corporation the Certificate of Amendment of Certificate of Incorporation, in the form attached hereto;


FURTHER RESOLVED, That the proper officers of the Corporation be and they hereby are authorized and directed to deliver, file and record in its behalf, the Certificate of Amendment of Certificate of Incorporation, and to take such action as may be deemed necessary or advisable to confirm and make effective in all respects the change of this Company's name to EXXONMOBIL OIL CORPORATION.


WITNESS, my hand and the seal of the Corporation at Irving, Texas, this 8th day of June, 2001.


Assistant Secretary

COUNTY OF DALLAS)
STATE OF TEXAS)
UNITED STATES OF AMERICA)

Sworn to and subscribed before me at Irving, Texas, U. S. A. on this the 8th day of June, 2001.


Notary Public



LISTING OF LEASES OF MOBIL OIL CORPORATION**Lease Number**

- 1) 14-20-0603-6504
- 2) 14-20-0603-6505
- 3) 14-20-0603-6506
- 4) 14-20-0603-6508
- 5) 14-20-0603-6509
- 6) 14-20-0603-6510
- 7) 14-20-0603-7171
- 8) 14-20-0603-7172A
- 9) 14-20-600-3530
- 10) 14-20-603-359
- 11) 14-20-603-368
- 12) 14-20-603-370
- 13) 14-20-603-370A
- 14) 14-20-603-372
- 15) 14-20-603-372A
- 16) 14-20-603-4495
- 17) 14-20-603-5447
- 18) 14-20-603-5448
- 19) 14-20-603-5449
- 20) 14-20-603-5450
- 21) 14-20-603-5451

6/1/01

CHUBB GROUP OF INSURANCE COMPANIES

1000 West Loop South, Suite 1900, Houston, Texas 77027-3301
Telephone: (713) 297-4600 • Facsimile: (713) 297-4750

NW Bond

FEDERAL INSURANCE COMPANY RIDER
to be attached to and form a part of

BOND NO 8027 31 97

wherein

Mobil Oil Corporation and Mobil Exploration and Producing U.S., Inc. is
named as Principal and

FEDERAL INSURANCE COMPANY AS SURETY,

in favor of United States of America, Department of the Interior
Bureau of Indian Affairs

in the amount of \$150,000.00

bond date: 11/01/65

IT IS HEREBY UNDERSTOOD AND AGREED THAT effective June 1, 2001
the name of the Principal is changed

FROM: Mobil Oil Corporation and Mobil Exploration and Producing U.S., Inc.

TO : ExxonMobil Oil Corporation

All other terms and conditions of this Bond are unchanged.

Signed, sealed and dated this 12th of June, 2001.

ExxonMobil Oil Corporation

By: 

FEDERAL INSURANCE COMPANY

By: 

Mary Pierson, Attorney-in-fact

**Chubb
Surety****POWER
OF
ATTORNEY****Federal Insurance Company
Vigilant Insurance Company
Pacific Indemnity Company****Attn.: Surety Department
15 Mountain View Road
Warren, NJ 07059**

Know All by These Presents, That **FEDERAL INSURANCE COMPANY**, an Indiana corporation, **VIGILANT INSURANCE COMPANY**, a New York corporation, and **PACIFIC INDEMNITY COMPANY**, a Wisconsin corporation, do each hereby constitute and appoint **R.F. Bobo**,
Mary Pierson, **Philana Berros**, and **Jody E. Specht** of **Houston, Texas**-----

each as their true and lawful Attorney-in-Fact to execute under such designation in their names and to affix their corporate seals to and deliver for and on their behalf as surety thereon or otherwise, bonds and undertakings and other writings obligatory in the nature thereof (other than bail bonds) given or executed in the course of business, and any instruments amending or altering the same, and consents to the modification or alteration of any instrument referred to in said bonds or obligations.

In Witness Whereof, said **FEDERAL INSURANCE COMPANY**, **VIGILANT INSURANCE COMPANY**, and **PACIFIC INDEMNITY COMPANY** have each executed and attested these presents and affixed their corporate seals on this 10th day of May, 2001.


 Kenneth C. Wendel, Assistant Secretary


 Frank E. Robertson, Vice President

STATE OF NEW JERSEY } ss.
 County of Somerset

On this 10th day of May, 2001, before me, a Notary Public of New Jersey, personally came Kenneth C. Wendel, to me known to be Assistant Secretary of **FEDERAL INSURANCE COMPANY**, **VIGILANT INSURANCE COMPANY**, and **PACIFIC INDEMNITY COMPANY**, the companies which executed the foregoing Power of Attorney, and the said Kenneth C. Wendel being by me duly sworn, did depose and say that he is Assistant Secretary of **FEDERAL INSURANCE COMPANY**, **VIGILANT INSURANCE COMPANY**, and **PACIFIC INDEMNITY COMPANY** and knows the corporate seals thereof, that the seals affixed to the foregoing Power of Attorney are such corporate seals and were thereto affixed by authority of the By-Laws of said Companies; and that he signed said Power of Attorney as Assistant Secretary of said Companies by like authority; and that he is acquainted with Frank E. Robertson, and knows him to be Vice President of said Companies; and that the signature of Frank E. Robertson, subscribed to said Power of Attorney is in the genuine handwriting of Frank E. Robertson, and was thereto subscribed by authority of said Companies in his presence.



Notary Public State of New Jersey
 No. 2231647

Commission Expires Oct 28, 2004


 Karen A. Price

Notary Public

Extract from the By-Laws of **FEDERAL INSURANCE COMPANY**, **VIGILANT INSURANCE COMPANY**, and **PACIFIC INDEMNITY COMPANY**:

"All powers of attorney for and on behalf of the Company may and shall be executed in the name and on behalf of the Company, either by the Chairman or the President or a Vice President or an Assistant Vice President, jointly with the Secretary or an Assistant Secretary, under their respective designations. The signature of such officers may be engraved, printed or lithographed. The signature of each of the following officers: Chairman, President, any Vice President, any Assistant Vice President, any Secretary, any Assistant Secretary and the seal of the Company may be affixed by facsimile to any power of attorney or to any certificate relating thereto appointing Assistant Secretaries or Attorneys-in-Fact for purposes only of executing and attesting bonds and undertakings and other writings obligatory in the nature thereof, and any such power of attorney or certificate bearing such facsimile signature or facsimile seal shall be valid and binding upon the Company and any such power so executed and certified by such facsimile signature and facsimile seal shall be valid and binding upon the Company with respect to any bond or undertaking to which it is attached."

I, Kenneth C. Wendel, Assistant Secretary of **FEDERAL INSURANCE COMPANY**, **VIGILANT INSURANCE COMPANY**, and **PACIFIC INDEMNITY COMPANY** (the "Companies") do hereby certify that

- (i) the foregoing extract of the By-Laws of the Companies is true and correct,
- (ii) the Companies are duly licensed and authorized to transact surety business in all 50 of the United States of America and the District of Columbia and are authorized by the U. S. Treasury Department; further, Federal and Vigilant are licensed in Puerto Rico and the U. S. Virgin Islands, and Federal is licensed in American Samoa, Guam, and each of the Provinces of Canada except Prince Edward Island; and
- (iii) the foregoing Power of Attorney is true, correct and in full force and effect.

Given under my hand and seals of said Companies at Warren, NJ this 12th day of June, 2001




 Kenneth C. Wendel, Assistant Secretary

IN THE EVENT YOU WISH TO NOTIFY US OF A CLAIM, VERIFY THE AUTHENTICITY OF THIS BOND OR NOTIFY US OF ANY OTHER MATTER, PLEASE CONTACT US AT ADDRESS LISTED ABOVE, OR BY
 Telephone (908) 903-3485 Fax (908) 903-3656 e-mail: surety@chubb.com

CSC

5184334741

06/01 '01 08:46 NO.410 03/05

CSC

06/01 '01 09:06 NO.135 02/04

F010601000187

CERTIFICATE OF AMENDMENT
OF
CERTIFICATE OF INCORPORATION
OF
MOBIL OIL CORPORATION

CSC 45

(Under Section 805 of the Business Corporation Law)

Pursuant to the provisions of Section 805 of the Business Corporation Law, the undersigned President and Secretary, respectively, of Mobil Oil Corporation hereby certify:

FIRST: That the name of the corporation is MOBIL OIL CORPORATION and that said corporation was incorporated under the name of Standard Oil Company of New York.

SECOND: That the Certificate of Incorporation of the corporation was filed by the Department of State, Albany, New York, on the 10th day of August, 1882.

THIRD: That the amendments to the Certificate of Incorporation effected by this Certificate are as follows:

(a) Article 1st of the Certificate of Incorporation, relating to the corporate name, is hereby amended to read as follows:

"1st The corporate name of said Company shall be,
ExxonMobil Oil Corporation",

(b) Article 7th of the Certificate of Incorporation, relating to the office of the corporation is hereby amended to read as follows:

The office of the corporation within the State of New York is to be located in the County of Albany. The Company shall have offices at such other places as the Board of Directors may from time to time determine.

CSC
CSC

5184334741

06/01 '01 08:47 NO.410 04/05
06/01 '01 07:00 NO.133 03/04

FOURTH: That the amendments to the Certificate of Incorporation were authorized by the Board of Directors followed by the holder of all outstanding shares entitled to vote on amendments to the Certificate of Incorporation by written consent of the sole shareholder dated May 22, 2001.

IN WITNESS WHEREOF, this Certificate has been signed this 22nd Day of May, 2001.



F. A. Risch, President

STATE OF TEXAS)
COUNTY OF DALLAS)

F. L. REID, being duly sworn, deposes and says that he is the Secretary of MOBIL OIL CORPORATION, the corporation mentioned and described in the foregoing instrument; that he has read and signed the same and that the statements contained therein are true.




F. L. REID, Secretary

SUBSCRIBED AND SWORN TO before me, the undersigned authority, on this the 22nd day of May, 2001.

[SEAL]



NOTARY PUBLIC, STATE OF TEXAS



=> CSC

.TEL=5184334741

06/01'01 08:19

CSC
CSC

5184334741

06/01 '01 09:01 NO. 411 02/02
06/01 '01 09:06 NO. 133 04/04
F010601000187**CSC 45****CERTIFICATE OF AMENDMENT****OF****MOBIL OIL CORPORATION**


Under Section 805 of the Business Corporation Law

*SAC***STATE OF NEW YORK
DEPARTMENT OF STATE**Filed by: EXXONMOBIL CORPORATION
(Name)

FILED JUN 01 2001

5959 Las Colinas Blvd.
(Mailing address)

TAX \$

BY: *SAC*Irving, TX 75039-2298
(City, State and Zip code)*ny Albany**Cust Ref # 165578 MPJ***010601000195**

=> CSC

TEL=5184334741

06/01'01 08:19

*State of New York }
Department of State } ss:*

I hereby certify that the annexed copy has been compared with the original document in the custody of the Secretary of State and that the same is a true copy of said original.

Witness my hand and seal of the Department of State on **JUN 01 2001**



Special Deputy Secretary of State

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires: March 31, 2007

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals.

SUBMIT IN TRIPLICATE- Other instructions on reverse side.

1. Type of Well
☐ Oil Well ☐ Gas Well ☒ Other

2. Name of Operator **Exxon Mobil Oil Corporation**

3a. Address
P.O. Box 4358, Houston, TX 77210-4358

3b. Phone No. (include area code)
281-654-1936

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)
NWSE, 1860' FSL & 1820' FEL, Sec 29, T41S, R24E

5. Lease Serial No.
1420603407

6. If Indian, Allottee or Tribe Name
Ship Rock

7. If Unit or CA/Agreement, Name and/or No.
UTU68931A

8. Well Name and No.
Ratherford 29-33

9. API Well No.
43-037-30932-00-S1

10. Field and Pool, or Exploratory Area
Aneth

11. County or Parish, State
San Juan County, UT

12. CHECK APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input checked="" type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input checked="" type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation (clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirements, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection.)

5/25/05 MIRU WSU Key Rig # 38, Bled well down, RU hoses from wellhead to pit and pump. Pressure tested the tubing to 500 psi and held good for 15 min. Bled well down POOH with polish rod and LD, Unseated the pump, POOH with 85 - 7/8" and 141 3/4" rods and stood them in the derrick, LD Pump.

5/26/05 Bled well down, Pumped some kill fluid down the tubing. TIH with 10 stands of 3/4" rod from the derrick, TOOHH and LD 10 joints of 3/4" rods, Pumped 30 bbls of produce down the tubing for flush. PU 16' GA, Pump, Stabilizers, and 141 joints of 3/4" and 85 7/8" couldn't seat the pump, due to Gas Anchor being too long, TOOHH with all the rods and stood back in the derrick and LD pump.

5/27/05 Bled well down, PU 1' GA, Pump, Stabilizers, TIH with 10 new rods and 131 old rods from the derrick, and 85 old 7/8" rods. Tagged, seated, and space out pump. Hang on well, loaded the tubing and psi test to 500 psi and it held good., RD hoses from the wellhead, pit and pump. RDWSU. FINAL REPORT.

Returned to production 8-01-05. Well test 8-01-05: 70 bbls/d Oil, 64 bbls/d SW, 3 kcf/d Gas.
Well test 10-01-05: 2 bbls/d Oil, 4 bbls/d SW, 3 kcf/d Gas.

14. I hereby certify that the foregoing is true and correct
Name (Printed/Typed)

Tiffany Stebbins

Title **Staff Office Assistant**

Signature

Tiffany Stebbins

Date

11/11/2005

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved by

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Title

Date

Office

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

RECEIVED
NOV 18 2005
DIV. OF OIL, GAS & MINING

Division of Oil, Gas and Mining
OPERATOR CHANGE WORKSHEET

ROUTING

1. DJJ
2. CDW

X Change of Operator (Well Sold)

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective: **6/1/2006**

FROM: (Old Operator):
 N1855-ExxonMobil Oil Corporation
 PO Box 4358
 Houston, TX 77210-4358
 Phone: 1 (281) 654-1936

TO: (New Operator):
 N2700-Resolute Natural Resources Company
 1675 Broadway, Suite 1950
 Denver, CO 80202
 Phone: 1 (303) 534-4600

CA No.

Unit:

RATHERFORD

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 4/21/2006
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 4/24/2006
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 6/7/2006
- Is the new operator registered in the State of Utah: YES Business Number: 5733505-0143
- If **NO**, the operator was contacted on: _____
- (R649-9-2) Waste Management Plan has been received on: requested
- Inspections of LA PA state/fee well sites complete on: n/a
- Reports current for Production/Disposition & Sundries on: ok
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM n/a BIA not yet
- Federal and Indian Units:**
 The BLM or BIA has approved the successor of unit operator for wells listed on: not yet
- Federal and Indian Communization Agreements ("CA"):**
 The BLM or BIA has approved the operator for all wells listed within a CA on: n/a
- Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 6/12/2006

DATA ENTRY:

- Changes entered in the **Oil and Gas Database** on: 6/22/2006
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 6/22/2006
- Bond information entered in RBDMS on: n/a
- Fee/State wells attached to bond in RBDMS on: n/a
- Injection Projects to new operator in RBDMS on: 6/22/2006
- Receipt of Acceptance of Drilling Procedures for APD/New on: n/a

BOND VERIFICATION:

- Federal well(s) covered by Bond Number: n/a
- Indian well(s) covered by Bond Number: PA002769
- (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number n/a
- The **FORMER** operator has requested a release of liability from their bond on: n/a
 The Division sent response by letter on: n/a

LEASE INTEREST OWNER NOTIFICATION:

- (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

COMMENTS:

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

5. LEASE DESIGNATION AND SERIAL NUMBER:

See attached list

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

Navajo Tribe

7. UNIT or CA AGREEMENT NAME:

Ratherford Unit

8. WELL NAME and NUMBER:

See attached list

9. API NUMBER:

Attached

10. FIELD AND POOL, OR WILDCAT:

Greater Aneth

1. TYPE OF WELL

OIL WELL ☐

GAS WELL ☐

OTHER Unit Agreement

2. NAME OF OPERATOR:

Resolute Natural Resources Company

N2700

3. ADDRESS OF OPERATOR:

1675 Broadway, Suite 1950

CITY

Denver

STATE

CO

ZIP

80202

PHONE NUMBER:

(303) 534-4600

4. LOCATION OF WELL

FOOTAGES AT SURFACE: See attached list

COUNTY: San Juan

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

STATE:

UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ NOTICE OF INTENT
(Submit in Duplicate)

Approximate date work will start:

☒ SUBSEQUENT REPORT
(Submit Original Form Only)

Date of work completion:

TYPE OF ACTION

☐ ACIDIZE

☐ ALTER CASING

☐ CASING REPAIR

☐ CHANGE TO PREVIOUS PLANS

☐ CHANGE TUBING

☐ CHANGE WELL NAME

☐ CHANGE WELL STATUS

☐ COMMINGLE PRODUCING FORMATIONS

☐ CONVERT WELL TYPE

☐ DEEPEN

☐ FRACTURE TREAT

☐ NEW CONSTRUCTION

☒ OPERATOR CHANGE

☐ PLUG AND ABANDON

☐ PLUG BACK

☐ PRODUCTION (START/RESUME)

☐ RECLAMATION OF WELL SITE

☐ RECOMPLETE - DIFFERENT FORMATION

☐ REPERFORATE CURRENT FORMATION

☐ SIDETRACK TO REPAIR WELL

☐ TEMPORARILY ABANDON

☐ TUBING REPAIR

☐ VENT OR FLARE

☐ WATER DISPOSAL

☐ WATER SHUT-OFF

☐ OTHER: _____

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Effective June 1, 2006 Exxon Mobil Oil Corporation resigns as operator of the Ratherford Unit. Also effective June 1, 2006 Resolute Natural Resources Company is designated as successor operator of the Ratherford Unit.

A list of affected producing and water source wells is attached. A separate of affected injection wells is being submitted with UIC Form 5, Transfer of Authority to Inject.

As of the effective date, bond coverage for the affected wells will transfer to BIA Bond # PA002769.

NAME (PLEASE PRINT)

Dwight E Mallory

TITLE

Regulatory Coordinator

SIGNATURE

Dwight E Mallory

DATE

4/20/2006

(This space for State use only)

APPROVED 6127106

Earlene Russell

Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

RECEIVED

APR 24 2006

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Ship Rock
2. NAME OF OPERATOR: ExxonMobil Oil Corporation <i>N1855</i>		7. UNIT or CA AGREEMENT NAME: UTU68931A
3. ADDRESS OF OPERATOR: P.O. Box 4358 CITY Houston STATE TX ZIP 77210-4358		8. WELL NAME and NUMBER: Ratherford
4. LOCATION OF WELL FOOTAGES AT SURFACE: _____ QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: _____		9. API NUMBER: attached
		10. FIELD AND POOL, OR WILDCAT: Aneth
		COUNTY: San Juan
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: <u>6/1/2006</u>	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

ExxonMobil Oil Corporation is transferring operatorship of Greater Aneth field, Ratherford lease to Resolute Natural Resources Company. All change of operator notices should be made effective as of 7:00 AM MST on June 1, 2006.

Attached please find a listing of producers and water source wells included in the transfer.

NAME (PLEASE PRINT) <u>Laurie Kilbride</u>	TITLE <u>Permitting Supervisor</u>
SIGNATURE <i>Laurie B. Kilbride</i>	DATE <u>4/19/2006</u>

(This space for State use only)

APPROVED 6/30/06
Earlene Russell
Division of Oil, Gas and Mining
Earlene Russell, Engineering Technician

RECEIVED
APR 21 2006

Ratherford Unit - Producer Well List

minus P&A's

Lease	Number	API #	Status	Lease #	Location					
					Sec	T	R	QTR/QTR	NSFoot	EWFoot
Ratherford	01-14	430373116200S1	Producing	1420603246A	1	41S	23E	SWSW	0660FSL	0660FWL
Ratherford	01-34	430371638501S1	SI	1420603246A	1	41S	23E	SWSE	1133FSL	1980FEL
Ratherford	11-41	430373154400S1	Producing	1420603246A	11	41S	23E	NENE	0860FNL	0350FEL
Ratherford	11-43	430373162201S1	Producing	1420603246A	11	41S	23E	NESE	1980FSL	0660FEL
Ratherford	12-12	430373119000S1	Producing	1420603246A	12	41S	23E	SWNW	1850FNL	0660FWL
Ratherford	12-14	430371584400S1	SI	1420603246A	12	41S	23E	SWSW	0660FSL	4622FEL
Ratherford	12-21	430373120100S1	Producing	1420603246A	12	41S	23E	NENW	0660FNL	1980FWL
Ratherford	12-23	430371584601S1	Producing	1420603246A	12	41S	23E	NESW	1958FSL	3300FEL
Ratherford	12-32	430373120300S1	Producing	1420603246A	12	41S	23E	SWNE	1820FNL	1820FEL
Ratherford	12-34	430373112600S1	Producing	1420603246A	12	41S	23E	SWSE	0675FSL	1905FEL
Ratherford	12-43	430373120200S1	SI	1420603246A	12	41S	23E	NESE	2100FSL	0660FEL
Ratherford	13-12	430373112701S1	Producing	1420603247A	13	41S	23E	SWNW	1705FNL	0640FWL
Ratherford	13-14	430373158900S1	Producing	1420603247A	13	41S	23E	SWSW	0660FSL	0660FWL
Ratherford	13-21	430373112801S1	SI	1420603247A	13	41S	23E	NENW	0660FNL	1920FWL
Ratherford	13-23	430373112900S1	Producing	1420603247A	13	41S	23E	NESW	1980FSL	1930FWL
Ratherford	13-34	430373113001S1	Producing	1420603247A	13	41S	23E	SWSE	0660FSL	1980FEL
Ratherford	13-41	430371585601S1	Producing	1420603247A	13	41S	23E	NENE	660FNL	660FEL
Ratherford	13-43	430373113100S1	Producing	1420603247A	13	41S	23E	NESE	1700FSL	0960FEL
Ratherford	14-32	430371585801S1	Producing	1420603247A	14	41S	23E	SWNE	2130FNL	1830FEL
Ratherford	14-41	430373162300S1	Producing	1420603247A	14	41S	23E	NENE	0521FNL	0810FEL
Ratherford	24-32	430373159300S1	Producing	1420603247A	24	41S	23E	SWNE	2121FNL	1846FEL
Ratherford	24-41	430373113200S1	Producing	1420603247A	24	41S	23E	NENE	0660FNL	0710FEL
Ratherford	17-11	430373116900S1	Producing	1420603353	17	41S	24E	NWNW	1075FNL	0800FWL
Ratherford	17-13	430373113301S1	Producing	1420603353	17	41S	24E	NWSW	2100FSL	0660FWL
Ratherford	17-22	430373117001S1	Producing	1420603353	17	41S	24E	SENE	1882FNL	1910FWL
Ratherford	17-24	430373104400S1	Producing	1420603353	17	41S	24E	SESW	0720FSL	1980FWL
Ratherford	17-31	430373117800S1	Producing	1420603353	17	41S	24E	NWNE	0500FNL	1980FEL
Ratherford	17-33	430373113400S1	Producing	1420603353	17	41S	24E	NWSE	1980FSL	1845FEL
Ratherford	17-42	430373117700S1	Producing	1420603353	17	41S	24E	SENE	1980FNL	0660FEL
Ratherford	17-44	430371573201S1	Producing	1420603353	17	41S	24E	SESE	0660FSL	0660FEL
Ratherford	18-11	430371573300S1	SI	1420603353	18	41S	24E	NWNW	0720FNL	0730FWL
Ratherford	18-13	430371573401S1	Producing	1420603353	18	41S	24E	NWSW	1980FSL	0500FWL
Ratherford	18-22	430373123600S1	Producing	1420603353	18	41S	24E	SENE	2200FNL	2210FWL
Ratherford	18-24	430373107900S1	Producing	1420603353	18	41S	24E	SESW	0760FSL	1980FWL
Ratherford	18-31	430373118101S1	Producing	1420603353	18	41S	24E	NWNE	0795FNL	2090FEL
Ratherford	18-33	430373113501S1	Producing	1420603353	18	41S	24E	NWSE	1870FSL	1980FEL
Ratherford	18-42	430373118200S1	Producing	1420603353	18	41S	24E	SENE	2120FNL	0745FEL
Ratherford	18-44	430373104500S1	SI	1420603353	18	41S	24E	SESE	0660FSL	0660FEL
Ratherford	19-11	430373108000S1	Producing	1420603353	19	41S	24E	NWNW	0660FNL	0660FWL
Ratherford	19-13	430373171900S1	Producing	1420603353	19	41S	24E	NWSW	1980FSL	0660FWL
Ratherford	19-22	430373104601S1	Producing	1420603353	19	41S	24E	SENE	1840FNL	1980FWL
Ratherford	19-24	430373175401S1	Producing	1420603353	19	41S	24E	SESW	0600FSL	1980FWL
Ratherford	19-31	430373104701S1	Producing	1420603353	19	41S	24E	NWNE	510FNL	1980FEL
Ratherford	19-33	430373104800S1	Producing	1420603353	19	41S	24E	NWSE	1980FSL	1980FEL
Ratherford	19-42	430373091600S1	Producing	1420603353	19	41S	24E	SENE	1880FNL	0660FEL
Ratherford	19-44	430373108100S1	Producing	1420603353	19	41S	24E	SESE	0660FSL	0660FEL
Ratherford	19-97	430373159600S1	Producing	1420603353	19	41S	24E	SENE	2562FNL	0030FEL
Ratherford	20-11	430373104900S1	Producing	1420603353	20	41S	24E	NWNW	0500FNL	0660FWL
Ratherford	20-13	430373091700S1	Producing	1420603353	20	41S	24E	NWSW	2140FSL	0500FWL
Ratherford	20-22	430373093000S1	Producing	1420603353	20	41S	24E	SENE	2020FNL	2090FWL
Ratherford	20-24	430373091800S1	Producing	1420603353	20	41S	24E	SESW	0820FSL	1820FWL

Ratherford Unit - Producer Well List

minus P&A's

Lease	Number	API #	Status	Lease #	Location					
					Sec	T	R	QTR/QTR	NSFoot	EWFoot
Ratherford	20-31	430373105001S1	Producing	1420603353	20	41S	24E	NWNE	0660FNL	1880FEL
Ratherford	20-33	430373093100S1	Producing	1420603353	20	41S	24E	NWSE	1910FSL	2140FEL
Ratherford	20-42	430373105100S1	Producing	1420603353	20	41S	24E	SENE	1980FNL	0660FEL
Ratherford	20-44	430373091501S1	Producing	1420603353	20	41S	24E	SESE	0620FSL	0760FEL
Ratherford	20-66	430373159201S1	Producing	1420603353	20	41S	24E	SWNW	1369FNL	1221FWL
Ratherford	20-68	430373159100S1	Producing	1420603353	20	41S	24E	NWSW	1615FSL	1276FWL
Ratherford	15-12	430371571501S1	Producing	1420603355	15	41S	24E	SWNW	1820FNL	0500FWL
Ratherford	15-22	430373044900S1	SI	1420603355	15	41S	24E	SENE	1980FNL	2050FWL
Ratherford	15-32	430371571700S1	Producing	1420603355	15	41S	24E	SWNE	1980FNL	1980FEL
Ratherford	15-33	430371571800S1	Producing	1420603355	15	41S	24E	NWSE	1650FSL	1980FEL
Ratherford	15-41	430371571900S1	TA	1420603355	15	41S	24E	NENE	0660FNL	0660FEL
Ratherford	15-42	430373044800S1	Producing	1420603355	15	41S	24E	SENE	2020FNL	0820FEL
Ratherford	16-13	430373116801S1	Producing	1420603355	16	41S	24E	NWSW	1980FSL	660FWL
Ratherford	16-32	430371572300S1	Producing	1420603355	16	41S	24E	SWNE	1980FNL	1980FEL
Ratherford	16-41	430371572500S1	Producing	1420603355	16	41S	24E	NENE	0660FNL	0660FEL
Ratherford	16-77	430373176800S1	Producing	1420603355	16	41S	24E	NESW	2587FSL	2410FWL
Ratherford	21-23	430371375400S1	Producing	1420603355	21	41S	24E	NESW	1740FSL	1740FWL
Ratherford	21-24	430373172001S1	SI	1420603355	21	41S	24E	SESW	487FSL	2064FWL
Ratherford	21-32	430371575500S1	SI	1420603355	21	41S	24E	SWNE	1880FNL	1980FEL
Ratherford	21-77	430373175801S1	SI	1420603355	21	41S	24E	NWSE	2511FSL	2446FEL
Ratherford	07-11	430373116300S1	Producing	1420603368	7	41S	24E	NWNW	0660FNL	0710FWL
Ratherford	07-13	430373116400S1	Producing	1420603368	7	41S	24E	NWSW	2110FSL	0740FWL
Ratherford	07-22	430373116500S1	Producing	1420603368	7	41S	24E	SENE	1980FNL	1980FWL
Ratherford	07-24	430373116600S1	Producing	1420603368	7	41S	24E	SESW	0880FSL	2414FWL
Ratherford	07-44	430373118900S1	SI	1420603368	7	41S	24E	SESE	0737FSL	0555FEL
Ratherford	08-12	430371599100S1	Producing	1420603368	8	41S	24E	SWNW	1909FNL	0520FWL
Ratherford	08-21	430371599300S1	Producing	1420603368	8	41S	24E	NENW	0616FNL	1911FWL
Ratherford	08-23	430371599400S1	Producing	1420603368	8	41S	24E	NESW	1920FSL	2055FWL
Ratherford	08-32	430371599500S1	Producing	1420603368	8	41S	24E	SWNE	1980FNL	1980FEL
Ratherford	08-34	430371599600S1	Producing	1420603368	8	41S	24E	SWSE	0660FSL	1980FEL
Ratherford	04-34	430371616400S1	Producing	14206034035	4	41S	24E	SWSE	0660FSL	1980FEL
Ratherford	11-14	430371616700S1	Producing	14206034037	11	41S	24E	SWSW	0660FSL	0660FWL
Ratherford	09-34	430371571100S1	SI	14206034043	9	41S	24E	SWSE	0660FSL	1980FEL
Ratherford	10-12	430371571200S1	Producing	14206034043	10	41S	24E	SWNW	1980FNL	0660FWL
Ratherford	10-14	430371571300S1	Producing	14206034043	10	41S	24E	SWSW	0510FSL	0710FWL
Ratherford	10-32	430371571400S1	TA	14206034043	10	41S	24E	SWNE	2080FNL	1910FEL
Ratherford	10-44	430373045100S1	TA	14206034043	10	41S	24E	SESE	0820FSL	0510FEL
Ratherford	29-11	430373105300S1	Producing	1420603407	29	41S	24E	NWNW	0770FNL	0585FWL
Ratherford	29-22	430373108200S1	Producing	1420603407	29	41S	24E	SENE	2130FNL	1370FWL
Ratherford	29-31	430373091401S1	Producing	1420603407	29	41S	24E	NWNE	0700FNL	2140FEL
Ratherford	29-33	430373093200S1	SI	1420603407	29	41S	24E	NWSE	1860FSL	1820FEL
Ratherford	29-34	430371534000S1	SI	1420603407	29	41S	24E	SWSE	0817FSL	2096FEL
Ratherford	29-42	430373093700S1	SI	1420603407	29	41S	24E	SENE	1850FNL	0660FEL
Ratherford	30-32	430371534200S1	Producing	1420603407	30	41S	24E	SWNE	1975FNL	2010FEL
Ratherford	28-11	430373044600S1	Producing	1420603409	28	41S	24E	NWNW	0520FNL	0620FWL

Ratherford Unit - Producer Well List

minus P&A's

Lease	Number	API #	Status	Lease #	Location					
					Sec	T	R	QTR/QTR	NSFoot	EWFoot
Ratherford	09-12	430371512600S1	Producing	14206035045	9	41S	24E	SWNW	1865FNL	0780FWL
Ratherford	09-14	430371512700S1	Producing	14206035046	9	41S	24E	SWSW	0695FSL	0695FWL
Ratherford	04-14	430371616300S1	Producing	14206035446	4	41S	24E	SWSW	0500FSL	0660FWL
Ratherford	03-12	430371562000S1	Producing	14206036506	3	41S	24E	SWNW	2140FNL	0660FWL

Water Source Wells (Feb 2006)

RU	S1	4303700001	Active
RU	S2	4303700002	Active
RU	S3	4303700003	Active
RU	S4	4303700004	Active
RU	S5	4303700005	Active
RU	S6	4303700006	Active
RU	S7	4303700007	Active
RU	S8	4303700008	Active
RU	S9	4303700009	Active
RU	S10	4303700010	Active
RU	S11	4303700011	Active
RU	S12	4303700012	Active
RU	S13	4303700013	Active
RU	S14	4303700014	Active
RU	S16	4303700016	Active
RU	S17	4303700017	Active

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-603-407
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NAVAJO
2. NAME OF OPERATOR: RESOLUTE NATURAL RESOURCES		7. UNIT or CA AGREEMENT NAME: RATHERFORD
3. ADDRESS OF OPERATOR: 1675 Boradway Ste 1950, Denver, CO, 80202		8. WELL NAME and NUMBER: 29-33
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1860 FSL 1820 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 29 Township: 41.0S Range: 24.0E Meridian: S		9. API NUMBER: 43037309320000
PHONE NUMBER: 303 534-4600 Ext		9. FIELD and POOL or WILDCAT: GREATER ANETH
		COUNTY: SAN JUAN
		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 3/19/2013	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input checked="" type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER:
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Resolute proposes to drill dual horizontal laterals from the current wellbore in Ratherford Unit 29-33 to better drain the Desert Creek IA & IB intervals along the SW edge of the structure. The new laterals will be left open hole and will be produced commingled with perforations in the vertical wellbore. Attached is proposed drilling plan, directional plans/plots for 2 laterals, plat, water permits.

Surt

4117418X

6506604

37.191066

-109.302548

 BH Federal Approval of this
 Action is Necessary

4118284X

6499154

37.198997


-109.310761

 Approved by the
 Utah Division of
 Oil, Gas and Mining

Date: 03-21-13

By:


NAME (PLEASE PRINT) Sherry Glass	PHONE NUMBER 303 573-4886	TITLE Sr Regulatory Technician
SIGNATURE N/A	DATE 3/14/2013	

T. 41 S., R. 24 E., S.L.M.**SURVEYOR'S STATEMENT:**

I, John A. Vukonich, of Farmington, New Mexico, hereby state: This plat was made from notes taken during an actual survey under my direct supervision on FEBRUARY 8, 2013, and it correctly shows the location of RATHERFORD UNIT WELL NO. 29-33.

LEGEND

- ◆ SURFACE WELL LOCATION
● BOTTOM HOLE LOCATION
○ CALCULATED POSITION
- FOUND MONUMENT
L DENOTES 90° TIE
(C) CALCULATED

**EXHIBIT A**

P.O. BOX 3651
FARMINGTON, N.M.
(505) 334-0408

SCALE: 1" = 1000'**JOB No. 10445****DATE: 03/01/13**

**SURFACE: 1859' F/SL & 1836' F/EL,
BOTTOM HOLE 1: 544' F/NL & 1069' F/WL,
BOTTOM HOLE 2: 829' F/SL & 628' F/EL, SECTION 29,
T. 41 S, R. 24 E, SLM., SAN JUAN COUNTY, UTAH**

BY: H.S.

DWG.#: 10445W01

ADDITIONAL SUPPORT INFORMATION
Sundry – Notice of Intent
Ratherford Unit 29-33 Producer
Drill Dual Horizontal Laterals for DC-1A, 1B Reserves

1. Formation Tops

Existing Formation Tops (MD):

Upper Ismay:	5513'
Lower Ismay:	5606'
Gothic Shale:	5653'
Desert Creek IA	5674'
Desert Creek IB	5703'

2. Wellbore Diagrams –

Existing Wellbore Diagram – Attachment No. 1

Proposed Wellbore Diagram – Attachment No. 2

3. BOP Diagram and Equipment Description – Attachment No. 3

4. Directional Plan Leg#1 – Attachment No. 4, Leg#2 Attachment No. 5

5. Drilling Mud Specifications

- a. Proposed to drill laterals with N2 foamed fresh water fluid, in an underbalanced situation, or if conditions warrant,
- b. CaCl₂ brine water will be used, and if this will not control formation pressure during the drilling operations,
- c. Drilling mud with a salt polymer will be used if required for control of formation pressure during the drilling operations

Ratherford Unit 29-33H
1859' FSL & 1836' FEL
Sec 29, T41S, R24E
San Juan County, Utah
API 43-037-30932

Job Scope – Drill dual horizontal laterals from the current vertical wellbore to better drain the Desert Creek IA& IB intervals along the SW edge of the structure. The new laterals will be left open hole and will be produced commingled with perforations in the vertical wellbore.

Procedure: (Sundry Notice of Intent)

1. MIRU Well Service Unit.
2. Pull & LD rods & pump.
3. NU BOP, Pull production tubing & BHA.
4. Make cleanout trip to ~5630' with bit & scraper.
5. Run Casing Inspection and Cement Bond Logs from ~5630' to surface.
6. Set RBP for KOP at ~5455'. (Exact depth to be determined from csg inspection and CBL logs.)
7. RIH & set whipstock on RBP & orient same.
8. Mill ~7' window in 7" casing for 5455' KOP.
9. Drill the curve & 3847' x 6-1/8" lateral to the NW, Azimuth ~319 degrees.
10. RIH & set second whipstock for KOP ~11' above the first at ~5444' & orient same.
11. Mill ~7' window in 7" casing for 5444' KOP.

12. Drill the curve & 1474' x 6-1/8" lateral to the SE, Azimuth ~139 degrees.
13. Acid stimulate both laterals & flow back the acid load volume.
14. Retrieve both whipstocks & RBP.
15. Run production tubing & BHA.
16. Run rods & insert pump.
17. ND BOPE, NU Wellhead & flow line.
18. RDMO Drilling rig.



Resolute Natural Resources

Ratherford Unit

Ratherford Unit 29-33

29-33H

Leg #1

Plan: Leg #1 - Design #1

Standard Planning Report

31 January, 2013

RESOLUTE
NATURAL RESOURCES

MESA WEST
DIRECTIONAL**Mesa West Directional**

Planning Report

RESOLUTE
NATURAL RESOURCES

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Site Ratherford Unit 29-33
Company:	Resolute Natural Resources	TVD Reference:	Est. KB @ 4927.0usft
Project:	Ratherford Unit	MD Reference:	Est. KB @ 4927.0usft
Site:	Ratherford Unit 29-33	North Reference:	Grid
Well:	29-33H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Leg #1	Job #:	
Design:	Leg #1 - Design #1		

Project	Ratherford Unit		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Utah South 4303		Using geodetic scale factor

Site	Ratherford Unit 29-33		
Site Position:		Northing:	198,416.02 usft
From:	Lat/Long	Easting:	2,640,325.80 usft
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16 "
		Latitude:	37° 11' 27.348 N
		Longitude:	109° 18' 6.120 W
		Grid Convergence:	1.35 °

Well	29-33H		
Well Position	+N/-S	0.0 usft	Northing:
	+E/-W	0.0 usft	Easting:
Position Uncertainty	0.0 usft	Wellhead Elevation:	Ground Level:
			4,915.0 usft
			Latitude:
			37° 11' 27.348 N
			Longitude:
			109° 18' 6.120 W

Wellbore	Leg #1		
Magnetics	Model Name	Sample Date	Declination (°)
	IGRF2010	01/02/2013	10.39
			Dip Angle (°)
			63.52
			Field Strength (nT)
			50,630

Design	Leg #1 - Design #1		
Audit Notes:			
Version:	Phase:	PROTOTYPE	Tie On Depth:
			0.0
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)
	0.0	0.0	0.0
			Direction (°)
			318.99

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
5,454.8	0.00	0.00	5,454.8	0.0	0.0	0.00	0.00	0.00	0.00	
5,813.0	89.56	318.99	5,684.0	171.6	-149.2	25.00	25.00	0.00	318.99	
6,963.0	89.56	318.99	5,692.8	1,039.4	-903.8	0.00	0.00	0.00	0.00	
7,007.0	90.00	318.99	5,693.0	1,072.6	-932.6	1.00	1.00	0.00	0.00	
7,743.6	90.00	318.99	5,693.0	1,628.5	-1,416.0	0.00	0.00	0.00	0.00	
7,781.5	90.32	318.99	5,692.9	1,657.1	-1,440.8	0.86	0.86	0.00	0.00	
8,642.6	90.32	318.99	5,688.0	2,306.9	-2,005.8	0.00	0.00	0.00	0.00	
8,657.4	91.31	318.99	5,687.8	2,318.1	-2,015.5	6.70	6.70	0.00	0.00	
9,432.9	91.31	318.99	5,670.0	2,903.1	-2,524.2	0.00	0.00	0.00	0.00	Toe (29-33)

MESA WEST
DIRECTIONAL**Mesa West Directional**

Planning Report

RESOLUTE
NATURAL RESOURCES

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Site Ratherford Unit 29-33
Company:	Resolute Natural Resources	TVD Reference:	Est. KB @ 4927.0usft
Project:	Ratherford Unit	MD Reference:	Est. KB @ 4927.0usft
Site:	Ratherford Unit 29-33	North Reference:	Grid
Well:	29-33H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Leg #1	Job #:	
Design:	Leg #1 - Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	Subsea Depth (m)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
KOP at 5454.8 TVD, BUR = 25°/30m										
5,454.8	0.0	0.0	5,454.8	-527.8	0.0	0.0	0.0	0.0	0.0	0.0
5,460.0	1.3	319.0	5,460.0	-533.0	0.0	0.0	0.1	25.0	25.0	0.0
5,480.0	6.3	319.0	5,479.9	-553.0	1.0	-0.9	1.4	25.0	25.0	0.0
5,500.0	11.3	319.0	5,499.7	-572.7	3.4	-2.9	4.4	25.0	25.0	0.0
Upper Ismay										
5,513.6	14.7	319.0	5,513.0	-586.0	5.7	-4.9	7.5	25.0	25.0	0.0
5,520.0	16.3	319.0	5,519.1	-592.1	7.0	-6.0	9.2	25.0	25.0	0.0
5,540.0	21.3	319.0	5,538.1	-611.1	11.8	-10.3	15.7	25.0	25.0	0.0
5,560.0	26.3	319.0	5,556.3	-629.4	17.9	-15.6	23.7	25.0	25.0	0.0
5,580.0	31.3	319.0	5,573.9	-646.9	25.2	-21.9	33.4	25.0	25.0	0.0
5,600.0	36.3	319.0	5,590.5	-663.5	33.6	-29.2	44.5	25.0	25.0	0.0
Lower Ismay										
5,619.9	41.3	319.0	5,606.0	-679.0	43.0	-37.4	57.0	25.0	25.0	0.0
5,620.0	41.3	319.0	5,606.1	-679.1	43.0	-37.4	57.0	25.0	25.0	0.0
5,640.0	46.3	319.0	5,620.5	-693.5	53.5	-46.5	70.9	25.0	25.0	0.0
5,660.0	51.3	319.0	5,633.7	-706.7	64.8	-56.4	85.9	25.0	25.0	0.0
5,680.0	56.3	319.0	5,645.5	-718.5	77.0	-66.9	102.0	25.0	25.0	0.0
Gothic										
5,694.2	59.9	319.0	5,653.0	-726.0	86.1	-74.9	114.1	25.0	25.0	0.0
5,700.0	61.3	319.0	5,655.8	-728.8	89.9	-78.2	119.1	25.0	25.0	0.0
Gothic LSW										
5,718.4	65.9	319.0	5,664.0	-737.0	102.3	-89.0	135.6	25.0	25.0	0.0
5,720.0	66.3	319.0	5,664.6	-737.7	103.4	-89.9	137.1	25.0	25.0	0.0
5,740.0	71.3	319.0	5,671.9	-744.9	117.5	-102.2	155.7	25.0	25.0	0.0
DC-IA (top of Desert Creek)										
5,746.9	73.0	319.0	5,674.0	-747.0	122.5	-106.5	162.3	25.0	25.0	0.0
5,760.0	76.3	319.0	5,677.5	-750.5	132.0	-114.8	174.9	25.0	25.0	0.0
5,780.0	81.3	319.0	5,681.3	-754.3	146.8	-127.6	194.5	25.0	25.0	0.0
5,800.0	86.3	319.0	5,683.5	-756.5	161.8	-140.7	214.4	25.0	25.0	0.0
Start 1150.0 hold at 5813.0 MD - Landing Pt. (29-33)										
5,813.0	89.6	319.0	5,684.0	-757.0	171.6	-149.2	227.4	25.0	25.0	0.0
Target landing within DC-IA										
5,816.1	89.6	319.0	5,684.0	-757.0	173.9	-151.2	230.5	0.0	0.0	0.0
5,900.0	89.6	319.0	5,684.6	-757.6	237.3	-206.3	314.4	0.0	0.0	0.0
6,000.0	89.6	319.0	5,685.4	-758.4	312.7	-271.9	414.4	0.0	0.0	0.0
6,100.0	89.6	319.0	5,686.2	-759.2	388.2	-337.5	514.4	0.0	0.0	0.0
6,200.0	89.6	319.0	5,686.9	-759.9	463.6	-403.1	614.4	0.0	0.0	0.0
6,300.0	89.6	319.0	5,687.7	-760.7	539.1	-468.7	714.4	0.0	0.0	0.0
6,400.0	89.6	319.0	5,688.5	-761.5	614.6	-534.3	814.4	0.0	0.0	0.0
6,500.0	89.6	319.0	5,689.2	-762.3	690.0	-600.0	914.4	0.0	0.0	0.0

MESA WEST
DIRECTIONAL**Mesa West Directional**
Planning Report**RESOLUTE**
NATURAL RESOURCES

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Site Ratherford Unit 29-33
Company:	Resolute Natural Resources	TVD Reference:	Est. KB @ 4927.0usft
Project:	Ratherford Unit	MD Reference:	Est. KB @ 4927.0usft
Site:	Ratherford Unit 29-33	North Reference:	Grid
Well:	29-33H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Leg #1	Job #:	
Design:	Leg #1 - Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	Subsea Depth (m)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
6,600.0	89.6	319.0	5,690.0	-763.0	765.5	-665.6	1,014.4	0.0	0.0	0.0
6,700.0	89.6	319.0	5,690.8	-763.8	840.9	-731.2	1,114.4	0.0	0.0	0.0
Hold at 6760.0 MD (1175 VS)										
6,760.6	89.6	319.0	5,691.2	-764.3	886.7	-770.9	1,175.0	0.0	0.0	0.0
6,800.0	89.6	319.0	5,691.5	-764.6	916.4	-796.8	1,214.4	0.0	0.0	0.0
6,900.0	89.6	319.0	5,692.3	-765.3	991.9	-862.4	1,314.4	0.0	0.0	0.0
Start 1° Build at 6963 MD										
6,963.0	89.6	319.0	5,692.8	-765.8	1,039.4	-903.8	1,377.4	0.0	0.0	0.0
Start 736.6 hold at 7007.0 MD										
7,007.0	90.0	319.0	5,693.0	-766.0	1,072.6	-932.6	1,421.4	1.0	1.0	0.0
7,100.0	90.0	319.0	5,693.0	-766.0	1,142.8	-993.6	1,514.4	0.0	0.0	0.0
7,200.0	90.0	319.0	5,693.0	-766.0	1,218.3	-1,059.2	1,614.4	0.0	0.0	0.0
7,300.0	90.0	319.0	5,693.0	-766.0	1,293.7	-1,124.9	1,714.4	0.0	0.0	0.0
7,400.0	90.0	319.0	5,693.0	-766.0	1,369.2	-1,190.5	1,814.4	0.0	0.0	0.0
7,500.0	90.0	319.0	5,693.0	-766.0	1,444.6	-1,256.1	1,914.4	0.0	0.0	0.0
7,600.0	90.0	319.0	5,693.0	-766.0	1,520.1	-1,321.7	2,014.4	0.0	0.0	0.0
7,700.0	90.0	319.0	5,693.0	-766.0	1,595.6	-1,387.3	2,114.4	0.0	0.0	0.0
Start 0.86° Build at 7743.7 MD (2158 VS)										
7,743.6	90.0	319.0	5,693.0	-766.0	1,628.5	-1,416.0	2,158.0	0.0	0.0	0.0
Start 861.1 hold at 7781.5 MD										
7,781.5	90.3	319.0	5,692.9	-765.9	1,657.1	-1,440.8	2,195.9	0.9	0.9	0.0
7,800.0	90.3	319.0	5,692.8	-765.8	1,671.0	-1,452.9	2,214.4	0.0	0.0	0.0
7,900.0	90.3	319.0	5,692.2	-765.2	1,746.5	-1,518.5	2,314.4	0.0	0.0	0.0
8,000.0	90.3	319.0	5,691.6	-764.6	1,822.0	-1,584.2	2,414.4	0.0	0.0	0.0
8,100.0	90.3	319.0	5,691.1	-764.1	1,897.4	-1,649.8	2,514.4	0.0	0.0	0.0
8,200.0	90.3	319.0	5,690.5	-763.5	1,972.9	-1,715.4	2,614.4	0.0	0.0	0.0
8,300.0	90.3	319.0	5,689.9	-762.9	2,048.4	-1,781.0	2,714.4	0.0	0.0	0.0
8,400.0	90.3	319.0	5,689.4	-762.4	2,123.8	-1,846.6	2,814.3	0.0	0.0	0.0
8,500.0	90.3	319.0	5,688.8	-761.8	2,199.3	-1,912.2	2,914.3	0.0	0.0	0.0
8,600.0	90.3	319.0	5,688.2	-761.2	2,274.7	-1,977.8	3,014.3	0.0	0.0	0.0
Start 6.7° Build at 8642.7 MD (3057 VS)										
8,642.6	90.3	319.0	5,688.0	-761.0	2,306.9	-2,005.8	3,057.0	0.0	0.0	0.0
8,650.0	90.8	319.0	5,687.9	-760.9	2,312.5	-2,010.6	3,064.3	6.7	6.7	0.0
Start 775.5 hold at 8657.4 MD										
8,657.4	91.3	319.0	5,687.8	-760.8	2,318.1	-2,015.5	3,071.8	6.7	6.7	0.0
8,700.0	91.3	319.0	5,686.8	-759.8	2,350.2	-2,043.4	3,114.3	0.0	0.0	0.0
8,800.0	91.3	319.0	5,684.5	-757.5	2,425.6	-2,109.0	3,214.3	0.0	0.0	0.0
8,900.0	91.3	319.0	5,682.2	-755.2	2,501.1	-2,174.6	3,314.3	0.0	0.0	0.0
9,000.0	91.3	319.0	5,679.9	-752.9	2,576.5	-2,240.2	3,414.3	0.0	0.0	0.0
9,100.0	91.3	319.0	5,677.6	-750.6	2,652.0	-2,305.8	3,514.2	0.0	0.0	0.0
9,200.0	91.3	319.0	5,675.3	-748.3	2,727.4	-2,371.4	3,614.2	0.0	0.0	0.0
9,300.0	91.3	319.0	5,673.0	-746.0	2,802.9	-2,437.0	3,714.2	0.0	0.0	0.0

MESA WEST
DIRECTIONAL**Mesa West Directional**
Planning Report**RESOLUTE**
NATURAL RESOURCES

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Site Ratherford Unit 29-33
Company:	Resolute Natural Resources	TVD Reference:	Est. KB @ 4927.0usft
Project:	Ratherford Unit	MD Reference:	Est. KB @ 4927.0usft
Site:	Ratherford Unit 29-33	North Reference:	Grid
Well:	29-33H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Leg #1	Job #:	
Design:	Leg #1 - Design #1		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	Subsea Depth (m)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
9,400.0	91.3	319.0	5,670.7	-743.8	2,878.3	-2,502.6	3,814.1	0.0	0.0	0.0
TD at 9432.9, 5670.0 TVD (3847 VS) - Toe (29-33)										
9,432.9	91.3	319.0	5,670.0	-743.0	2,903.1	-2,524.2	3,847.1	0.0	0.0	0.0

Design Targets

Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
Landing Pt. (29-33) - plan hits target center - Point	0.00	0.00	5,684.0	171.6	-149.2	198,587.64	2,640,176.58	37° 11' 29.079 N	109° 18' 7.914 W
Toe (29-33) - plan hits target center - Point	0.00	0.00	5,670.0	2,903.1	-2,524.2	201,319.16	2,637,801.58	37° 11' 56.630 N	109° 18' 36.466 W

Formations

Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)
1,587.0	1,587.0	Chinle estimate		0.00	
2,585.0	2,585.0	De Chelley		0.00	
2,935.0	2,935.0	Organ Rock		0.00	
5,513.6	5,513.0	Upper Ismay		0.00	
5,619.9	5,606.0	Lower Ismay		0.00	
5,694.2	5,653.0	Gothic		0.00	
5,718.4	5,664.0	Gothic LSW		0.00	
5,746.9	5,674.0	DC-IA (top of Desert Creek)		0.00	
5,816.1	5,684.0	Target landing within DC-IA		0.00	

Plan Annotations

Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
5,454.8	5,454.8	0.0	0.0	KOP at 5454.8 TVD, BUR = 25°/30m
5,813.0	5,684.0	171.6	-149.2	Start 1150.0 hold at 5813.0 MD
6,760.6	5,691.2	886.7	-770.9	Hold at 6760.0 MD (1175 VS)
6,963.0	5,692.8	1,039.4	-903.8	Start 1° Build at 6963 MD
7,007.0	5,693.0	1,072.6	-932.6	Start 736.6 hold at 7007.0 MD
7,743.6	5,693.0	1,628.5	-1,416.0	Start 0.86° Build at 7743.7 MD (2158 VS)
7,781.5	5,692.9	1,657.1	-1,440.8	Start 861.1 hold at 7781.5 MD
8,642.6	5,688.0	2,306.9	-2,005.8	Start 6.7° Build at 8642.7 MD (3057 VS)
8,657.4	5,687.8	2,318.1	-2,015.5	Start 775.5 hold at 8657.4 MD
9,432.9	5,670.0	2,903.1	-2,524.2	TD at 9432.9, 5670.0 TVD (3847 VS)

Site: Rutherford Unit 29-33
Well: 29-33H
Wellbore: Leg #1
Design: Leg #1 - Design #1

RESOLUTE
NATURAL RESOURCES

SECTION DETAILS

MD	Inc	Azi	TVD	+N/S	+E/W	Disg	TFace	Vsect	Annotation
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
5454.8	0.00	0.00	5454.8	0.0	0.0	0.00	0.00	0.0	KOP at 5454.8 TVD, BUR = 25°/30m
5813.0	89.56	318.99	5684.0	171.0	-149.2	25.00	218.99	227.4	Start 1150.0 hold at 5813.0 MD
6963.0	89.56	318.99	5692.8	1039.4	-903.8	0.00	0.00	1377.4	Start 1" Build at 6963 MD
7007.0	90.00	318.99	5693.0	1072.6	-932.8	1.00	0.00	1421.4	Start 736.6 hold at 7007.0 MD
7743.6	80.00	318.99	5693.0	1626.5	-1416.0	0.00	0.00	2158.0	Start 0.86" Build at 7743.7 MD (2158 VS)
7781.5	80.32	318.99	5692.9	1637.1	-1440.8	0.86	0.00	2195.9	Start 861.1 hold at 7781.5 MD
8642.6	90.32	318.99	5688.0	2308.9	-2005.8	0.00	0.00	3057.0	Start 6.7" Build at 8642.7 MD (3057 VS)
8657.4	91.31	318.99	5687.6	2318.1	-2015.5	6.70	0.00	3071.8	Start 775.5 hold at 8657.4 MD
8432.9	91.31	318.99	5670.0	2993.1	-2524.2	0.00	0.00	3847.1	TD at 8432.9, 5670.0 TVD (3847 VS)


REFERENCE INFORMATION

Co-ordinate (N/E) Reference: Site Rutherford Unit 29-33, Grid North
Calculation Method: Minimum Curvature
Murching: 198416.02
Easting: 2640325.80
Latitude: 32° 11' 27.348 N
Longitude: 109° 16' 6.130 W
Ground Elevation: 4915.0
KB Elevation: Est. KB @ 4927.0m
Convergence: 1.35


MESA WEST
DIRECTIONAL

FORMATION TOP DETAILS

TVDPath	MDPath	Formation
1587.0	1587.0	Chinle estimate
2585.0	2585.0	De Chalky
2935.0	2935.0	Organ Rock
5513.0	5513.0	Upper Ismay
5696.0	5619.9	Lower Ismay
5653.0	5684.2	Gothic
5664.0	5718.4	Gothic LSW
5674.0	5746.8	DC-IA (top of Desert Creek)
5684.0	5816.1	Target landing within DC-IA



Vertical Section at 318.99° (50 usft/cm)



Vertical Section at 318.99° (50 usft/cm)

True North
Magnetic North: 8.56°
Magnetic Field
Strength: 5829.8uT
Dip Angle: 83.32°
Date: 01/02/2018
Model: IGRF2012



Resolute Natural Resources

Ratherford Unit
Ratherford Unit 29-33
29-33H

Leg #2

Plan: Leg #2 - Design #2

Standard Planning Report

31 January, 2013

RESOLUTE
NATURAL RESOURCES

Sundry Number: 35615 API Well Number: 43037309320000

MESA WEST
DIRECTIONAL

Mesa West Directional
Planning Report

RESOLUTE
NATURAL RESOURCES

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Site Ratherford Unit 29-33
Company:	Resolute Natural Resources	TVD Reference:	Est. KB @ 4927.0usft
Project:	Ratherford Unit	MD Reference:	Est. KB @ 4927.0usft
Site:	Ratherford Unit 29-33	North Reference:	Grid
Well:	29-33H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Leg #2	Job #:	
Design:	Leg #2 - Design #2		

Project	Ratherford Unit		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Utah South 4303		Using geodetic scale factor

Site	Ratherford Unit 29-33		
Site Position:		Northing:	198,416.02 usft
From:	Lat/Long	Easting:	2,640,325.80 usft
Position Uncertainty:	0.0 usft	Slot Radius:	13-3/16 "
		Latitude:	37° 11' 27.348 N
		Longitude:	109° 18' 6.120 W
		Grid Convergence:	1.35 °

Well	29-33H		
Well Position	+N/-S	0.0 usft	Northing:
	+E/-W	0.0 usft	Easting:
Position Uncertainty	0.0 usft	Wellhead Elevation:	
		Latitude:	37° 11' 27.348 N
		Longitude:	109° 18' 6.120 W
		Ground Level:	4,915.0 usft

Wellbore	Leg #2		
Magnetics	Model Name	Sample Date	Declination
			(°)
	IGRF2010	01/02/2013	10.39
			Dip Angle
			(°)
			Field Strength
			(nT)
			50,630

Design	Leg #2 - Design #2		
Audit Notes:			
Version:	Phase:	PROTOTYPE	Tie On Depth:
			5,444.0
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W
	(usft)	(usft)	(usft)
	0.0	0.0	0.0
			Direction
			(°)
			128.50

Plan Sections										
Measured	Inclination	Azimuth	Vertical	+N/-S	+E/-W	Dogleg	Build	Turn	TFO	Target
Depth	(°)	(°)	Depth	(usft)	(usft)	Rate	Rate	Rate	(°)	
(usft)			(usft)			(°/100usft)	(°/100usft)	(°/100usft)		
5,444.0	0.00	0.00	5,444.0	0.0	0.0	0.00	0.00	0.00	0.00	
5,814.7	88.49	128.50	5,683.9	-145.5	182.9	23.87	23.87	34.66	128.50	D2_Landing Pt. (29-3
5,819.5	88.21	128.50	5,684.1	-148.5	186.6	5.85	-5.85	0.00	180.00	
6,073.0	88.21	128.50	5,692.0	-306.2	385.0	0.00	0.00	0.00	0.00	
6,083.4	88.32	128.50	5,692.3	-312.7	393.1	1.00	1.00	0.00	0.00	
6,481.1	88.32	128.50	5,704.0	-560.2	704.1	0.00	0.00	0.00	0.00	
6,547.2	86.99	128.50	5,706.7	-601.3	755.8	2.00	-2.00	0.00	180.00	
6,743.5	86.99	128.50	5,717.0	-723.3	909.2	0.00	0.00	0.00	0.00	
6,754.9	86.88	128.50	5,717.6	-730.4	918.2	1.00	-1.00	0.00	180.00	
7,056.1	86.88	128.50	5,734.0	-917.6	1,153.5	0.00	0.00	0.00	0.00	D2_Toe (29-33_Leg#:

MESA WEST
DIRECTIONAL**Mesa West Directional**
Planning Report**RESOLUTE**
NATURAL RESOURCES

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Site Ratherford Unit 29-33
Company:	Resolute Natural Resources	TVD Reference:	Est. KB @ 4927.0usft
Project:	Ratherford Unit	MD Reference:	Est. KB @ 4927.0usft
Site:	Ratherford Unit 29-33	North Reference:	Grid
Well:	29-33H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Leg #2	Job #:	
Design:	Leg #2 - Design #2		

Planned Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	Subsea Depth (m)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
Tie-on at 5443.99 TVD, BUR = 23.87°, TFO 128.5										
5,444.0	0.0	0.0	5,444.0	-517.0	0.0	0.0	0.0	0.0	0.0	0.0
5,460.0	3.8	128.5	5,460.0	-533.0	-0.3	0.4	0.5	23.9	23.9	0.0
5,480.0	8.6	128.5	5,479.9	-552.9	-1.7	2.1	2.7	23.9	23.9	0.0
5,500.0	13.4	128.5	5,499.5	-572.5	-4.0	5.1	6.5	23.9	23.9	0.0
Upper Ismay										
5,514.0	16.7	128.5	5,513.0	-586.0	-6.3	7.9	10.1	23.9	23.9	0.0
5,520.0	18.1	128.5	5,518.7	-591.7	-7.4	9.3	11.9	23.9	23.9	0.0
5,540.0	22.9	128.5	5,537.5	-610.5	-11.8	14.8	18.9	23.9	23.9	0.0
5,560.0	27.7	128.5	5,555.5	-628.5	-17.1	21.5	27.5	23.9	23.9	0.0
5,580.0	32.5	128.5	5,572.8	-645.8	-23.4	29.4	37.5	23.9	23.9	0.0
5,600.0	37.2	128.5	5,589.2	-662.3	-30.5	38.3	48.9	23.9	23.9	0.0
5,620.0	42.0	128.5	5,604.6	-677.7	-38.4	48.3	61.7	23.9	23.9	0.0
Lower Ismay										
5,621.8	42.4	128.5	5,606.0	-679.0	-39.2	49.2	62.9	23.9	23.9	0.0
5,640.0	46.8	128.5	5,618.9	-691.9	-47.1	59.2	75.7	23.9	23.9	0.0
5,660.0	51.6	128.5	5,632.0	-705.0	-56.5	71.1	90.8	23.9	23.9	0.0
5,680.0	56.3	128.5	5,643.8	-716.8	-66.6	83.7	107.0	23.9	23.9	0.0
Gothic										
5,697.6	60.5	128.5	5,653.0	-726.0	-75.9	95.5	122.0	23.9	23.9	0.0
5,700.0	61.1	128.5	5,654.1	-727.2	-77.2	97.1	124.1	23.9	23.9	0.0
5,720.0	65.9	128.5	5,663.1	-736.1	-88.4	111.1	142.0	23.9	23.9	0.0
Gothic LSW										
5,722.3	66.4	128.5	5,664.0	-737.0	-89.7	112.7	144.0	23.9	23.9	0.0
5,740.0	70.7	128.5	5,670.5	-743.5	-99.9	125.6	160.5	23.9	23.9	0.0
DC-IA (top of Desert Creek)										
5,751.4	73.4	128.5	5,674.0	-747.0	-106.7	134.1	171.4	23.9	23.9	0.0
5,760.0	75.4	128.5	5,676.3	-749.3	-111.8	140.6	179.7	23.9	23.9	0.0
5,780.0	80.2	128.5	5,680.5	-753.5	-124.0	155.9	199.2	23.9	23.9	0.0
5,800.0	85.0	128.5	5,683.1	-756.1	-136.4	171.4	219.0	23.9	23.9	0.0
Start 5.85° Drop at 5814.7 MD - D2_Landing Pt. (29-33_Leg#2)										
5,814.7	88.5	128.5	5,683.9	-756.9	-145.5	182.9	233.7	23.9	23.9	0.0
Target landing within DC-IA										
5,816.6	88.5	128.5	5,684.0	-757.0	-146.6	184.3	235.6	0.0	0.0	0.0
Start 253.6 hold at 5819.5 MD										
5,819.5	88.2	128.5	5,684.1	-757.1	-148.5	186.6	238.5	9.5	-9.5	0.0
5,900.0	88.2	128.5	5,686.6	-759.6	-198.6	249.6	319.0	0.0	0.0	0.0
6,000.0	88.2	128.5	5,689.7	-762.7	-260.8	327.8	418.9	0.0	0.0	0.0
Start 1° Build at 6073.0 MD (492 VS)										
6,073.0	88.2	128.5	5,692.0	-765.0	-306.2	385.0	491.9	0.0	0.0	0.0
Start 397.6 hold at 6083.4 MD										
6,083.4	88.3	128.5	5,692.3	-765.3	-312.7	393.1	502.3	1.0	1.0	0.0

MESA WEST
DIRECTIONAL**Mesa West Directional**

Planning Report

RESOLUTE
NATURAL RESOURCES

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Site Ratherford Unit 29-33
Company:	Resolute Natural Resources	TVD Reference:	Est. KB @ 4927.0usft
Project:	Ratherford Unit	MD Reference:	Est. KB @ 4927.0usft
Site:	Ratherford Unit 29-33	North Reference:	Grid
Well:	29-33H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Leg #2	Job #:	
Design:	Leg #2 - Design #2		

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	Subsea Depth (m)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
6,100.0	88.3	128.5	5,692.8	-765.8	-323.0	406.1	518.9	0.0	0.0	0.0
6,200.0	88.3	128.5	5,695.7	-768.7	-385.2	484.3	618.8	0.0	0.0	0.0
6,300.0	88.3	128.5	5,698.7	-771.7	-447.5	562.5	718.8	0.0	0.0	0.0
6,400.0	88.3	128.5	5,701.6	-774.6	-509.7	640.7	818.7	0.0	0.0	0.0
DC-IB										
6,447.0	88.3	128.5	5,703.0	-776.0	-539.0	677.5	865.7	0.0	0.0	0.0
Start 2° Drop at 6481.1 MD (900 VS)										
6,481.1	88.3	128.5	5,704.0	-777.0	-560.2	704.1	899.8	0.0	0.0	0.0
6,500.0	87.9	128.5	5,704.6	-777.6	-571.9	718.9	918.7	2.0	-2.0	0.0
Start 196.3 hold at 6547.2 MD										
6,547.2	87.0	128.5	5,706.7	-779.7	-601.3	755.8	965.8	2.0	-2.0	0.0
6,600.0	87.0	128.5	5,709.5	-782.5	-634.1	797.1	1,018.6	0.0	0.0	0.0
6,700.0	87.0	128.5	5,714.7	-787.7	-696.3	875.3	1,118.4	0.0	0.0	0.0
Start 1° Drop at 6743.5 MD (1162 VS)										
6,743.5	87.0	128.5	5,717.0	-790.0	-723.3	909.2	1,161.9	0.0	0.0	0.0
Start 301.2 hold at 6754.9 MD										
6,754.9	86.9	128.5	5,717.6	-790.6	-730.4	918.2	1,173.2	1.0	-1.0	0.0
6,800.0	86.9	128.5	5,720.1	-793.1	-758.4	953.4	1,218.3	0.0	0.0	0.0
6,900.0	86.9	128.5	5,725.5	-798.5	-820.6	1,031.5	1,318.1	0.0	0.0	0.0
7,000.0	86.9	128.5	5,730.9	-803.9	-882.8	1,109.7	1,418.0	0.0	0.0	0.0
TD at 7056.1 MD, 5734.0 TVD (1474 VS) - D2_Toe (29-33_Leg#2)										
7,056.1	86.9	128.5	5,734.0	-807.0	-917.6	1,153.5	1,474.0	0.0	0.0	0.0

Design Targets

Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
- hit/miss target									
- Shape									
D2_Landing Pt. (29-33_L	0.00	0.00	5,683.9	-145.5	182.9	198,270.52	2,640,508.70	37° 11' 25.867 N	109° 18' 3.903 W
- plan hits target center									
- Point									
D2_Toe (29-33_Leg#2)	0.00	0.00	5,734.0	-917.6	1,153.6	197,498.42	2,641,479.41	37° 11' 18.010 N	109° 17' 52.135 W
- plan hits target center									
- Point									

MESA WEST
DIRECTIONAL**Mesa West Directional**

Planning Report

RESOLUTE
NATURAL RESOURCES

Database:	EDM 5000.1 Single User Db	Local Co-ordinate Reference:	Site Ratherford Unit 29-33
Company:	Resolute Natural Resources	TVD Reference:	Est. KB @ 4927.0usft
Project:	Ratherford Unit	MD Reference:	Est. KB @ 4927.0usft
Site:	Ratherford Unit 29-33	North Reference:	Grid
Well:	29-33H	Survey Calculation Method:	Minimum Curvature
Wellbore:	Leg #2	Job #:	
Design:	Leg #2 - Design #2		

Formations

Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)
1,587.0	1,587.0	Chinle estimate		0.00	
2,585.0	2,585.0	De Chelley		0.00	
2,935.0	2,935.0	Organ Rock		0.00	
5,514.0	5,513.0	Upper Ismay		0.00	
5,621.8	5,606.0	Lower Ismay		0.00	
5,697.6	5,653.0	Gothic		0.00	
5,722.3	5,664.0	Gothic LSW		0.00	
5,751.4	5,674.0	DC-IA (top of Desert Creek)		0.00	
5,816.6	5,684.0	Target landing within DC-IA		0.00	
6,447.0	5,703.0	DC-IB		0.00	

Plan Annotations

Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
5,444.0	5,444.0	0.0	0.0	Tie-on at 5443.99 TVD, BUR = 23.87°, TFO 128.5
5,814.7	5,683.9	-145.5	182.9	Start 5.85° Drop at 5814.7 MD
5,819.5	5,684.1	-148.5	186.6	Start 253.6 hold at 5819.5 MD
6,073.0	5,692.0	-306.2	385.0	Start 1° Build at 6073.0 MD (492 VS)
6,083.4	5,692.3	-312.7	393.1	Start 397.6 hold at 6083.4 MD
6,481.1	5,704.0	-560.2	704.1	Start 2° Drop at 6481.1 MD (900 VS)
6,547.2	5,706.7	-601.3	755.8	Start 196.3 hold at 6547.2 MD
6,743.5	5,717.0	-723.3	909.2	Start 1° Drop at 6743.5 MD (1162 VS)
6,754.9	5,717.6	-730.4	918.2	Start 301.2 hold at 6754.9 MD
7,056.1	5,734.0	-917.6	1,153.5	TD at 7056.1 MD, 5734.0 TVD (1474 VS)

Site: Rutherford Unit 29-33
Well: 29-33H
Wellbore: Leg #2
Design: Leg #2 - Design #2

RESOLUTE
NATURAL RESOURCES

SECTION DETAILS

MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSec	Annotation
5444.0	0.00	0.00	5444.0	0.0	0.0	0.00	0.00	0.6	Tie-on at 5443.99 TVD, BUR = 23.87°, TFO 128.5
5814.7	88.49	128.50	5883.9	-145.5	182.8	23.87	128.50	233.7	Start 5.85° Drop at 5814.7 MD
5819.5	88.21	128.50	5884.1	-148.5	186.8	5.85	180.00	238.5	Start 253.6 hold at 5819.5 MD
6073.0	88.21	128.50	5882.0	-306.2	385.9	0.00	0.00	491.9	Start 1° Build at 6073.0 MD (492 VS)
6083.4	88.32	128.50	5892.3	-312.7	393.1	0.00	1.00	502.3	Start 397.6 hold at 6083.4 MD
6481.1	88.32	128.50	5704.0	-560.2	704.1	0.00	0.00	899.6	Start 2° Drop at 6481.1 MD (900 VS)
6547.2	88.99	128.50	5706.7	-601.3	755.8	2.00	180.00	965.6	Start 196.3 hold at 6547.2 MD
6743.5	88.99	128.50	5717.0	-723.3	909.2	0.00	0.00	1161.8	Start 1° Drop at 6743.5 MD (1162 VS)
6754.9	88.88	128.50	5717.6	-730.4	918.2	1.00	180.00	1173.2	Start 301.2 hold at 6754.9 MD
7056.1	88.88	128.50	5734.0	-917.6	1153.5	0.00	0.00	1474.6	TD at 7056.1 MD, 5734.0 TVD (1474 VS)



REFERENCE INFORMATION

Co-ordinate (N/E) Reference: Site Rutherford Unit 29-33, Grid North
Calculation Method: Minimum Curvature
Northing: 1984.15 02
Easting: 2640325.80
Latitude: 37° 11' 27.348 N
Longitude: 109° 18' 6.120 W
Ground Elevation: 4915.0
KB Elevation: Est. KB @ 4927.0ust
Convergence: 1.35

MESA WEST
DIRECTIONAL

FORMATION TOP DETAILS:

TVDPath	MDPath	Formation
1587.0	1587.0	Chinle estimate
2385.0	2385.0	De Chelly
2935.0	2935.0	Organ Rock
5513.0	5514.0	Upper Ismay
5606.0	5621.6	Lower Ismay
5653.0	5697.6	Gothic
5684.0	5722.3	Gothic LSW
5674.0	5751.4	DC-IA (top of Desert Creek)
5684.0	5816.6	Target landing within DC-IA
5703.0	6447.6	DC-IB



True North
Magnetic North
Magnetic Field
Strength: 50.79 BnT
Dip Angle: 63.32°
Date: 11/05/2013
Model: IGRF2010

RATHERFORD UNIT # 29-33

PRODUCER

GREATER ANETH FIELD

1859' FSL & 1836' FEL


SEC 29-T41S-R24E

SAN JUAN COUNTY, UTAH

API 43-037-30932

PRISM 0043140

Attachment 1 - Existing



RATHERFORD UNIT # 29-33H

PRODUCER

GREATER ANETH FIELD

1859' FSL & 1836' FEL


SEC 29-T41S-R24E

SAN JUAN COUNTY, UTAH

API 43-037-30932


PRISM 0043140

Attachment 2 - Proposed



-63-

Attachment No. 3



TYPICAL WORKOVER BOP STACK

Figure 30

Sundry Number: 35615 API Well Number: 43037309320000

API Well Number: 43037309320000

Well No.	WUP No.	WUP # 1996	WUP # 1997	Sec. - Twp - Rg.	GPS Coordinates	Elev. (1985)	N.43. (1995)	Acq. #	Completed	Comments
MCH-8100										
1-PIT	PIT	95-529	97-223	16-41S-25E		659950	4121100			Abandoned
2	12-0715	95-530	97-201	17-41S-25E	37° 13 226 N 109° 12 747 N	659410	4120950	29718 A3777	9/14/61	
3	12-0716	95-531	97-202	17-41S-25E	37° 13 196 N 019° 12 187 N	659660	4120460	29718 A3777	10/3/61	
4	12-0717	95-532	97-203	17-41S-25E	37° 13 166 N 019° 12 147 N	659640	4120520	29718 A3777	10/17/61	
5	12-0718	95-533	97-204	17-41S-25E	37° 13 122 N 019° 12 068 N	659630	4120460	29718 A3777	10/19/61	
6	12-0719	95-534	97-205	17-41S-25E	37° 13 092 N 019° 12 053 N	659630	4120460	31023 A3777	4/26/62	
7	12-0720	95-512	97-206	17-41S-25E	37° 13 055 N 019° 12 032 N	659720	4120320	31023 A3777	4/30/62	
8	12-0721	95-513	97-207	17-41S-25E	37° 13 023 N 019° 12 980 N	659660	4120260	31023 A3777	5/4/62	
9	12-0722	95-514	97-208	17-41S-25E	37° 13 010 N 109° 11 937 N	659680	4120230	31023 A3777	5/8/62	
10	12-0723	95-515	97-209	17-41S-25E	37° 12 966 N 109° 11 865 N	659680	4120220	31023 A3777	5/12/62	
11	12-0724	95-516	97-210	17-41S-25E	37° 12 902 N 109° 11 809 N	660060	4120210	29718 A31023	11/28/62	
12	12-0725	95-517	97-211	17-41S-25E	37° 13 026 N 109° 11 708 N	660120	4120270	29718 A3777	*2/5/62	Not in Service, no pump
13	12-0726	95-518	97-212	16-41S-25E	37° 13 432 N 109° 12 415 N	659145	4121010	29718 A31023	12/9/62	
14	12-0727	95-519	97-213	16-41S-25E	37° 13 436 N 109° 12 473 N	659045	4121010	A-31023	12/12/62	
15	12-0728	95-520	97-214	17-41S-25E	37° 13 404 N 109° 12 365 N	659730	4120950	A-31023	12/26/62	
16	12-0729	95-521	97-215	17-41S-25E	37° 13 361 N 109° 12 341 N	659205	4120870	A-31023	1/6/63	
17	12-0730	95-522	97-216	17-41S-25E	37° 13 312 N 109° 12 325 N	659285	4120785	A-31023	1/12/63	
18	12-0731	95-523	97-217	17-41S-25E	37° 13 027 N 109° 12 894 N	659640	4120770	29718 A3777	4/5/63	
19	12-0732	95-524	97-218	17-41S-25E	37° 13 002 N 109° 12 903 N	659625	4120730	29718 A3777	4/10/63	
20	12-0733	95-525	97-219	17-41S-25E	37° 13 062 N 109° 12 994 N	659780	4120335	29718 A3777	4/17/63	
21	12-0734	95-526	97-220	17-41S-25E	37° 13 013 N 109° 12 945 N	659630	4120210	29718 A3777	4/19/63	
22	12-0735	95-527	97-221	17-41S-25E	37° 13 030 N 109° 12 015 N	659750	4120278	A3777 29718	4/22/63	
O-24	12-0736	95-528	97-222	17-41S-25E	37° 13 475 N 109° 12 504 N	659815	4120300		3/14/64	former oil well. MCH O-24, 13-3/8" x 10' 5-5/8" prod. cs. 1200' deep, out of service since 1975, needs P&A


Sundry Number: 35615 API Well Number: 43037309320000


Well # 14-33

Well No.	Well No.	Well #	Well #	Sec - Twp - R	S - T - R	Uplift	Depth	Appl #	Completed	Comments
14-33	06-0614	96-496	97-224	5-41S-24E	37° 15' 30" N	109° 17' 56" W	65174E	4124430	32-733	12-19-01
2	06-0615	96-497	97-225	5-41S-24E	37° 15' 30" N	109° 17' 56" W	65174E	4124430	32-733	12-19-01
3	06-0616	96-498	97-226	5-41S-24E	37° 15' 30" N	109° 17' 56" W	65174E	4124430	32-733	12-19-01
4	06-0617	96-499	97-227	5-41S-24E	37° 15' 30" N	109° 17' 56" W	65174E	4124430	32-733	12-19-01
5	06-0618	96-500	97-228	5-41S-24E	37° 15' 30" N	109° 17' 56" W	65174E	4124430	32-733	12-19-01
6	06-0619	96-501	97-229	5-41S-24E	37° 15' 30" N	109° 17' 56" W	65174E	4124430	32-733	12-19-01
7	06-0620	96-502	97-230	5-41S-24E	37° 15' 30" N	109° 17' 56" W	65174E	4124430	32-733	12-19-01
8	06-0621	96-503	97-231	5-41S-24E	37° 15' 30" N	109° 17' 56" W	65174E	4124430	32-733	12-19-01
9	06-0622	96-504	97-232	5-41S-24E	37° 15' 30" N	109° 17' 56" W	65174E	4124430	32-733	12-19-01
10	06-0623	96-505	97-233	5-41S-24E	37° 15' 30" N	109° 17' 56" W	65174E	4124430	32-733	12-19-01
11	06-0624	96-506	97-234	5-41S-24E	37° 15' 30" N	109° 17' 56" W	65174E	4124430	32-733	12-19-01
12	06-0625	96-507	97-235	5-41S-24E	37° 15' 30" N	109° 17' 56" W	65174E	4124430	32-733	12-19-01
13	06-0626	96-508	97-236	5-41S-24E	37° 15' 30" N	109° 17' 56" W	65174E	4124430	32-733	12-19-01
14	06-0627	96-509	97-237	5-41S-24E	37° 15' 30" N	109° 17' 56" W	65174E	4124430	32-733	12-19-01
15	06-0628	96-510	97-238	5-41S-24E	37° 15' 30" N	109° 17' 56" W	65174E	4124430	32-733	12-19-01
16	06-0629	96-511	97-239	5-41S-24E	37° 15' 30" N	109° 17' 56" W	65174E	4124430	32-733	12-19-01
14-33	06-0642	96-511	97-240	14-41S-24E	37° 15' 38" N	109° 17' 56" W	64585D	4115050		Water well abandoned 02-01-2005. CIP & Capped

Summary	35	operated wells								
	2	not prod	96-508	96-517						
	2	aband.	96-509	96-511						
	1	NTU	96-527							
	40	Total Wells in Field is: ROMA-55-06, WUP 16-406 to 96-528 & 96-202								

Additional Unlisted Wells at Ratherford	Sec - Twp - R	S - T - R	Uplift	Depth	Appl #	Completed	Comments
19		5-41S-24E	37° 15' 21" N	109° 16' 36" W		32-733	In Service
20		5-41S-24E	37° 15' 22" N	109° 16' 38" W		32-733	In Service
22		5-41S-24E	37° 15' 24" N	109° 16' 32" W		32-733	Operable but has power problems
23		5-41S-24E	37° 15' 26" N	109° 17' 04" W		32-733	Operable but has power problems
4	Additional unlisted wells						





**PROPOSED WELL LOCATION FOR
RESOLUTE NATURAL RESOURCES
RATHERFORD UNIT WELL NO. 29-33**

P.O. BOX 3651
FARMINGTON, N.M.
(505) 334-0408

SCALE: 1" = 3000'

JOB No. 10445

DATE: 03/01/13

**EXISTING ROAD
ACCESS/EGRESS**

**EXHIBIT
2A**

BY: H.S. DWG.#: 10445T01

RECEIVED: Mar. 14, 2013

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 03/14/2013

API NO. ASSIGNED: 43-037-30932

WELL NAME: 29-33

OPERATOR: RESOLUTE NATURAL (N2700)

CONTACT: SHERRY GLASS

PHONE NUMBER: 303-573-4886

PROPOSED LOCATION:

NWSE 29 410S 240E

SURFACE: 1859 FSL 1836 FEL

BOTTOM: 0544 FNL 1069 FWL

COUNTY: SAN JUAN

LATITUDE: 37.19107 LONGITUDE: -109.30255

UTM SURF EASTINGS: 650660 NORTHINGS: 4117418

FIELD NAME: GREATER ANETH (365)

INSPECT LOCATN BY: / /

Tech Review

Initials

Date

Engineering

Geology

Surface

LEASE TYPE: 2 - Indian

LEASE NUMBER: 14-20-603-407

SURFACE OWNER: 2 - Indian

PROPOSED FORMATION: DSCR

COALBED METHANE WELL? NO

RECEIVED AND/OR REVIEWED:

☒ Plat

☒ Bond: Fed[] Ind[2] Sta[] Fee[]
(No. PA002769)

☒ Potash (Y/N)

☒ Oil Shale 190-5 (B) or 190-3 or 190-13

☒ Water Permit
(No. 95-527)

☒ RDCC Review (Y/N)
(Date:)

☒ Fee Surf Agreement (Y/N)

☒ Intent to Commingle (Y/N)

LOCATION AND SITING:

R649-2-3.

Unit: RATHERFORD

R649-3-2. General

Siting: 460 From Qtr/Qtr & 920' Between Wells

R649-3-3. Exception

☒ Drilling Unit

Board Cause No: 152-6

Eff Date: 7-6-1998


Siting: Suspended General Siting

R649-3-11. Directional Drill

COMMENTS:

STIPULATIONS:

1- Lease Approval
2- DIRECTIONAL STIP



API Number: 4303730932

Well Name: 29-33


Township T41.0S Range R24.0E Section 29

Meridian: SLBM

Operator: RESOLUTE NATURAL RESOURCES

Map Prepared:

Map Produced by Diana Mason





GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

March 21, 2013

Resolute Natural Resources
1675 Broadway, Ste 1950
Denver, CO 80202


Subject: 29-33 Well, 1859' FSL, 1836' FEL, NW SE, Sec. 29, T. 41 South, R. 24 East, San Juan County, Utah

Ladies and Gentlemen:

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause: 152-6. The expected producing formation or pool is the Desert Creek Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-037-30932.

Sincerely,



John Rogers
Associate Director

JR/js
Enclosures

cc: San Juan County Assessor
Bureau of Land Management, Monticello Office

Operator: Resolute Natural Resources
Well Name & Number 29-33
API Number: 43-037-30932
Lease: 14-20-603-407

Location: NW SE **Sec.** 29 **T.** 41 South **R.** 24 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well – contact Carol Daniels at 801-538-5284 (please let a voicemail message if not available)

OR

Submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at <http://oilgas.ogm.utah.gov>

Notify the Division prior to commencing operations to plug and abandon the well.

- Contact Dustin Doucet at (801) 538-5281 office
(801) 733-0983 after office hours

3. Reporting Requirements

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited:

- Entity Action Form (Form 6) – due within 5 days of spudding the well
- Monthly Status Report (Form 9) – due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) – due prior to implementation
- Written Notice of Emergency Changes (Form 9) – due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) – due prior to implementation
- Report of Water Encountered (Form 7) – due within 30 days after completion
- Well Completion Report (Form 8) – due within 30 days after completion or plugging

4. State approval of this well does not supersede the required federal approval, which must be obtained prior to drilling.

5. In accordance with Utah Admin. R.649-3-21, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9																														
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-603-407																														
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NAVAJO																														
2. NAME OF OPERATOR: RESOLUTE NATURAL RESOURCES		7. UNIT or CA AGREEMENT NAME: RATHERFORD																														
3. ADDRESS OF OPERATOR: 1675 Boradway Ste 1950 , Denver, CO, 80202		8. WELL NAME and NUMBER: 29-33																														
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1859 FSL 1836 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 29 Township: 41.0S Range: 24.0E Meridian: S		9. API NUMBER: 43037309320000																														
9. FIELD and POOL or WILDCAT: GREATER ANETH		COUNTY: SAN JUAN																														
STATE: UTAH																																
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA																																
TYPE OF SUBMISSION <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 8/2/2013 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	TYPE OF ACTION <table style="width: 100%;"> <tr> <td><input type="checkbox"/> ACIDIZE</td> <td><input type="checkbox"/> ALTER CASING</td> <td><input type="checkbox"/> CASING REPAIR</td> </tr> <tr> <td><input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS</td> <td><input type="checkbox"/> CHANGE TUBING</td> <td><input type="checkbox"/> CHANGE WELL NAME</td> </tr> <tr> <td><input type="checkbox"/> CHANGE WELL STATUS</td> <td><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS</td> <td><input type="checkbox"/> CONVERT WELL TYPE</td> </tr> <tr> <td><input type="checkbox"/> DEEPEN</td> <td><input type="checkbox"/> FRACTURE TREAT</td> <td><input type="checkbox"/> NEW CONSTRUCTION</td> </tr> <tr> <td><input type="checkbox"/> OPERATOR CHANGE</td> <td><input type="checkbox"/> PLUG AND ABANDON</td> <td><input type="checkbox"/> PLUG BACK</td> </tr> <tr> <td><input type="checkbox"/> PRODUCTION START OR RESUME</td> <td><input type="checkbox"/> RECLAMATION OF WELL SITE</td> <td><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION</td> </tr> <tr> <td><input type="checkbox"/> REPERFORATE CURRENT FORMATION</td> <td><input type="checkbox"/> SIDETRACK TO REPAIR WELL</td> <td><input type="checkbox"/> TEMPORARY ABANDON</td> </tr> <tr> <td><input type="checkbox"/> TUBING REPAIR</td> <td><input type="checkbox"/> VENT OR FLARE</td> <td><input type="checkbox"/> WATER DISPOSAL</td> </tr> <tr> <td><input type="checkbox"/> WATER SHUTOFF</td> <td><input type="checkbox"/> SI TA STATUS EXTENSION</td> <td><input type="checkbox"/> APD EXTENSION</td> </tr> <tr> <td><input type="checkbox"/> WILDCAT WELL DETERMINATION</td> <td><input type="checkbox"/> OTHER</td> <td>OTHER: <input style="width: 100px;" type="text"/></td> </tr> </table>		<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR	<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR																														
<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME																														
<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE																														
<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION																														
<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK																														
<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION																														
<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON																														
<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL																														
<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION																														
<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>																														
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Resolute proposes a revision to recompletion procedure submitted previously on the subject well. Attached is revised procedure and proposed wellbore diagram																																
Accepted by the Utah Division of Oil, Gas and Mining Date: August 09, 2013 By: <u>Derek Quist</u>																																
NAME (PLEASE PRINT) Sherry Glass		PHONE NUMBER 303 573-4886																														
SIGNATURE N/A		TITLE Sr Regulatory Technician																														
DATE 7/31/2013																																

RESOLUTE

NATURAL RESOURCES

RU 29-33H Single Lateral Producer - Revision 2 Completion Procedure 7-30-13

Job scope: Sidetrack out of 7" wellbore, drill Lateral #1 ~3850' to the NW, acid stimulate, and run new **ESP BHA** with new 2-7/8" production tubing.

Procedure

This procedure revision begins after step 20 of the previous procedure below dated 2-11-2013, and includes CTU to perform caustic flush and acid stimulation of the lateral.

- 1) Perform necessary dirt work to accommodate 24-hour drilling rig.
- 2) MIRU Drilling Rig. Kill well as necessary.
- 3) Pull & LD rods & insert pump, inspecting condition.
- 4) ND WH; NU & test BOPE.
- 5) Release TAC, POH & LD 2-7/8" production tubing & BHA.
- 6) PU AOH workstring & RIH with bit/scraper to ~5630' (Top of perforations at 5640'KB.) Reverse circulate clean.
- 7) POH & LD bit and scraper.
- 8) RU BlueJet Wireline. Run MTT / 40-Arm Caliper Casing Inspection Log from 5630' to surface. POH & LD MTT.
- 9) Run RADII Sector Cement Bond Log from 5630' to 1000'.
- 10) Run & set RBP on wireline, spaced per Baker Hughes rep for KOP at ~ 5455'. Note: *Exact RBP setting depth will be determined from MTT & CBL data; See also Mesa West directional plan with KOP 5454.8' for Leg #1/lower lateral.*
- 11) RD BlueJet Wireline.
- 12) PU & RIH with Whipstock/Debris Mgmt Sub/Anchor/Mills.
Note: *Whipstock will be landed on RBP (Step 10).*
Note: *Whipstock Slide = 3 degree from vertical.*
Note: *Window Mills: Starter mill = 6-1/8" coarse blade, Dress Mill = 6-1/8" fine blade. Production Csg: 7", 23# & 26#, K-55 @ 5800'.*
- 13) Orient whipstock with gyro.
Note: *Leg #1 Azimuth ~318.99 degrees; refer to Mesa West final Directional Plan.*
- 14) Set whipstock anchor.
- 15) Mill window. Note: *Ensure that dress mill completely exits window.*
- 16) POH & LD window mills.
- 17) PU & RIH with 6-1/8" Tri-Cone bit, mud motor, and MWD package on workstring.
- 18) Drill OH Lateral leg #1 to 9134'MD/TD.
Note: *Drill OH lateral w/ produced water & N2.*
- 19) Circulate the lateral clean, POH & LD BHA.
- 20) Set RBP w/BHP tools below at 5090'; set 2nd RBP @ 623'. Wellbore has 10 ppg brine in lateral, 13.2 mud between RBP's. Released DJ rig #1 on 7-27-13.

- 21) MIRU daylight rig.
- 22) Install G-45 wellhead spool for 2-7/8 ESP completion. NOTE: Complete G-45 assembly is currently in stock; no need to purchase new.
- 23) NU & Test BOPE.
- 24) Kill well as necessary. Retrieve RBP's at 623' & 5090'. Have the BHP data from the instruments below the bottom RBP sent to Jim Styler (jstyler@ResoluteEnergy.com) and Jason Stewart (jstewart@ResoluteEnergy.com).
- 25) PU & RIH with 7" packer on the 2-7/8 workstring.
- 26) Set pkr at 5125' KB, which is 36' above window at 5161.5 - 5169' -- no tailpipe necessary.
- 27) Test packer & backside to 500 psi & leave this pressure in place.
- 28) MIRU 1-1/4" CTU, install hard line & choke manifold.
- 29) Put a jetting/swirl nozzle on the CT, appropriate for washing down the walls of the 6-1/8" diameter lateral to remove the residual lubricant used in drilling the hole.
- 30) PT the lubricator, BOP's & coil reel to 4500 psi.
- 31) RIH with coil tubing & nozzle to the end of the lateral at 9134' MD, checking pickup weight at regular intervals on the trip in.
- 32) Jet/wash the walls of the lateral back to the window using caustic solution, while taking returns to a frac tank at surface. Composition & details of the caustic solution to be determined.
- 33) Run CTU back to the toe of the lateral and displace the lateral to water to remove any residual caustic solution.
- 34) RU acid vendor to acidize the lateral with 4650 gals inhibited 20% HCL (110.8 bbls). Max Treating Pressure = 3700 psi on the 2-7/8. Pump 5 bbls fresh water ahead of acid; displace acid with fresh water.
- 35) With CTU nozzle near the end of the lateral at 9134', and returns shut in, begin acidizing. Pump at maximum rate & pressure allowable on the CT and work the nozzle the full length of the lateral back to the window, then out to the toe again to finish. At 3/4 bpm rate, coil should move at 53.7 fpm; at 1 bpm rate, coil should move at 72 fpm to accomplish this.
- 36) Pump 150 bbls fresh water displacement while pulling the CT back to just above the window (lateral volume w/o CTU in it is 144.6 bbls).
- 37) POOH & RD CTU. Shut well in for 2 hours, or overnight if practical.
- 38) RU Global N2 to the workstring. Lift back ~150% of the acid load volume, or until oil or gas handling becomes an issue.
- 39) Re-kill the well with water. POH & LD treating packer.
- 40) RIH with retrieving hook & jars. Latch whipstock & release anchor.
- 41) POH & LD Whipstock/Debris Mgmt Sub/Anchor.
- 42) Retrieve RBP at the base of the window. Window = 5161.5 to 5169'.
- 43) PU & RIH with Centinel, ESP assembly, ESP cable, and new 2-7/8" 6.5# J-55 SMLS FBNAU tubing. Include check valve two joints above top of ESP and sliding sleeve w/2.31" X nipple profile 1 joint above the check valve. Include 1/4" capillary string to 60' depth. Land bottom of Centinel at ~ 5150'.
- 44) Perform WH penetrator cable tie-ins at tubing hanger, including 1/4" capillary stinger for chemical injection, and land tubing.
- 45) ND BOPE, NU WH.
- 46) RDMO WSU.

- 47) Complete electrical tie-ins to VSD and transformer.**
- 48) Notify Area Production Supervisor Billison Rentz (970) 779-9273 that the well is ready to return to production.**
- 49) Begin appropriate chemical treatment.**

RATHERFORD UNIT # 29-33H

PRODUCER

GREATER ANETH FIELD

1859' FSL & 1836' FEL


SEC 29-T41S-R24E

SAN JUAN COUNTY, UTAH

API 43-037-30932

PRISM 0043140

Attachment 2 - **Proposed**



J. Styler 2-11-2013

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-603-407
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NAVAJO
2. NAME OF OPERATOR: RESOLUTE NATURAL RESOURCES		7. UNIT or CA AGREEMENT NAME: RATHERFORD
3. ADDRESS OF OPERATOR: 1675 Boradway Ste 1950 , Denver, CO, 80202		8. WELL NAME and NUMBER: 29-33
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1859 FSL 1836 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 29 Township: 41.0S Range: 24.0E Meridian: S		9. API NUMBER: 43037309320000
PHONE NUMBER: 303 534-4600 Ext		9. FIELD and POOL or WILDCAT: GREATER ANETH
COUNTY: SAN JUAN		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 8/18/2013	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input checked="" type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between;"> <div style="width: 65%;"> <p>Resolute completed a single lateral from the vertical wellbore in this well, to better drain the Desert Creek IA and IB. A new ESP BHA was run with new 2-7/8" production tubing. Attachment is daily job log. A completion report was filed 8/27/13. Well was returned to production 8/18/13.</p> </div> <div style="width: 30%; text-align: right;"> <p>Accepted by the Utah Division of Oil, Gas and Mining</p> <p>FOR RECORD ONLY</p> <p>August 27, 2013</p> </div> </div>		
NAME (PLEASE PRINT) Sherry Glass	PHONE NUMBER 303 573-4886	TITLE Sr Regulatory Technician
SIGNATURE N/A	DATE 8/27/2013	



Daily Activity Report

Well Name: Ratherford U 2933

API Number 43037309320000	Section 29	Township 41S	Range 24E	Field Name Ratherford	County San Juan	State/Province Utah
Ground Elevation (ft) 4,911.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 16.90	KB-Casing Flange Distance (ft)	Well Spud Date/Time 12/26/1983 00:00	Rig Release Date/Time 1/28/1984 00:00	

Job Category Drilling	Primary Job Type Drilling - re-entry	Secondary Job Type
Start Date 6/7/2013	End Date 8/18/2013	AFE Number 10013781

Objective
Job scope: Sidetrack out of 7" wellbore, drill Lateral #1 ~3850' to the NW, and Lateral #2 ~1500' to the SE, acid stimulate, and run new rod pumping BHA with new 2-7/8" production tubing.

Contractor Four Corners Well Service	Rig Number 6	Rig Type Service
Contractor D&J	Rig Number 1	Rig Type Drilling - Double
Contractor Key	Rig Number 670	Rig Type

Report Start Date 2/8/2013	Report End Date 2/8/2013	Operations Summary United Field Services surveyed the loc. Well survey is complete
Report Start Date 6/7/2013	Report End Date 6/7/2013	Operations Summary Load and Haul pit runs for road and blade
Report Start Date 6/10/2013	Report End Date 6/10/2013	Operations Summary Load and haul dirt, load and haul pit runs and blade road
Report Start Date 6/13/2013	Report End Date 6/13/2013	Operations Summary Test hole, dig out at RU 29-33
Report Start Date 6/18/2013	Report End Date 6/18/2013	Operations Summary Bleed off flow line for crew, unload at RU Battery 2
Report Start Date 6/19/2013	Report End Date 6/19/2013	Operations Summary Bleed off flow line for crew, unload at MCU area 1 Battery
Report Start Date 6/21/2013	Report End Date 6/21/2013	Operations Summary Dig out flow line at location and drag down the road off location, back fill and back drag location
Report Start Date 6/25/2013	Report End Date 6/25/2013	Operations Summary Haul 5 loads pf fresh water to 29-33 to water down road and location
Report Start Date 6/26/2013	Report End Date 6/26/2013	Operations Summary Haul 8 loads of FW, haul to 29-33 wet down roads to location
Report Start Date 6/27/2013	Report End Date 6/27/2013	Operations Summary Move rig from MCU to location, spot in. Fill out jsa, hold tailgate safety meeting. Spot pad and pump. Spot rig on pad. Shut down.

Dur (hrs)	Comment
1.00	Move rig from MCU to location, spot in.
0.50	Fill out jsa, hold tailgate safety meeting.
1.00	Spot pad and pump. Spot rig on pad. Shut down.
1.00	

Report Start Date 6/28/2013	Report End Date 6/28/2013	Operations Summary JSA, hold tailgate safety meeting on emergency response plan. Set out safety equipment. Have digging permit filled out by B.Rentz, dig and set 2 anchors. Finish spotting equipment. Rig up pulling unit, tighten and flag guy lines. 30 psi on tubing, 120 psi on casing, blow down to pit. Spot empty rod trailer. Unseat pump, lay down polish rod, subs, 75- 7/8, 142- 3/4, 8- 1", 2 subs, pump and gas anchor. Lunch. Pump 20 bbl's down casing, 5 bbl's down tubing. Change blocks over for tubing. NDWH, release tac, nubops. Rig up floor, tongs, hand rails and ladder. Pull 1 jnt, add test pckr, set 20' in hole. Test bop-hydril @200psi low, 1100 psi high, good test. Release and lay down packer. TOOH laying down 160 jnt's of tubing on float. TOOH with 19 jnt's to derrick, lay down bha. Make up rbp, tih with 19 jnt's, set rbp @ 620' KB, J off. Pumped 60 bbl's produced water, hole never filled, casing on vacuum, retag rbp, still in place. Notify D.Trimble of possible hole in casing. Lay down 19 jnt's and retrieving tool. Shut well in.
--------------------------------	------------------------------	--

Dur (hrs)	Comment
1.00	
1.00	Fill out jsa, hold tailgate safety meeting on emergency response plan. Set out safety equipment.
3.00	Have digging permit filled out by B.Rentz, dig and set 2 anchors.
1.50	Finish spotting equipment. Rig up pulling unit, tighten and flag guy lines.
0.50	30 psi on tubing, 120 psi on casing, blow down to pit.
2.50	Spot empty rod trailer. Unseat pump, lay down polish rod, subs, 75- 7/8, 142- 3/4, 8- 1", 2 subs, pump and gas anchor. Lunch.
0.50	Pump 20 bbl's down casing, 5 bbl's down tubing. Change blocks over for tubing.
1.00	NDWH, release tac, nubops. Rig up floor, tongs, hand rails and ladder.
0.50	Pull 1 jnt, add test pckr, set 20' in hole. Test bop-hydril @200psi low, 1100 psi high, good test. Release and lay down packer.
2.00	TOOH laying down 160 jnt's of tubing on float.
0.50	TOOH with 19 jnt's to derrick, lay down bha.
0.50	Make up rbp, tih with 19 jnt's, set rbp @ 620' KB, J off.



Daily Activity Report

Well Name: Ratherford U 2933

API Number 43037309320000	Section 29	Township 41S	Range 24E	Field Name Ratherford	County San Juan	State/Province Utah
Ground Elevation (ft) 4,911.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 16.90	KB-Casing Flange Distance (ft)	Well Spud Date/Time 12/26/1983 00:00	Rig Release Date/Time 1/28/1984 00:00	

Dur (hrs)		Comment
1.00		Pumped 60 bbl's produced water, hole never filled, casing on vacuum, retag rbp, still in place. Notify D.Trimble of possible hole in casing.
0.50		Lay down 19 jnt's and retrieving tool.
0.50		Shut well in.
1.00		
Report Start Date 6/29/2013	Report End Date 6/29/2013	Operations Summary Fill out jsa, hold tailgate safety meeting on heat, rigging down. RD tongs, hand rails, ladder and floor. ND BOPs, set on rack. MU B-1 flange with tapped bull plug and niddle valve. RD pump and pit. Drop lines, RD PU, MOL. Move equipment off location. Move rig to AU yard. Turn location over to Lansing to prep for D&J rig.
Dur (hrs)		Comment
1.00		
0.50		Fill out jsa, hold tailgate safety meeting on heat, rigging down.
1.00		Rig down tongs, hand rails, ladder and floor. NDBOPs, set on rack.
0.50		Make up b-1 flange with tapped bull plug and niddle valve.
1.00		Rig down pump and pit. Drop lines, rig down pulling unit. Move off location. Move equipment off location.
0.50		Move rig to AU yard.
1.00		
Report Start Date 6/30/2013	Report End Date 6/30/2013	Operations Summary Haul fresh water to water down the road and location
Report Start Date 7/2/2013	Report End Date 7/2/2013	Operations Summary Move rig from AU yard to location. JSA, hold tailgate safety meeting on hand protection, proper gloves for the job. Rig up pulling unit, tighten and flag guy lines. Check pressure's, 35 psi on casing, blow down gas. ND B-1 flange. NU BOPS. Spot in ws, pick up pckr and 1 jnt, set 20' in hole. Test bop-hydril 300 psi L, 1000 psi H, good test. Release and lay down pckr. Make up retrieving tool, tally, pick up 20 jnt's, latch onto rbp and release. TOOH with 20 jnt's, lay down rbp. Make up rbp, pckr combo, run 20 jnt's, continue picking up 140 jnt's, 160 jnt's total, set rbp @ 5175', lay down 1jnt, 159 jnt's in hole. Circulate hole with 200 bbl's fresh water, still gassy.
Dur (hrs)		Comment
1.00		
1.00		Move rig from AU yard to location.
1.00		Fill out jsa, hold tailgate safety meeting on hand protection, proper gloves for the job.
1.50		Spot in pad and pump. Spot rig on pad, level out, rig up pulling unit, tighten and flag guy lines.
0.50		Check pressure's, 35 psi on casing, blow down gas.
1.50		ND B-1 flange. NU BOPS, rig up floor, hand rails, ladder and tongs.
1.00		Spot in ws, pick up pckr and 1 jnt, set 20' in hole. Test bop-hydril 300 psi L, 1000 psi H, good test. Release and lay down pckr.
0.50		Make up retrieving tool, tally, pick up 20 jnt's, latch onto rbp and release.
0.50		TOOH with 20 jnt's, lay down rbp.
4.50		Make up rbp, pckr combo, run 20 jnt's, continue picking up 140 jnt's, 160 jnt's total, set rbp @ 5175', lay down 1jnt, 159 jnt's in hole.
2.00		Circulate hole with 200 bbl's fresh water, still gassy.
0.50		SWI.
1.00		
Report Start Date 7/3/2013	Report End Date 7/3/2013	Operations Summary Fill out jsa, hold tail gate safety meeting on house keeping, clean doghouse, rig floor and cat walks. Check well pressure's, 80 psi on tubing, 0 psi on casing, open to pit, blow down gas. Circulate hole clean with 50bbl's fresh water, no gas coming back. Set packer @5163', test rbp and pckr @530 psi, good test. Test casing from 5163' to surface @520 psi, good test. Witnessed by D.Trimble. Release pckr, leave rbp set @5175', tooh laying down 159 jnt's on float, lay down pckr. Spot in and rig up Blue Jet, hold saety meeting on wire line work, run cil from 5170' to surface, run cbl from 5170' to 1000', rig down logging truck. Have logs sent to D.Trimble. Rig down tongs, ladder, hand rails and floor. NDBOPs, set on rack. Make up B-1 flange with tapped bull plug. Rig down pulling unit. Move rig and equipment to AU yard. Shut down.
Dur (hrs)		Comment
1.00		
0.50		Fill out jsa, hold tail gate safety meeting on house keeping, clean doghouse, rig floor and cat walks.
0.50		Check well pressure's, 80 psi on tubing, 0 psi on casing, open to pit, blow down gas.
0.50		Circulate hole clean with 50bbl's fresh water, no gas coming back.
0.50		Set packer @5163', test rbp and pckr @530 psi, good test. Test casing from 5163' to surface @520 psi, good test. Witnessed by D.Trimble.
2.00		Release pckr, leave rbp set @5175', tooh laying down 159 jnt's on float, lay down pckr.
5.00		Spot in and rig up Blue Jet, hold saety meeting on wire line work, run cil from 5170' to surface, run cbl from 5170' to 1000', rig down logging truck. Have logs sent to D.Trimble.
0.50		Rig down tongs, ladder, hand rails and floor. NDBOPs, set on rack. Make up B-1 flange with tapped bull plug.



Daily Activity Report

Well Name: **Ratherford U 2933**

API Number 43037309320000	Section 29	Township 41S	Range 24E	Field Name Ratherford	County San Juan	State/Province Utah
Ground Elevation (ft) 4,911.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 16.90	KB-Casing Flange Distance (ft)	Well Spud Date/Time 12/26/1983 00:00	Rig Release Date/Time 1/28/1984 00:00	

Dur (hrs)		Comment
1.00		Rig down pulling unit.
1.00		Move rig and equipment to AU yard. Shut down.
1.00		
Report Start Date 7/5/2013	Report End Date 7/6/2013	Operations Summary Move rig from AU 317X to RU 29-33H, Spot in and rig up equipment, N/U 7 1/16" BOP stack, Fabricate 6" lines to gas buster with welders, Pressure test BOPE and casing.
Dur (hrs)		Comment
4.00		Move rig from AU 317X to RU 29-33H
8.00		Spot in and rig up all equipment
9.00		N/U 7 1/16" BOP stack, Rig up and pre fab 6" lines to gas buster with welders.
		Test 3 1/2" pipe rams, inner and outer choke valves and blind rams to 250 psi low f/5 min, 3000 psi high f/10 min, test annular to 1500 psi f/10 min, Test casing to 500psi for 30 min.
Report Start Date 7/6/2013	Report End Date 7/7/2013	Operations Summary Finish R/U gas buster, Pressure test BOPE, Load racks, Strap pipe, RIH 38 jts 3 1/2" HWDP, Stand back 16 stds HWDP, P/U whip stock, Mills, UBHO, TIH 19 stds HWDP, P/U 128 jts 3 1/2" DP, R/U Blue Jet, Orientate whipstock and set @ 5175' tool face @ 319.47*, R/D Blue Jet, P/U & R/U 3.5 power swivel. Start milling window @ 05:00
Dur (hrs)		Comment
1.50		Finish Test 3 1/2" pipe rams, inner and outer choke valves and blind rams to 250 psi low f/5 min, 3000 psi high f/10 min, test annular to 1500 psi f/10 min, Test casing to 500psi for 30 min. All test good
5.00		Finish fabricating gas buster and flow line.
2.50		Lay out and strap 38 jts 3 1/2" HWDP and 126 jts 3 1/2" drill pipe.
2.50		M/U 6 1/8" bit, bit sub, P/U 38 jts 3 1/2" HWDP.
0.50		POOH 19 stds HWDP
7.50		P/U whipstock assembly and orientate to UBHO sub, RIH w/ 18 stds HWDP and P/U 128 jts 3 1/2" DP.
0.50		R/U Blue Jet for gyro run
1.50		RIH w/ gyro for whipstock orientation Set whipstock @ 5175' and tool face @ 319.47*
0.50		R/D Blue Jet wireline.
1.00		P/U and R/U 3.5 power swivel.
1.00		Start milling window, WOB 1, GPM 173, RPM 60
Report Start Date 7/7/2013	Report End Date 7/8/2013	Operations Summary Repack swivel, Mill window and 8' rathole, TOOHL/D & Load out mills, P/U and orientate directional tools, TIH, P/U swivel and R/U blue jet wireline.
Dur (hrs)		Comment
1.00		Remove and replace swivel washpipe and upper packing.
12.00		Milled window plus 8' rat hole to 5176', Reamed window until there was no drag up or down,
3.50		Hang back swivel, POOH, lay down and load out mills.
0.50		Safety meeting with rig crew, directional drillers and MWD, prior to picking up tools.
6.50		P/U directional BHA with motor bend @ 1.8", .56 Rev/gal and orientate same, TIH w/15 stds DP, 19 stds HWDP and 47 stds DP to 5174', P/U swivel.
0.50		R/U Blue Jet for gyro operations
Report Start Date 7/8/2013	Report End Date 7/9/2013	Operations Summary TIH W/ Gyro and Blue Jet wireline and directional tools, build angle for curve, sliding most of day. Rotated @ 5 AM.
Dur (hrs)		Comment
0.50		R/U Bluejet W/Gyo Data tools to run Gyo to build angle out of casing window.
1.00		P/U Swivel W/ wireline.
22.50		Building Angle in new formation to get out of casing window with Gyro tool in hole, F/5174' T/5430', sliding W/ no rotating until 5 AM rotated first joint, Minimal drag while siding.
		W/O bit 12K, ROP 20, GPM 187, SPP 1487psi, RPM 0 Sliding,
		Last Survey @ 5:45 on Depth 5375' INC 25.75, AZ 314.40
Report Start Date 7/9/2013	Report End Date 7/10/2013	Operations Summary Building curve and angle in 6-1/8" hole section, sliding and rotating, running polymer sweeps. Drilling w/ 8.8 lb produced water, Diff PSI 80 -107, WOB 25-35K, ROP 11'-26' hr, SPP 1400-1560 psi, Drill F/ 5430' to 5740'.
		Last MWD survey, 5685' INC 57.20, AZ 317.60.
Dur (hrs)		Comment
24.00		BLDNG curve and Angle in 6-1/8" hole section, sliding and rotating, running polymer sweeps, Drilling W/ 8.8lb produced water, Diff PSI 80 -107, WOB25-35K, ROP 11'-26' hr, SPP 1400-1560psi, Drill F/ 5430' to 5740'
		Last MWD survey, 5685' INC 57.20, AZ 317.60



Daily Activity Report

Well Name: Ratherford U 2933

API Number 43037309320000	Section 29	Township 41S	Range 24E	Field Name Ratherford	County San Juan	State/Province Utah
Ground Elevation (ft) 4,911.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 16.90	KB-Casing Flange Distance (ft)	Well Spud Date/Time 12/26/1983 00:00	Rig Release Date/Time 1/28/1984 00:00	

Report Start Date 7/10/2013	Report End Date 7/11/2013	Operations Summary Rotating & sliding, building 6-1/8" hole section, building curve F/5740' T/5783'. At 11:00 SPP psi spiked to 2500 psi. While drilling, the psi was staying @ 1500 psi, Smith 6-1/8" tir-cone bit stopped making any more footage. Decided to TOOH, once out of hole the Tri-cone bit was missing one cone and shank, also the gap sub was damaged on the plastic bands. Called Weatherford Fishing to bring out 6-1/8" magnet and junk basket. TIH with magnet and junk basket @ 21:00. Circulate, rotate on btm, TOOH.
--------------------------------	------------------------------	---

Dur (hrs)

Comment

5.00 Rotating & sliding building 6-1/8" hole section building curve, F/5740' T/5783' @ 11:00 SPP psi spiked to 2500 psi it while drilling the psi was staying @ 1500 psi, Smith 6-1/8" tir-cone bit stopped making any more footage.

Last MWD Survey Depth: 5735" INC 61.6 AZ 318.5

5.00 TOOH, once out of hole the Tri-cone bit was missing one cone and shank, also the gap sub was damaged on the plastic bands. Called Weatherford Fishing to bring out 6-1/8" magnet and junk basket,

5.00 Waiting on Weatehrford Fisherman with tools to fish bit cone and shank.

3.00 TIH with magnet and junk basket @ 21:00.

1.00 Fishing for 6-1/8" cone and shank, W/ open ended tooth bit, Magnet & junk Basket, Tagged @ 5783' this is current new hole depth, got good circulation, circulated btms up, work joint, circulate on btm turn pump off anf TOOH.

Note: did encounter tight spot coming out of hole at 5700', turned pump on and ciclated through tight spot.

5.00 TOOH, Got out of hole and did retrieve fish, looks like all junk is on fish, we will break down fishing BHA, Make up Directional BHA with Smith PDC TIH start curve and lateral.

Report Start Date 7/11/2013	Report End Date 7/12/2013	Operations Summary Make up 6-1/8" PDC w/directional 1.83 DEG bend motor & MWD tools. TIH, drilled 6-1/8" hole section building curve and angle from 5783' - 5935'.
--------------------------------	------------------------------	---

Last MWD survey @ 5834' INC 70.8 AZ 319.4

Dur (hrs)

Comment

2.00 P/U 6-1/8" Smith PDC Bit, Type MDS:613, SN# JG1791, & directional tools 1.83 motor W/ Monels, & MWD tools.

7.00 TIH W/ PDC and Directional tools W/ 1.83 Deg Bend Motor. Including MWD, Broke circulation @ 4000', P/U Singles TIH to window @ 5174', Then rotate and circulate each JNT, Hit tight spot @ 5700' TO 5710' cleaned this section of hole, Then continued to Rotate and circulate to 5780' Circulate 1-1/2 BTMS UP, & Ran Polymer sweeps to make sure we had hole clean of any trash that might me in hole,

NOTE: No issues TIH into window, & in open hole only tight spot @ 5700' to 5710' did clean this section out before proceeding to btm.

15.00 Building angle and curve F/5783' T/5935', Sliding & Rotating, Pump Rate 195 GPM, DIFF PSI 85-125, WOB 13-30K, SPP 1350-1550 PSI, RPM 40-50, Sliding and Rotating good W/ Minimal Torque,

Last MWD Survey @ 5834' INC 70.8 AZ 319.4

Report Start Date 7/12/2013	Report End Date 7/13/2013	Operations Summary DRI 6-1/8" hole section Building curve and angel. F/5935' T/6023' .DRI 6-1/8" Lateral hole section F/6023' T/6205',
--------------------------------	------------------------------	---

NOTE: @ 6099' Rotation Torque 3,000 to 3,500, P/U WT 90k, Slide WT 80k, Rotation WT 84k,

With PDS Super (L) @ 6161' Rotation Torque 2,800, P/U WT 80k, Slide wt 74k, Rotation wt 80k,

Dur (hrs)

Comment

5.50 Sliding and Rotating building 6-1/8" curve F/5935' T/6023', We were having Trouble with hole cleaning, So we build a 35 vis, 8.7 lb, 9.5 PH system. This helped get cutting out of hole, ROP picked up and we were able to get directional tool to be more agressive so we could get close to target landing depth.

NOTE: We landed curve 4.32' lower than target depth, @ 6023' INC 91.25 AZ 320.2

18.50 DRLG 6-1/8" Lateral section F/6023' T/6205', W/ 38 VIS, 8.32 LB, 9.5 PH system. We drilled 100' of new hole and did Drag, Torque, RPM, & ROP tests, Then we added the product PDS Super (L) Lubricant from (Binder Science), Still seeing slow drilling.

We did see some oil @ 6023' & some natural gas,

NOTE: @ 6099' Rotation Torque 3,000 to 3,500, P/U WT 90k, Slide WT 80k, Rotation WT 84k,

With PDS Super (L) @ 6161' Rotation Torque 2,800, P/U WT 80k, Slide wt 74k, Rotation wt 80k,

Report Start Date 7/13/2013	Report End Date 7/14/2013	Operations Summary DRLG 6-1/8" Lateral section F/6205' T/6225', Work on power swivel, POOH to window, Change out power unit and swivel, TIH, DRLG 6-1/8" Lateral section F/6225' T/6266'
--------------------------------	------------------------------	---



Daily Activity Report

Well Name: Ratherford U 2933

API Number 43037309320000	Section 29	Township 41S	Range 24E	Field Name Ratherford	County San Juan	State/Province Utah
Ground Elevation (ft) 4,911.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 16.90	KB-Casing Flange Distance (ft)	Well Spud Date/Time 12/26/1983 00:00	Rig Release Date/Time 1/28/1984 00:00	

Dur (hrs)	Comment
2.00	DRLG 6-1/8" Lateral section F/6205' T/6225', W/ 38 VIS, 8.32 LB, 9.5 PH system.
	NOTE: @ 6099' Rotation Torque 3,000 to 3,500, P/U WT 90k, Slide WT 80k, Rotation WT 84k,
	, 0.50 Service rig, Grease crown, blocks and swivel.
4.00	Motor on power swivel unit went down. Attempt to restart. No success, Wait on mechanic from High Tech rental, trouble shoot, wait on parts from town and or replacement Power swivel unit from Weatherford rental. Circulate and work pipe while waiting on mechanic and replacement power swivel unit.
1.50	Hang back swivel and POOH F/6225' - T/5139'
9.00	Power unit and swivel from Weatherford rental showed up before the parts and second mechanic for High Tech. Rig down High Tech swivel and power unit. Spot in and rig up power unit and swivel from Weatherford rental. Mechanics for High Tech rental worked on there unit on location replacing fuel and oil sensors with no success. A mechanic from Wagner (Catipiller) will be on location tomorrow to trouble shoot problems on High Tech swivel power unit.
	Note: Monitor well at shale shaker, no losses or gains.
0.50	TIH F/5139' - T/5414', P/U swivel and break circulation.
1.50	Circulate and work pipe @ 5414'
1.00	Continue TIH F/5414' - T/6225', P/U swivel break circulation, Survey and tag bottom (No fill)
4.00	DRLG 6-1/8" Lateral section F/6225' T/6266', W/ 38 VIS, 8.5 LB, 8.5 PH

Report Start Date 7/14/2013	Report End Date 7/15/2013	Operations Summary Drlg 6-1/8" lateral section F/6266' T/6721'.
--------------------------------	------------------------------	--

Dur (hrs)	Comment
6.00	DRLG 6-1/8" Lateral section - Rotate F/6266' - T/6369', W/ 36 VIS, 8.6 LB, 7.5 PH,
6.00	DRLG 6-1/8" Lateral section - Rotate F/6369' T/6503', W/ 36 VIS, 8.6 LB, 7.5 PH, WL 8
6.00	DRLG 6-1/8" Lateral section - Rotate F/6503' T/6636', 36 VIS, 8.6 MW, 8.5 PH, WL 9
6.00	DRLG 6-1/8" Lateral section - Rotate F/6636' T/6658', Slide F/6658' T/6668', Rotate F/6668' T/6718', Slide F/6718 - T/6720, VIS, 8.6 MW, 8.5 PH, WL 9, P/U WT 86, SOW 76, ROT WT 80.

Report Start Date 7/15/2013	Report End Date 7/16/2013	Operations Summary DRLG 6-1/8" Lateral section F/6721' - T/7291'
--------------------------------	------------------------------	---

Dur (hrs)	Comment
6.00	DRLG 6-1/8" Lateral section - Slide F/6720 - T/6723, Rotate F/6723' - T/6780', Slide F/6780' - T/6788', Rotate F/6788' - T/6832', Slide F/6832' - T/6842', VIS 38, 8.9 MW, 8.5 PH, WL 5.5, P/U WT 86, SOW 76, ROT WT 80.
6.00	DRLG 6-1/8" Lateral section - Rotate F/6842' - T/6885', Slide F/6885' - T/ 6894', Rotate F/6894' - T/ 6989', VIS 36, 8.7 MW, 9.5 PH, WL 8, P/U WT 86, SOW 76, ROT WT 80.
6.00	DRLG 6-1/8" Lateral section - Rotate F/6989' - T/7013', Slide F/ 7013' - T/7029', Rotate F/7029' - T/7164', VIS 39, MW 8.8 , PH 9.5, WL 6.4, P/U WT 88, SOW 76, ROT WT 80.
6.00	DRLG 6-1/8" Lateral section - Rotate F/7164' - T/7184', Slide F/7184' - T/7188', Rotate F/7188' - T/7291', VIS 40, MW 8.9 , PH 9.5, WL 6.4, P/U WT 88, SOW 76, ROT WT 80.

Report Start Date 7/16/2013	Report End Date 7/17/2013	Operations Summary Drlg 6-1/8" Lateral section F/7291' - T/7371'. Well flowing, shut in and monitor pressure build up to 720 psi. SD injector well, bleed down pressure and open rams. Drlg 6-1/8" lateral section F/7371' - T/7706'.
--------------------------------	------------------------------	--

Dur (hrs)	Comment
3.00	DRLG 6-1/8" Lateral section - Rotate F/7291' - T/7308', Slide F/7308' - T/7314', Rotate F/7314 - T/7371', VIS 37, MW 8.9 , PH 9.5, WL 8.5, P/U WT 88, SOW 76, ROT WT 80.
2.00	Well flowing 1" stream, Shut in well pressured up to 720 psi. Notified supervisor and was informed a injection well in the area would be shut down. Bleed down pressure off well bore through choke manifold, opened pipe rams and continued drilling.
6.00	Drlg 6-1/8" Lateral section - Rotate F/7371' - T/7401', Slide F/7401' - T/7406', Rotate F/7406' - T/7464', Slide F/7464' - T/7468', VIS 37, MW 8.8 , PH 9, WL 9, P/U WT 88, SOW 72, ROT WT 83.
6.00	Drlg 6-1/8" Lateral section - Rotate F/7468' - T/7478', Slide F/7478' - T/7485', Rotate F/7485' - T/7567', VIS 37, MW 8.8 , PH 9, WL 9, P/U WT 88, SOW 74, ROT WT 80.
7.00	Drlg 6-1/8" Lateral section - Slide Slide F/7567' - T/7575', Rotate F/7575' - T/7629', Slide F/7629' - T/7639', Rotate F/7639' - T/7692', Slide F/7692' - T/7697', Rotate F/7697' - T/7706', MW 8.9 , PH 9.5, WL 9.8, P/U WT 88, SOW 76, ROT WT 80.

Note; Well flowing 11 bbls/hr @ 7619', Start adding Safe Carb to bring up MW

Report Start Date 7/17/2013	Report End Date 7/18/2013	Operations Summary Drlg 6-1/8" lateral section F/7371' - T/7865'. Circulate, SI well, pressure build up to 600 psi. RU flare stack, circulate. POOH to window, spot 15.6# MW top kill. TOO, PU new motor, set bend 1.76" bend. PU directional BHA and TIH 1272', circ and test mud motor.
--------------------------------	------------------------------	--



Daily Activity Report

Well Name: Ratherford U 2933

API Number 43037309320000	Section 29	Township 41S	Range 24E	Field Name Ratherford	County San Juan	State/Province Utah
Ground Elevation (ft) 4,911.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 16.90	KB-Casing Flange Distance (ft)	Well Spud Date/Time 12/26/1983 00:00	Rig Release Date/Time 1/28/1984 00:00	

Dur (hrs)	Comment
6.00	Drlg 6-1/8" Lateral section - Rotate F/7706' - T/7783', Slide F/7783' - T/7790', Rotate F/7790' - T/7804', Slide F/7804' - T/7814', Vis 38, MW 9, PH 9.1, WL 12, P/U WT 88, SOW 76, ROT WT 80.
3.00	Drlg 6-1/8" Lateral section - Rotate F/7814' - T/7834', Slide F/7834' - T/7840', Rotate F/7840' - T/7865', Vis 38, MW 9, PH 9.1, WL 12, P/U WT 88, SOW 76, ROT WT 80.
2.00	Circulate, pump high vis sweep and work pipe.
3.00	Shut in well, pressure build up to 600 psi, R/U flare stack.
2.00	Circulate gas out of well bore through choke manifold.
1.00	Hang back swivel and TOO H to window.
1.50	Spot 62 bbls 15.6# mud in annulas and 17 bbls in drill pipe.
3.00	TOOH from 5175', lay out motor and bit.
2.50	P/U new motor set bend at 1.76", P/U directional BHA and TIH to 1272' and test motor.

Report Start Date 7/18/2013	Report End Date 7/19/2013	Operations Summary M/U 6-1/8" BHA W/1.76 Directional motor, TIH W/ 6-1/8" BHA, P/U Power Swivel, Circulate hole & Get 15.6lb mud out of system, Drlg 6-1/8" Lateral hole section F/7865' T/8073', Note: Flow test 7.5 bbls hour, have a 5' flare.
--------------------------------	------------------------------	---

Dur (hrs)	Comment
2.00	M/U 6-1/8" BHA with 1.76 deg bend motor. With 6-1/8" Reed PDC Bit.
0.50	TIH with 6-1/8" PDC bit and 1.76 Deg motor.
1.50	Break Circulation, Circulate well, Unload 15.6 lbs mud and haul to mud plant in water trucks. Got system back to the 9.0 lb produced water.
1.50	TIH with 6-1/8" PDC bit and 1.76 Deg motor.
2.00	P/U and R/U Power Swivel.
6.00	Drill 6-1/8" Lateral section - Rotate F/7865' T/7930' VIS 38, MW 9lb, PH 9.5, P/U WT 88, SOW 68, ROT WT 82, Note: @ 22:30 We did flow test flow was At 10 gal a min, = 7.5 BBLs and hour, Also flare was out, @ 9:00 we got another Injector well turned off.
6.00	Drill 6-1/8" Lateral section - Rotate F/7930' T/7971' Slide F/7971' T/7979', Rotate F/7979' 8001', Slide F/8001' T/8007', VIS 38, MW 9lb, PH 9.5, P/U WT 88, SOW 68, ROT WT 82, Note: We still have no flare.
4.50	Drill 6-1/8" Lateral section - Rotate F/8007 T/8032', Slide F/8032 T/8039', Rotate F/8039 T/8063', Slide F/8063' T/8073', VIS 38, MW 9lb, PH 9.5, P/U WT 88, SOW 68, ROT WT 82, Note: We still have a 5" Flare, and we having problems building angle down. We will slide a little more aggressive.

Report Start Date 7/19/2013	Report End Date 7/20/2013	Operations Summary DRLG Lateral hole section F/8073' T/8084' sliding and rotating, Circulate, TOO H to replace MWD battery, Spot 80 bbl 11.1lb kill pill, TIH, Circulate 11.1 lbs kill pill out of mud system, TIH while circulating seeing 7.5 bbl flow and gas,
--------------------------------	------------------------------	--

Dur (hrs)	Comment
2.00	Drill 6-1/8" Lateral section - Slide F/8073' T/8075', Rotate F/8075' T/8084', VIS 38, MW 9lb, PH 9.5, P/U WT 88, SOW 68, ROT WT 82, Note: We still have a 5" Flare, and we having problems building angle down. We will slide a little more aggressive.
1.00	Circulate condition hole to TOO H to change MWD Battery,
3.00	TOOH To Replace Battery on MWD tool, TOO H to one joint into 7" casing @ 5168',
1.00	Pressure test hole for one hour to get the MW needed to set kill pill in 7" casing, NOTE: one hour the well stabilized at 400 psi shut in psi, and 7.5 bbls hour flow.
3.00	Build 80 bbls of 11.1 lb mud to pump kill pill into 7" casing, Pump 80 bbl 11.1 lb kill pill at 100 strokes per min, for 17 min, btm set @ 5168' top at 2650',
3.00	TOOH and replaced Battery MWD tool.
1.00	Circulate 80 bbl 11.1 lb kill pill out of system.
2.00	Service rig and put new rubber in BOP.
8.00	TIH circulating, Note seeing 7.5 bbl flow and gas.

Report Start Date 7/20/2013	Report End Date 7/21/2013	Operations Summary TIH, Circulate, Rig Service, Unload hole, Install dual external transducer for MWD tool, Drill 6-1/8" lateral hole section F/8084' T/8275', (Sliding and Rotating) NOTE: We did have to treat mud with ALMN Stearate to shear gas out.
--------------------------------	------------------------------	---



Daily Activity Report

Well Name: Ratherford U 2933

API Number 43037309320000	Section 29	Township 41S	Range 24E	Field Name Ratherford	County San Juan	State/Province Utah
Ground Elevation (ft) 4,911.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 16.90	KB-Casing Flange Distance (ft)	Well Spud Date/Time 12/26/1983 00:00	Rig Release Date/Time 1/28/1984 00:00	

Dur (hrs)	Comment
1.00	TIH T/8084', No Fill, kept hole full of mud, and circulated every 10 stands, NOTE: Mud is estranged with gas, 1.00 P/U power swivel, Circulate, 2.50 Circulate on bottom, Unload hole, Mud is still very light and bubble with gas, 5.50 MWD Tool is not able to get any readings, the mud is to light with the gas properties, We circulated through choke half way open to shear gas out of mud. Received ALMN Stearate on location treated mud to help get gas out. (These to processes worked well). NOTE: We also installed a Dual External Transducer for MWD TOOL this also corrected issue, 6.00 Drilling 6-1/8" Lateral hole section, Rotate 10' F/8084' T/8094, Re- Log gamma, Slide F/8094' T/8104', Rotate F/8104' T/8151', Slide F/8150' T/8160', Things are looking good! MUD Properties: VIS-37, MW-9.0, PH-9.1, WL20, Drill String TEST: WT-88, SOW-68, ROT WT-82 Note: We are getting a 7.5 bbl hour flow, 7' flare. 6.00 Drilling 6-1/8" Lateral hole section, Rotate 10' F/8160' T/8185', Slide F/8185' T/8195', Rotate F/8195' T/8211', Slide F/8211' T/8219', Rotate F/8219' T/8247', Things are looking good! MUD Properties: VIS-37, MW-9.0, PH-9.1, WL20, Drill String TEST: WT-88, SOW-68, ROT WT-82 Note: We are getting a 7.5 bbl hour flow, 7' flare. 2.00 Drilling 6-1/8" Lateral hole section, Slide F/8247' T/8263', Rotate F/8263' T/8275', Things are looking good! MUD Properties: VIS-37, MW-9.0, PH-9.1, WL20, Drill String TEST: WT-88, SOW-68, ROT WT-82 Note: We are getting a 7.5 bbl hour flow, 7' flare.

Report Start Date 7/21/2013	Report End Date 7/22/2013	Operations Summary Drilling 6-1/8" lateral section (Sliding & Rotating) F/8275' T/8538. NOTE: We are seeing a 7.5 bbl hour flow, 7 ft flare.
--------------------------------	------------------------------	--

Dur (hrs)	Comment
6.00	Drilling 6-1/8" Lateral hole section, Sliding F/8075' T/8283', Rotate F/8283' T/8308', Slide F/8308' T/8315', Rotate F/8315' T/8339', Slide F/8339' T/8347', MUD Properties: VIS 38, MW 9.0, PH 9.0, WL 28. DLG String Test: WT-90, SOW-70, ROT WT-83. NOTE: We are seeing a 7.5 BBL HR Flow, 7ft flare. 6.00 Drilling 6-1/8" Lateral hole section, Rotate F/8347' T/8397', Slide F/8397' T/8406', Rotate F/8406' T/8417', MUD Properties: VIS 38, MW 9.0, PH 9.0, WL 28. DLG String Test: WT-90, SOW-70, ROT WT-83. NOTE: We are seeing a 7.5 BBL HR Flow, 7ft flare. 6.00 Drilling 6-1/8" Lateral hole section, Rotate F/8417' T/8462, Slide F/8462' T/8470', Rotate F/8470' T/8492', MUD Properties: VIS 38, MW 9.0, PH 9.0, WL 28. DLG String Test: WT-90, SOW-70, ROT WT-83. NOTE: We are seeing a 7.5 BBL HR Flow, 7ft flare.



Daily Activity Report

Well Name: Ratherford U 2933

API Number 43037309320000	Section 29	Township 41S	Range 24E	Field Name Ratherford	County San Juan	State/Province Utah
Ground Elevation (ft) 4,911.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 16.90	KB-Casing Flange Distance (ft)	Well Spud Date/Time 12/26/1983 00:00	Rig Release Date/Time 1/28/1984 00:00	

Dur (hrs)	Comment
6.00	Drilling 6-1/8" Lateral hole section, Slide F/8492' T/8497', Rotate F/8497' T/8512', Slide F/8512', T/8522', Rotate F/8522' T/8538', MUD Properties: VIS 38, MW 9.0, PH 9.0, WL 28. DLG String Test: WT-90, SOW-70, ROT WT-83. NOTE: We are seeing a 7.5 BBL HR Flow, 7ft flare.

Report Start Date 7/22/2013	Report End Date 7/23/2013	Operations Summary Drilling 6-1/8" lateral section (Sliding & Rotate) F/8538' T/8789', NOTE: We are seeing a 8.5 bbl hour flow, 5ft flare. 2- BOP Drills 60 sec to Muster.
--------------------------------	------------------------------	---

Dur (hrs)	Comment
6.00	Drilling 6-1/8" Lateral hole section, Rotate F/8538' T/8580', Slide F/8580' T/8586', Rotate F/8586', T/8601', MUD Properties: VIS 36, MW 8.9, PH 9.5, WL 27. DLG String Test: WT-115, SOW-40, ROT WT-78. TQ 4200, 4500. NOTE: We are seeing a 8.5 BBL HR Flow, 5ft flare.
6.00	Drilling 6-1/8" Lateral hole section, Slide F/8601' T/8613', Rotate F/8613' T/8652', MUD Properties: VIS 36, MW 8.9, PH 9.5, WL 27. DLG String Test: WT-110, SOW-40, ROT WT-78. TQ 3800, 4200 NOTE: We are seeing a 8.5 BBL HR Flow, 5ft flare.
6.00	Drilling 6-1/8" Lateral hole section, Rotate F/8652' T/8727', MUD Properties: VIS 36, MW 8.9, PH 9.5, WL 27. DLG String Test: WT-98, SOW-50, ROT WT-78. TQ 4000, 4500. NOTE: We are seeing a 8.5 BBL HR Flow, 5ft flare.

Report Start Date 7/23/2013	Report End Date 7/24/2013	Operations Summary Drilling 6-1/8" Lateral hole section F/8789' - T/8851', Circulate, Back ream out of hole F/8851' - T/7895', Circulate, Wash and ream to bottom F/7895' - T/8851', Drilling 6-1/8" Lateral hole section F/8851' - T/9010'
--------------------------------	------------------------------	--

Dur (hrs)	Comment
7.00	Drilling 6-1/8" Lateral hole section, Rotate F/8789' T/8794', Slide F/8794' T/ 8799', Rotate F/ 8799'. T/ 8851'. MUD Properties: VIS 38, MW 9, PH 9.2, WL 20+. DLG String Test: WT-110, SOW-50, ROT WT-78. TQ 4000, 4500. NOTE: We are seeing a 7.4 BBL HR Flow, 3ft flare.



Daily Activity Report

Well Name: Ratherford U 2933

API Number 43037309320000	Section 29	Township 41S	Range 24E	Field Name Ratherford	County San Juan	State/Province Utah
Ground Elevation (ft) 4,911.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 16.90	KB-Casing Flange Distance (ft)	Well Spud Date/Time 12/26/1983 00:00	Rig Release Date/Time 1/28/1984 00:00	

Dur (hrs)	Comment
1.00	Condition and Circulate mud for 15 stand wiper trip. Note: Having trouble trying to slide 2.00 Back ream out of hole with swivel F/8851' - T/7895' (30 joints). For drag issues while trying to slide. 0.50 Circulate bottoms up to remove gas bubble from wellbore. 3.50 Wash and ream back to bottom F/7895' - T/8851', Ream each joint 2 times. 6.00 Drilling 6-1/8" Lateral hole section, Rotate F/8851' T/8861, Slide F/8861' T/ 8871', Rotate F/ 8871'. T/ 8898'. Slide F/8898' T/8906', Rotate F/8906' T/8961' MUD Properties: VIS 36, MW 8.9, PH 9.5, WL 20+. DLG String Test: WT-110, SOW-45, ROT WT-82. NOTE: We are seeing a 7.4 BBL HR Flow, 3ft flare. 4.00 Drilling 6-1/8" Lateral hole section, Slide F/8961' T/8965', Rotate F/8965' T/8992', Slide F/8992' T/8998', Rotate F/8998' T/9010' MUD Properties: VIS 36, MW 8.9, PH 9.5, WL 20+. DLG String Test: PU WT-110, SOW-50, ROT WT-80. NOTE: We are seeing a 7.4 BBL HR Flow, 3ft flare.

Report Start Date 7/24/2013	Report End Date 7/25/2013	Operations Summary Drilling 6-1/8" Lateral hole section, F/9010' T/9134' (TD) called by geologist, Circulate, Flow test = 8.4bbls/hr, Shut in well pressured built up to 500 psi, Bleed down well through choke manifold at 74 stks/min (SPR)
--------------------------------	------------------------------	--

Dur (hrs)	Comment
6.00	Drilling 6-1/8" Lateral hole section, Rotate F/9010' T/9036', Slide F/9036' T/9042', Rotate F/9042' T/9068' MUD Properties: VIS 38, MW 8.8, PH 9.5, WL 20+. DLG String Test: PU WT-110, SOW-50, ROT WT-80. NOTE: We are seeing a 7.4 BBL HR Flow, 3ft flare. 6.00 Drilling 6-1/8" Lateral hole section, Slide F/9068' T/9073', Rotate F/9073' T/9083', Slide F/9083' T/9088', Rotate F/9088' T/9107' MUD Properties: VIS 37, MW 8.8, PH 9.5, WL 20+. DLG String Test: PU WT-110, SOW-68, ROT WT-80. 4.50 Drilling 6-1/8" Lateral hole section, Rotate F/9107' T/9115', Slide F/9115' T/9123', Rotate F/9123' T/9134' MUD Properties: VIS 37, MW 8.8, PH 9.5, WL 20+. DLG String Test: PU WT-110, SOW-68, ROT WT-80. Note: TD called by Geologist Jason Burris 1.00 Circulate and condition mud 0.50 Flow check, Well flowing 8.4bbls/hr 4.50 Shut in well for pressure build up. Pressure build to 500 psi 1.50 Circulate bottoms up through choke manifold @ SPR 74 strokes

Report Start Date 7/25/2013	Report End Date 7/26/2013	Operations Summary Continue circulate bottoms up through choke manifold, Circulate and condition hole,work pipe, Shut in well, Transfer mud from mud pit to frac tanks on location, Fill mud pit with 10# brine. Displace hole with 10.1# brine, Well flowing @ 4bbls/hr, POOH to window, Spot top kill plug 80 bbls @ 13.7#, TOOH and lay down directional BHA, P/U and M/U 7" TS - RBP and 19' - 2 3/8" perf sub with Micro soft memory gauges. TIH w/72 stands drill pipe
--------------------------------	------------------------------	---

Dur (hrs)	Comment
0.50	Continue circulate bottoms up through choke manifold @ SPR 74 strokes 2.50 Circulate and condition hole,work pipe. 5.00 Shut in well, Transfer mud from mud pit to frac tanks on location, Fill mud pit with 10# brine. 2.00 Displace mud with 293 bbls10# brine, circulate through choke manifold. Flow check, well flowing @ 4bbls/hr 4.50 Lay down 10 jts with swivel, Hang back swivel, POOH 15 stands to derrick, lay down 80 jts drill pipe 8 jts HWDP, Chain out and SLM. 1.50 P/U swivel, Spot 90 bbls @ 13.5 # MW, top kill plug F/5199' - T/2847' 5.00 Hang back swivel, L/D HWDP stand back 67 stands.Lay out directional tools.



Daily Activity Report

Well Name: **Ratherford U 2933**

API Number 43037309320000	Section 29	Township 41S	Range 24E	Field Name Ratherford	County San Juan	State/Province Utah
Ground Elevation (ft) 4,911.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 16.90	KB-Casing Flange Distance (ft)	Well Spud Date/Time 12/26/1983 00:00	Rig Release Date/Time 1/28/1984 00:00	

Dur (hrs)		Comment
1.00		P/U and M/U 7" TS - RBP and 19' - 2 3/8" perf sub with Micro soft memory gauges.
2.00		TIH w/ 72 stands drill pipe, and RBP
Report Start Date 7/26/2013	Report End Date 7/27/2013	Operations Summary Finish TIH w/ RBP and pressure bomb, Set packer at 5090', pressure test 1000 psi, TOO 10 stds. Lay down 144 jts DP. TIH with RBP #2 set @ 623', load hole w/10# brine. LD 20 jts DP, RD swivel, ND BOPE. Clean mud tanks, RD prep to move to AU H-236A, Rig released @ 06:00 on 7-27-13.
Dur (hrs)		Comment
0.50		Finish TIH w/ RBP and pressure bomb, Set packer at 5090'
4.00		POOH 10 stds to derrick and lay down 144 jts DP
0.50		P/U running tool and 7" TS- Packer
0.50		RIH w/7" TS-Packer set @ 623', Load hole with 10.1# brine
0.50		Lay down 20 joints drill pipe.
2.00		Lay down and load out power swivel.
4.00		N/D BOPE, Clean mud tanks
12.00		R/D prep to move rig F/ RU 2933H - T/ H-236A
Report Start Date 7/27/2013	Report End Date 7/27/2013	Operations Summary Cleaned up stained dirt
Report Start Date 7/31/2013	Report End Date 7/31/2013	Operations Summary Rig up, n/u BOP, P/u tbq & retri RBP
Dur (hrs)		Comment
1.00		Capital, completion Raod rig to loc.
0.50		Safety mtg, fill out JSA.
2.50		Spot rig, & rig equip.
1.00		Level rig up pad, rig up.
1.00		N/u hard lines to well, pump, rig pit & frac tank.Chk pres, 0 psi on csg. Spot 2-7/8" wrk/strg trailer.
1.00		N/dn B-1 flange & N/u BOP & rig floor.
0.50		P/u 1 jnt w/ tension Pkr & set 15' below BOP. Pres test BOP, pres test pipe ram @ 200 psi low, good & 1000 psi high, good. pres test Hydri @ 200 psi low, good & 1000 psi high, good, bled pres off. Unset tension Pkr & lay it dn.
3.00		Tally, P/u Retri head & P/u 19 jnts latch on to RBP @ 620' unset RBP, TOO 10 & lay dn RBP, TBIH w/19 jnts, tally, p/u 141 jnts @ 4,583.43.
0.50		Shut well in, P/u tools.
1.00		Traveled.
Report Start Date 8/1/2013	Report End Date 8/1/2013	Operations Summary PU tbq, unset RBP, pump kill fluid.
Dur (hrs)		Comment
1.00		Capital, completion. Crew traveled.
0.50		Safety mtg, fill out JSA.
0.50		Chk pres, 0 psi on tbq & csg. open to rig pit.
2.00		Tally & P/u 157 jnts & latch on to RBP @ 5,095', unset RBP, let it set for a while, pres came up to 400 psi, open to frac tank, open tbq & csg to frac tank, got a steady stream flowing. shut csg in & pump 10 bbls of 10# brine dn tbq, pres up to 700 psi, shut pump dn, bled pres off, back dn to steady stream @ 0 psi, shut well in for 10 mins, pressures up to 200 psi.
3.00		Flow back tbq & csg to frac tank @ 0 psi, flowing @ steady stream. Called Ralph to get 100 bbls of 15.2 mud.
4.50		Spot 2 MWS truck,. pump 25 bbls @ 750 psi dn csg, return 12.3 mud pump 40 bbls @ 900 psi return 14.7 mud pump 25 bbls @ 950 psi return 10.5 Csg went on a vac. tbq stil flowing @ 0 psi, steady stream, pump 15 bbls dn tbq, pres up to 400 psi. shut tbq for 30 mins, flow back tbq drop dn to zero, still got steady stream. & csg still on a vac. (Pump 80 bbls dn csg & 15 bbls dn tbq).
0.50		Pull 1 std, still flowing.
0.50		Shut well in, P/u tools.
1.00		Traveled.
Report Start Date 8/2/2013	Report End Date 8/2/2013	Operations Summary Kill well, TOO 10, TBIH w/ trt Pkr, N/u CTU
Dur (hrs)		Comment
1.00		Capital, completion. Crew traveled.
0.50		Safety mtg, fill out JSA.
2.50		Chk pres, 400 psi on tbq & 50 psi on csg. Flow tbq back to frac tank steady stream @ 0 psi, fluid & gas.



Daily Activity Report

Well Name: Ratherford U 2933

API Number 43037309320000	Section 29	Township 41S	Range 24E	Field Name Ratherford	County San Juan	State/Province Utah
Ground Elevation (ft) 4,911.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 16.90	KB-Casing Flange Distance (ft)	Well Spud Date/Time 12/26/1983 00:00	Rig Release Date/Time 1/28/1984 00:00	

Dur (hrs)	Comment
1.00	Pump 5 bbls dn tbg, shut tbg in, Excavation done by Julius C., Dig earth pit, lined & fenced by MWS. Check prfes on tbg, tbg's on a vac.
1.50	TOOH w/ 157 wrk/ strg, lay dn 19' of subs & 17' of BHP data instrument & sent to Jim S. Handle by Tefteller, lay dn RBP.
1.50	P/u 7" treating Pkr (LHM HD) 1-2-7/8 x 2.31 XA sliding sleeve, 1- 4' x 2-7/8 sub, 1- 2-7/8 x 2.25 "R" w/ 2.19 nogo nipple, TIH & set 7" Treating Pkr @ 5,105' w/ KB, above window @ 5,161.5. Open sliding sleeve.
2.00	Circ 15.2 out w/ Fw. (75 bbls of 15.2 mud returned).
0.50	Pres test pkr @ 500 psi for 30 mins, good
1.50	Spot CTU, safety mtg, R/u CTU to tbg & n/u hose to unit.
0.50	Shut well in, P/u tools.
1.00	Traveled.

Report Start Date 8/3/2013	Report End Date 8/3/2013	Operations Summary RIH w/ CTU, to 7926.
-------------------------------	-----------------------------	--

Dur (hrs)	Comment
1.00	Capital, completion. Crew traveled.
0.50	Safety mtg, fill out JSA.
0.50	Chk pres, 1000 psi on tbg & 500 psi on csg. Choke back csg @ 48 psi back to frac tank
10.50	Basic CTU, RIH w/ Vortac- wash nozzle (rotate nozzle), tag @ 5169' @ the window, not going in lateral. POOH, Bend coil tbg to northwest & RBIH, Tight spot from 6440' to 7727' coil tbg pres @ 3000 psi & when hit tight spot, pres up to 9000 psi. got dn to 7900' to 7926', hit tight spot, work it for 2.50 hrs. no luck, update Donnie T. with the well, decide to run a motor w/ a mill. POOH w/ coil.
0.50	Shut well in, P/u tools.
1.00	Traveled.

Report Start Date 8/4/2013	Report End Date 8/4/2013	Operations Summary No Standby charged on CTU.
-------------------------------	-----------------------------	--

Dur (hrs)	Comment
1.00	Capital, completion. Crew traveled.
0.50	Safety mtg, fill out JSA.
12.50	P/u on CTU, P/u 1.25 coil connector, OD 1.69, 1 motor head assembly, OD 1.69, 1- mud motor, OD 1.69, 1- 3 blade junk mill, OD 1.875, Chk pres, 1000 psi on tbg & 500 psi on csg. Choke back csg @ 48 psi back to frac tank. RIH w/ coil. RIH w/ 3 blade junk mill, Tight spot @ 7582', 12:30- 1:30 pm, mill from 7582' to 8060' = 478' 1:30 - 3:30 pm, mill from 8060' to 8200' = 140 / 70' per hr 3:30 - 4:30 pm, mill from 8200 to 8212' = 12' per hr 4:30 - 5:30, mill from 8212' to 8232' = 20' 5:30 - 6:30, mill from 8232' to 8247' = 15' Getting returns mud & sand. POOH to surface.
0.50	Shut well in, P/u tools.
1.00	Traveled.

Report Start Date 8/5/2013	Report End Date 8/5/2013	Operations Summary RIH w/ CTU, mill out to 8247'.
-------------------------------	-----------------------------	--

Dur (hrs)	Comment
1.00	Capital, completion. Crew traveled.
0.50	Safety mtg, fill out JSA.

Report Start Date 8/6/2013	Report End Date 8/6/2013	Operations Summary RIH w/ mill, clean out to 8438', POOH.
-------------------------------	-----------------------------	--

Dur (hrs)	Comment
1.00	Capital, completion. Crew traveled.
0.50	Safety mtg, fill out JSA.



Daily Activity Report

Well Name: Ratherford U 2933

API Number 43037309320000	Section 29	Township 41S	Range 24E	Field Name Ratherford	County San Juan	State/Province Utah
Ground Elevation (ft) 4,911.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 16.90	KB-Casing Flange Distance (ft)	Well Spud Date/Time 12/26/1983 00:00	Rig Release Date/Time 1/28/1984 00:00	

Dur (hrs)	Comment
11.00	<p>Chk pres, 700 psi on tbq & 400 psi on csg. RIH w/ Vortac, wash nizzle (rotate) Tight spot @ 7962 10:00 -11:00 am, mill from 7962' to 8270' = 308' 11:00- 12:00 pm, mill from 8270' to 8291' = 21' 12:00 - 1:00 pm, mill from 8291' to 8318' = 27' 1:00 - 2:00 pm, mill from 8318 to 8376' = 58' 2:00 - 3:00 pm mill from 8376' to 8392' = 16' 3:00 - 4:00 pm, mill from 8392' to 8438, = 46' @ 8438' tight spot. not moving.no luck Getting returns oil & sand. POOH, pull up CTU & lay dn mill & motor, P/u Vortac wash nozzle & M/u to coil,</p> <p>0.50 Shut well in, P/u tools. 1.00 Traveled.</p>

Report Start Date	Report End Date	Operations Summary
8/7/2013	8/7/2013	TIH w/ CTU, wash lateral w/ 149 bbls caustic, 10.5 ph.
Dur (hrs)		Comment
1.00		Capital, completion. Crew traveled.
0.50		Safety mtg, fill out JSA.
7.00		Chk pres, 450 psi on tbg & 400 psi on csg. RIH w/ Vortac, wash nizzle (rotate) Tag up @ 5375', pull up to 50' & TBIH & tag @ 5372' still no luck, Called DonnieT.said to POOH & bend coil NW-319, start POOH, pull up on CTU & bend coil 319 to NW,TBIH, dn to 8451', Called Ralph to mix Caustic, safety mtg, on MSDS on caustic & handling, Mix caustic, chk PH, got 8-9, Ralph went back to Mud plant to pick up 2 bags of caustic.
1.00		Wait on caustic for an hr.
5.50		Mix caustic and bring PH up to 10.5, start washing (149 bbls of caustic) the wall on the laderal back to the window @ 5175' and back dn to 8451' & flash laderal w/ F/w back to window & POOH.
0.50		Shut well in, P/u tools.
1.00		Traveled.

Report Start Date 8/8/2013	Report End Date 8/8/2013	Operations Summary RIH w/ coil, pump 4650 gal, 20% HCL acid @ .6 bpm w/ 3410 psi from 9080' back to window, flush w/ 150 bbls of FW. POOH w/ coil, RD Baker Hughes & CTU.
Dur (hrs)		Comment
1.00		Capital, completion. Crew traveled.
0.50		Safety mtg, fill out JSA.
3.50		Chk pres, 560 psi on tbq & 400 psi on csg. RIH w/ Vortac, wash nozzle (rotate) tight spot @ 7885', work it dn to 8090', (the caustic has clean up oil from laderal & coil won't slide).notified Donnie T. and agreed to pump acid.
6.50		Spot Baker Hughes, N/u hradlines. Safety mtg w/ all contractors on loc..Pres test lines to 5500 psi. Pump 5 bbls of F/w ahead @ .6 bpm w/ 1240 psi, shut in return. Begin pumping 4650 gal, 20% HCL acid @ .6 bpm w/ 3410 psi from 9080' working w/ wash the lateral back to the window @ 53.7 fpm, pump,150 bbls flush @ .6 bpm w/ 3145 psi Shut dn.w/ 973 psi, 15 mins shut in. 5-min 905 psi, 10-min 860 psi, 15-min 837 psi.
1.50		R/dn CTU. & Baker Hughes. P/u tools.
1.00		Traveled.

Report Start Date 8/9/2013	Report End Date 8/9/2013	Operations Summary Chk pres, 600 psi on tbq & 400 psi on csg. Bled csg off, Flow back tbq to rig pit, got choke set @ .23, (lots of gas).flow back 55 bbls of oil within 4.5 hrs.
Dur (hrs)		Comment
1.00		Capital, completion. Crew traveled.
0.50		Safety mtg, fill out JSA.
8.50		Chk pres, 600 psi on tbq & 400 psi on csg. Bled csg off, Flow back tbq to rig pit, got choke set @ .23, (lots of gas oil).flow back 55 bbls of oil within 4.5 hrs. (well's got lots of gas, had to choke back if flowing back to rig pit, but flowing to frac tank we can open it more. But decide plumb tbq to flow line (satalite-20.). Called Billison R. to set up a crew to plumb line in. plumb hardline from tbq to ground level.(chk pres @ 800 psi) H.T. haul 10 2-7/8 B/B tbq to loc for flow line & run line from well head to end of loc. J.R Const. plumb line in. MWS truck empty out 2- 400 tank, haul fluid to mud plant.
1.00		Traveled.

Report Start Date 8/12/2013	Report End Date 8/12/2013	Operations Summary TOOH w/ treating pkr, TBIH & retrieve whipstock @ 5,165'. TBIH w/ retrieving head.
--------------------------------	------------------------------	--



Daily Activity Report

Well Name: Ratherford U 2933

API Number 43037309320000	Section 29	Township 41S	Range 24E	Field Name Ratherford	County San Juan	State/Province Utah
Ground Elevation (ft) 4,911.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 16.90	KB-Casing Flange Distance (ft)	Well Spud Date/Time 12/26/1983 00:00	Rig Release Date/Time 1/28/1984 00:00	

Dur (hrs)	Comment
1.00	Capital, completion. (Key Energy had their safety mtg. in Cortez.) Shut tbg in while waiting on crew. Crew traveled.
0.50	Safety mtg, fill out JSA.
0.50	Chk pres, 120 psi on tbg & 0 psi on csg.
1.50	Flow back to frac tank (gas & oil), Pump 25 bbls of 10 # brine dn tbg & 20 bbls dn csg, well's dead.
2.00	Unset treating Pkr, TOO H & lay dn treating Pkr.(pump 10 bbls of 10 # brine every 20 std pull).
1.50	P/u Baker Tools, 1- hook, 1- jar, 1- x-over, float, 1- x-over. TIH w/ 157 jnts, P/u 2 jnts tag & hook on to whip stock(Retri slot @ 5,165').
1.50	Put drill line on tie back, pull up to 65 K & unset whipstock, lay 1 jnt dn & pull next jnt 10', hit tight spot @ 5,160' (csg collar), wrkin it and got it through the tight spot. Put drill line back on double.
1.50	TOOH & lay dn whipstock & tools. (well came around)
1.00	P/u retri head & pump 30 bbls of 10 # dn csg. TIH w/ 40 stds.
0.50	Shut well in, P/u tool.
1.00	Traveled.

Report Start Date 8/13/2013	Report End Date 8/13/2013	Operations Summary TIH & retrieve RBP, LD wrk/strg, set CIBP @ 5,269' w/ Blue Jet. PU 140 jnts of 2-7/8" FBNAU tbg.
--------------------------------	------------------------------	--

Dur (hrs)	Comment
1.00	Capital, completion. Crew traveled.
0.50	Safety mtg, fill out JSA.
0.50	Chk pres, 350 psi on tbg & 200 psi on csg. Bled tbg & csg to frac tank, pump 15 bbls of 10 # brine dn tbg & pump 20 bbls dn csg.
2.00	TIH & latch on to RBP, unset RBP & well went on vac.notified Donnie T. start laying dn tbg, tbg,s starting to flow, pump 10 # dn tbg & pres up, went ahead and reset RBP and latch off RBP, tbg went on a vac, latch back on to RBP & unset RBP.
0.50	Crew took lunch.
3.00	Lay dn 159 of wrk/strg, spot trailer (2-7/8 FBNAU Tbg).
1.50	Wait 1.5 hr on Blue Jet to set CIBP.
2.00	Spot Blue Jet, safety mtg, R/u wire line, TIH w/ CIBP & set @ 5,269'. POOH, R/dn wire line.
3.00	Count tbg, take thread protectors off, tally tbg, P/u 140 jnts @ 4,485'.
0.50	Shut well in, P/u tools.
1.00	Traveled.

Report Start Date 8/14/2013	Report End Date 8/14/2013	Operations Summary PU 18 jnts, TOO H w/ 60 jnts, flow well back.
--------------------------------	------------------------------	---

Dur (hrs)	Comment
1.00	Capital, completion. Crew traveled.
0.50	Safety mtg, fill out JSA.
1.00	Chk pres, 260 psi on tbg & 300 psi on csg. Bled tbg & csg to frac tank (gas & oil), pump 15 bbls of 20 # brine dn tbg & pump 30 bbls dn csg. well's dead.
0.50	Take thread protectors off, tally & P/u 18 jnts= 158 jnts of 2-7/8' FBNAU
2.50	TOOH w/ 60 jnts, tbg slip not working properly, called Wes R. and sent hand dn to Key yard, see there's one in yard.continue tripping pipe, pull 1 std, well came around, flowing @ 100 psi. to rig pit.
0.50	Flow well back, pump 25 bbls dn tbg & 60 bbls dn csg, shut well in. (300 psi on tbg & 500 psi on csg.). Notified Donnie T. talk about kill fluid, decide to change to calcium. Called Ralph to get calcium ready by morning.
3.00	N/u tbg to flowline.Called pumper to open line @ satelite.
0.50	Shut well in, P/u tools.
1.00	Traveled.

Report Start Date 8/15/2013	Report End Date 8/15/2013	Operations Summary TOOH w/ 98 jnts, TBIH w/ sub pump, landed. RD, open sliding sleeve.
--------------------------------	------------------------------	---

Dur (hrs)	Comment
1.00	Capital, completion. Crew traveled.
0.50	Safety mtg, fill out JSA.
1.00	Chk pres, 250 psi on tbg & on csg. Bled tbg & csg to frac tank (gas & oil).
0.50	Pump 5 bbls of calcium carbinat dn tbg & pump 15 bbls dn csg. well's dead.
1.00	TOOH w/ 98 jnts.
1.50	P/u & service sub pump, M/u 1-4' sub to pump & P/u pump-1 & pump-2, P/u gas separator, seal-1 & seaL-2, P/u motor & centinel w/ 4' sub.= 60.21.
0.50	Crew took lunch.



Daily Activity Report

Well Name: Ratherford U 2933

API Number 43037309320000	Section 29	Township 41S	Range 24E	Field Name Ratherford	County San Juan	State/Province Utah
Ground Elevation (ft) 4,911.00	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 16.90	KB-Casing Flange Distance (ft)	Well Spud Date/Time 12/26/1983 00:00	Rig Release Date/Time 1/28/1984 00:00	

Dur (hrs)	Comment
4.00	Spot in spooler trailer. TIH w/ 2- jnts, check valve @ 5,027.17, 1-jnt, 1 sliding sleeve @ 4,994.27, TIH w/ 155 2-7/8 FBNAU tbgs. R/dn spooler, splice lower connector, add capillary string, 60', land tubing.
1.00	R/dn rig floor & BOP.
0.50	Pull up on tbgs & replaced o-ring on tbgs hanger & reland tbgs hanger, N/u master valve & flow-T.
1.00	Rig dn, R/dn part of hard lines back on pump.
1.00	Spot tefteller, safety mtg. R/u Tefteller, Run in, put 600 psi on tbgs, open sliding sleeve @ 4,984'. R/dn Tefteller.
1.00	Pump 45 bbls P/w dn tbgs to circ calcium out & csg Flowing oil, shut pump dn..100 psi on csg & 120 psi on tbgs.
0.50	Shut well in, P/u tools.
1.00	Traveled.

Report Start Date 8/16/2013	Report End Date 8/16/2013	Operations Summary move off loc. move to MCU P-09
--------------------------------	------------------------------	--

Dur (hrs)	Comment
1.00	Capital, completion. Crew traveled.
0.50	Safety mtg, fill out JSA.
1.50	Chk pres, 80 psi on tbgs & on csg. Open tro rig pit well's dead, rig crew move to P-09. waiting on F/w, got flow back crew from Lansing, spot MWS truck F/w & pump F/w dn csg and out tbgs 60 bbls, start to get calcium back, pump total of 245 bbls of F/w, w/ 100 psi on pump, total return of 236 bbls, starting to clear up after we pump 50 bbls.shut well in.
12.00	5th hand stayed behind to monitor well. Waiting on F/w, got flow back crew from Lansing, spot MWS truck F/w & pump F/w dn csg and out tbgs 60 bbls, start to get calcium back, pump total of 245 bbls of F/w, w/ 1000 psi on pump, total return of 236 bbls, starting to clear up after we pump 50 bbls.shut well in.

Report Start Date 8/17/2013	Report End Date 8/17/2013	Operations Summary Flow back.180 psi on tbgs & 200 psi on csg.
--------------------------------	------------------------------	---

Dur (hrs)	Comment
20.00	Flow well back. Chk pres, 180 pon tbgs & 200 psi on csg, flow tbgs back to Rig pit @ 20 psi in the morning, getting returns w/ 10 % oil & F/w we pump. @ noon, pres came up 40-50 psi, returns w/ 40 % oil & F/w, stil getting sand back. but it's clearing up.

Report Start Date 8/18/2013	Report End Date 8/18/2013	Operations Summary Chk press,100 psi on tbgs & 425 psi on csg, flow back all day. SIP 60 psi on tbgs & 400 psi on csg.
--------------------------------	------------------------------	---

Dur (hrs)	Comment
8.00	Flow well back. Chk pres, 100 psi on tbgs & 425 psi on csg,open to rig pit, flowing wide open @ 20 psi & got 10 % oil & rest is water. 11:00 am 40 psi on tbgs & 380 psi on csg 10 % oil & rest is water, Roustabout & a welder showed uo on loc. Going to do some welding around the well, so had to shut well in, N/dn hard lines from tbgs & rig pit.shut in pres @ 60 psi on tbgs & 400 psi on csg.

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

AMENDED REPORT ☐ FORM 8
(highlight changes)

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> DRY <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: 1420603407
b. TYPE OF WORK: NEW WELL <input type="checkbox"/> HORIZ. LATS. <input type="checkbox"/> DEEP-EN <input checked="" type="checkbox"/> RE-ENTRY <input type="checkbox"/> DIFF RESVR <input type="checkbox"/> OTHER _____		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: Shiprock
2. NAME OF OPERATOR: Resolute Natural Resources		7. UNIT or CA AGREEMENT NAME: 7960041920
3. ADDRESS OF OPERATOR: 1675 Broadway, Ste 195 (City) Denver STATE CO ZIP 80202		8. WELL NAME and NUMBER: Ratherford 29-33
4. LOCATION OF WELL (FOOTAGES): Lateral #1 (NW) AT SURFACE: 1859 FSL, 1836 FEL AT TOP PRODUCING INTERVAL REPORTED BELOW: 2234 FSL, 2169 FEL AT TOTAL DEPTH: 649 FNL, 1035 FWL		9. API NUMBER: 4303730932
10. FIELD AND POOL, OR WILDCAT: Greater Aneth		11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSE 29 41S 24E S
12. COUNTY: San Juan		13. STATE: UTAH

14. DATE SPUDDED: 6/28/2013	15. DATE T.D. REACHED: 7/27/2013	16. DATE COMPLETED: 8/18/2013	ABANDONED <input type="checkbox"/> READY TO PRODUCE <input checked="" type="checkbox"/>	17. ELEVATIONS (OF, RKB, RT, GL): 4915 GL
18. TOTAL DEPTH: MD 9,134 TVD 5,678	19. PLUG BACK T.D.: MD TVD	20. IF MULTIPLE COMPLETIONS, HOW MANY? *		21. DEPTH BRIDGE PLUG SET: MD TVD
22. TYPE ELECTRIC AND OTHER MECHANICAL LOGS RUN (Submit copy of each): MD and TVD logs			23. WAS WELL CORED? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit analysis) WAS DST RUN? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit report) DIRECTIONAL SURVEY? NO <input checked="" type="checkbox"/> YES <input type="checkbox"/> (Submit copy)	

24. CASING AND LINER RECORD (Report all strings set in well)

HOLE SIZE	SIZE/GRADE	WEIGHT (#/ft.)	TOP (MD)	BOTTOM (MD)	STAGE CEMENTER DEPTH	CEMENT TYPE & NO. OF SACKS	SLURRY VOLUME (BBL)	CEMENT TOP **	AMOUNT PULLED
17 1/2	13 3/8 K-55	48	0	133		B 150		0 CIR	
12 1/4	9 5/8 K-55	36	0	1,600		B 600		0 CIR	
8 3/4	7 K-55	23 & 26	0	5,800		B 700		2922 CAL	

25. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)	SIZE	DEPTH SET (MD)	PACKER SET (MD)
2.875	5,161							

26. PRODUCING INTERVALS

FORMATION NAME	TOP (MD)	BOTTOM (MD)	TOP (TVD)	BOTTOM (TVD)	INTERVAL (Top/Bot - MD)	SIZE	NO. HOLES	PERFORATION STATUS
(A) Lower Ismay	5,606				5,640 5,644			Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(B) Desert Creek IA	5,674				5,674 5,696			Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(C) Desert Creek IB	5,703				5,706 5,727			Open <input checked="" type="checkbox"/> Squeezed <input type="checkbox"/>
(D)								Open <input type="checkbox"/> Squeezed <input type="checkbox"/>

28. ACID, FRACTURE, TREATMENT, CEMENT SQUEEZE, ETC.

DEPTH INTERVAL	AMOUNT AND TYPE OF MATERIAL
5175 to TD open hole	149 bbls caustic, 5 bbls FW head, 4650 gal 20% HCl acid, 150 bbls F/W flush

29. ENCLOSED ATTACHMENTS:

- | | | | |
|---|--|--|--|
| <input type="checkbox"/> ELECTRICAL/MECHANICAL LOGS | <input type="checkbox"/> GEOLOGIC REPORT | <input type="checkbox"/> DST REPORT | <input checked="" type="checkbox"/> DIRECTIONAL SURVEY |
| <input type="checkbox"/> SUNDRY NOTICE FOR PLUGGING AND CEMENT VERIFICATION | <input type="checkbox"/> CORE ANALYSIS | <input checked="" type="checkbox"/> OTHER: WBD, gas analysis | |

30. WELL STATUS:

producing

31. INITIAL PRODUCTION

INTERVAL A (As shown in Item #26)

DATE FIRST PRODUCED: 8/18/2013		TEST DATE: 8/23/2013		HOURS TESTED: 24		TEST PRODUCTION RATES: →		OIL – BBL: 413	GAS – MCF: 688	WATER – BBL: 44	PROD. METHOD: pumping
CHOKE SIZE: 22/64	TBG. PRESS. 160	CSG. PRESS. 100	API GRAVITY 37.80	BTU – GAS 1,639	GAS/OIL RATIO 1,666	24 HR PRODUCTION RATES: →		OIL – BBL: 413	GAS – MCF: 688	WATER – BBL: 44	INTERVAL STATUS: open

INTERVAL B (As shown in Item #26)

DATE FIRST PRODUCED		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS

INTERVAL C (As shown in Item #26)

DATE FIRST PRODUCED:		TEST DATE:		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE:	TBG. PRESS.	CSG PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

INTERVAL D (As shown in Item #26)

DATE FIRST PRODUCED:		TEST DATE		HOURS TESTED:		TEST PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	PROD. METHOD:
CHOKE SIZE	TBG. PRESS.	CSG. PRESS.	API GRAVITY	BTU – GAS	GAS/OIL RATIO	24 HR PRODUCTION RATES: →	OIL – BBL:	GAS – MCF:	WATER – BBL:	INTERVAL STATUS:

32. DISPOSITION OF GAS (Sold, Used for Fuel, Vented, Etc.)

recycled

33. SUMMARY OF POROUS ZONES (Include Aquifers):

Show all important zones of porosity and contents thereof. Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

34. FORMATION (Log) MARKERS:

Formation	Top (MD)	Bottom (MD)	Descriptions, Contents, etc.	Name	Top (Measured Depth)
Upper Ismay	5,513				
Lower Ismay	5,606				
Gothic Shale	5,653				
Desert Creek IA	5,674				
Desert Creek IB	5,703				

35. ADDITIONAL REMARKS (Include plugging procedure)

A single lateral was drilled to the NW, ran new ESP BHA with new 2-7/8" production tbg.

36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records.

NAME (PLEASE PRINT) Sherry GlassTITLE Sr Regulatory TechnicianSIGNATURE Sherry GlassDATE 8/27/2013

This report must be submitted within 30 days of

- completing or plugging a new well
- drilling horizontal laterals from an existing well bore
- recompleting to a different producing formation

- reentering a previously plugged and abandoned well
- significantly deepening an existing well bore below the previous bottom-hole depth
- drilling hydrocarbon exploratory holes, such as core samples and stratigraphic tests

* ITEM 20: Show the number of completions if production is measured separately from two or more formations.

** ITEM 24: Cement Top – Show how reported top(s) of cement were determined (circulated (CIR), calculated (CAL), cement bond log (CBL), temperature survey (TS)).

Send to: Utah Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
Box 145801
Salt Lake City, Utah 84114-5801

Phone: 801-538-5340

Fax: 801-359-3940

RATHERFORD UNIT # 29-33H

PRODUCER

GREATER ANETH FIELD


1859' FSL & 1836' FEL

SEC 29-T41S-R24E

SAN JUAN COUNTY, UTAH

API 43-037-30932

PRISM 0043140

Final Wellbore 8-15-13

J. Styler 8-26-2013

Diablo Analytical BTU Report

GPA 2145-03 Analysis

Sample Information

	Sample Information
Sample Name	R U 29-33
Station Number	
Method Name	NewNGA#3
Injection Date	8/21/2013 1:48:00 PM
Report Date	08/21/2013 01:51:58 PM
BTU Configuration File	GPA 2145-03 EMS.cfg
Data Source	Cerity data system connection
Instrument	G2801AGC - US10317001
Data Saved To:	R U 29-33-20130821-135158.btu

Component Results

Component Name	Ret. Time	Peak Area	Normalized Mole%	Heating Value (Btu / cu. ft.)	Molar Mass Ratio (G)	GPM (Gal. / 1000 cu. ft.)	
Nitrogen	0.483	9698	1.1783	0.0000	0.0114		
Methane	0.501	319207	50.2712	508.9138	0.2785		
Carbon Dioxide	0.651	13989	1.4242	0.0000	0.0216		
Hydrogen Sulfide	0.000	0	0.0000	0.0000	0.0000		
Ethane	0.724	228499	22.5990	400.8598	0.2346	6.0831	
Propane	1.855	166055	14.7415	371.7838	0.2245	4.0878	
i-Butane	0.360	75375	1.8343	59.7894	0.0368	0.6043	
n-Butane	0.383	187017	4.6498	152.0460	0.0933	1.4764	
i-Pentane	0.460	42673	0.9769	39.1752	0.0243	0.3600	
n-Pentane	0.492	54067	1.2001	48.2197	0.0299	0.4377	
Hexanes Plus	1.424	69423	1.1247	57.8216	0.0362	0.4914	
Total:			100.0000	1638.6093	0.9912	13.5407	

Results Summary

Result	Dry	Sat.	
Total Unnormalized Mole%	98.5536		
Pressure Base (psia)	14.730		
Water Mole%	-	1.7404	
Gross Heating Value (Btu / Ideal cu. ft.)	1638.6093	1610.0911	
Gross Heating Value (Btu / Real cu. ft.)	1650.3373	1622.2415	
Real Relative Density	0.99787	0.99179	
Gas Compressibility (Z) Factor	0.99289	0.99251	



Resolute Natural Resources

Ratherford Unit (Nad 27)

Ratherford Unit 29-33

29-33H

Hz

UWI:

WL:

Survey: Final

Standard Survey Report

25 July, 2013





Project: Ratherford Unit (Nad 27)
Site: Ratherford Unit 29-33
Well: 29-33H
Wellbore: Hz
Plan: Final



Azimuths to Grid North
True North: -1.35°
Magnetic North: 9.04°

Magnetic Field
Strength: 50629.8snT
Dip Angle: 63.52°
Date: 2/1/2013
Model: IGRF2010

Well Centre Reference

Geodetic System: US State Plane 1927 (Exact solution)
Ellipsoid: Clarke 1866
Zone: Utah South 4303
Northing: 60477.32
Easting: 804772.91
Latitude: 37° 11' 27.348 N
Longitude: 109° 18' 6.120 W
Grid Convergence: 1.35° West
Ground Elevation: 4911.4
KB Elevation: RKB @ 4927.9ft (D&J 1)

Formation Tops



No formation data is available

PLAN DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	5175.0	0.00	0.00	5175.0	0.0	0.0	0.00	0.00	0.0	
3	5969.1	89.21	319.00	5684.9	379.6	-330.0	11.23	319.00	503.0	Landing Pt. 29-33 P5
4	5969.3	89.22	319.00	5684.9	379.8	-330.2	3.00	-14.16	503.2	
5	6615.2	89.22	319.00	5693.7	867.2	-753.8	0.00	0.00	1149.0	
6	6641.1	90.00	318.99	5693.9	886.8	-770.9	3.00	-0.25	1175.0	VS 1175'
7	7624.2	90.00	318.99	5693.9	1628.6	-1415.9	0.00	0.00	2158.0	VS 2158'
8	7634.9	90.32	318.99	5693.9	1636.7	-1422.9	3.00	-0.97	2168.7	
9	8523.2	90.32	318.99	5688.9	2307.0	-2005.8	0.00	0.00	3057.0	VS 3057'
10	8556.7	91.33	318.99	5688.4	2332.3	-2027.8	3.00	0.00	3090.5	
11	9313.4	91.33	318.99	5670.9	2903.1	-2524.2	0.00	0.00	3847.0	Toe (29-33)

ANNOTATIONS

TVD	MD	Annotation
5161.5	5161.5	Top of Window;5161.5' MD
5169.0	5169.0	Btm of Window;5169' MD
5681.2	9006.0	Extrap to Bit; 9006' MD



Company:	Resolute Natural Resources	Local Co-ordinate Reference:	Well 29-33H
Project:	Ratherford Unit (Nad 27)	TVD Reference:	RKB @ 4927.9ft (D&J 1)
Site:	Ratherford Unit 29-33	MD Reference:	RKB @ 4927.9ft (D&J 1)
Well:	29-33H	North Reference:	Grid
Wellbore:	Hz	Survey Calculation Method:	Minimum Curvature
Design:	Final	Database:	EDM 5000.1 Single User Db

Project	Ratherford Unit (Nad 27)		
Map System:	US State Plane 1927 (Exact solution)	System Datum:	Mean Sea Level
Geo Datum:	NAD 1927 (NADCON CONUS)		
Map Zone:	Utah South 4303		Using geodetic scale factor

Site	Ratherford Unit 29-33		
Site Position:		Northing:	60,477.32 m
From:	Lat/Long	Easting:	804,772.91 m
Position Uncertainty:	0.0 ft	Slot Radius:	13.200 in
		Latitude:	37° 11' 27.348 N
		Longitude:	109° 18' 6.120 W
		Grid Convergence:	1.35 °

Well	29-33H		
Well Position	+N/-S	0.0 ft	Northing: 60,477.32 m
	+E/-W	0.0 ft	Easting: 804,772.91 m
Position Uncertainty	0.0 ft	Wellhead Elevation:	ft
		Latitude:	37° 11' 27.348 N
		Longitude:	109° 18' 6.120 W
		Ground Level:	4,911.4 ft

Wellbore	Hz				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	IGRF2010	2/1/2013	10.39	63.52	50,630

Design	Final				
Audit Notes:					
Version:	1.0	Phase:	ACTUAL	Tie On Depth:	0.0
Vertical Section:	Depth From (TVD) (ft)	+N/-S (ft)	+E/-W (ft)	Direction (°)	
	0.0	0.0	0.0	314.97	

Survey Program	Date	7/25/2013			
From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description	
5,161.5	9,134.0	Final (Hz)	MVVD	MVVD - Standard	

Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	Subsea (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.0	0.00	0.00	0.0	-4,927.9	0.0	0.0	0.0	0.00	0.00	0.00
Top of Window; 5161.5' MD										
5,161.5	0.00	0.00	5,161.5	233.6	0.0	0.0	0.0	0.00	0.00	0.00
Btm of Window; 5169' MD										
5,169.0	1.90	319.00	5,169.0	241.1	0.1	-0.1	0.1	25.33	25.33	0.00
5,191.0	2.60	327.38	5,191.0	263.1	0.8	-0.6	1.0	3.51	3.18	38.09
5,221.0	6.00	331.00	5,220.9	293.0	2.7	-1.7	3.1	11.36	11.33	12.07
5,251.0	9.20	315.60	5,250.6	322.7	5.8	-4.2	7.1	12.55	10.67	-51.33
5,283.0	13.30	313.50	5,282.0	354.1	10.2	-8.6	13.3	12.87	12.81	-6.56
5,314.0	17.70	311.90	5,311.9	384.0	15.8	-14.7	21.6	14.26	14.19	-5.16

Company:	Resolute Natural Resources	Local Co-ordinate Reference:	Well 29-33H
Project:	Ratherford Unit (Nad 27)	TVD Reference:	RKB @ 4927.9ft (D&J 1)
Site:	Ratherford Unit 29-33	MD Reference:	RKB @ 4927.9ft (D&J 1)
Well:	29-33H	North Reference:	Grid
Wellbore:	Hz	Survey Calculation Method:	Minimum Curvature
Design:	Final	Database:	EDM 5000.1 Single User Db

Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	Subsea (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
5,344.0	21.50	312.60	5,340.1	412.2	22.6	-22.2	31.6	12.69	12.67	2.33
5,375.0	25.70	314.40	5,368.5	440.6	31.1	-31.1	44.0	13.74	13.55	5.81
5,406.0	29.10	316.50	5,396.0	468.1	41.3	-41.1	58.3	11.40	10.97	6.77
5,438.0	29.50	318.40	5,424.0	496.1	52.8	-51.7	73.9	3.16	1.25	5.94
5,469.0	31.80	319.90	5,450.6	522.7	64.8	-62.1	89.7	7.82	7.42	4.84
5,499.0	35.90	320.10	5,475.5	547.6	77.6	-72.8	106.3	13.67	13.67	0.67
5,530.0	39.40	320.40	5,500.1	572.2	92.1	-84.9	125.2	11.31	11.29	0.97
5,561.0	42.20	320.30	5,523.5	595.6	107.7	-97.8	145.3	9.03	9.03	-0.32
5,593.0	45.80	319.20	5,546.6	618.7	124.7	-112.2	167.5	11.50	11.25	-3.44
5,624.0	50.80	317.70	5,567.2	639.3	142.0	-127.5	190.6	16.53	16.13	-4.84
5,654.0	55.40	317.60	5,585.2	657.3	159.7	-143.7	214.5	15.34	15.33	-0.33
5,685.0	57.20	318.40	5,602.4	674.5	178.9	-161.0	240.3	6.19	5.81	2.58
Landing Pt. (29-33)										
5,716.0	59.60	318.80	5,618.6	690.7	198.7	-178.4	266.6	7.82	7.74	1.29
5,741.0	61.60	318.60	5,630.9	703.0	215.1	-192.8	288.4	8.03	8.00	-0.80
5,772.0	65.40	318.60	5,644.7	716.8	235.9	-211.1	316.1	12.26	12.26	0.00
5,804.0	69.40	319.40	5,657.0	729.1	258.2	-230.5	345.5	12.71	12.50	2.50
5,834.0	70.80	319.40	5,667.2	739.3	279.6	-248.9	373.6	4.67	4.67	0.00
5,865.0	74.80	319.10	5,676.4	748.5	302.0	-268.2	403.2	12.94	12.90	-0.97
Landing Pt. 29-33 P3										
5,886.4	74.91	319.08	5,676.8	748.9	303.0	-269.1	404.5	7.90	7.74	-1.63
5,896.0	77.20	318.60	5,683.9	756.0	324.6	-288.0	433.2	7.90	7.74	-1.61
5,928.0	79.10	317.70	5,690.5	762.6	348.0	-308.9	464.4	6.54	5.94	-2.81
5,959.0	82.00	318.10	5,695.6	767.7	370.7	-329.4	495.0	9.44	9.35	1.29
Landing Pt. 29-33 P5										
5,965.0	82.79	318.31	5,696.3	768.4	375.1	-333.3	500.9	13.69	13.22	3.57
5,990.0	86.10	319.20	5,698.8	770.9	393.8	-349.7	525.7	13.69	13.23	3.54
6,021.0	90.40	320.10	5,699.7	771.8	417.4	-369.8	556.6	14.17	13.87	2.90
6,053.0	90.80	319.90	5,699.4	771.5	441.9	-390.4	588.5	1.40	1.25	-0.63
6,084.0	90.70	320.00	5,699.0	771.1	465.6	-410.3	619.4	0.46	-0.32	0.32
6,115.0	90.60	319.90	5,698.6	770.7	489.4	-430.3	650.3	0.46	-0.32	-0.32
6,147.0	90.30	320.10	5,698.4	770.5	513.9	-450.8	682.1	1.13	-0.94	0.63
6,178.0	90.30	320.20	5,698.2	770.3	537.7	-470.7	713.0	0.32	0.00	0.32
6,208.0	90.20	320.10	5,698.1	770.2	560.7	-489.9	742.9	0.47	-0.33	-0.33
6,238.0	90.20	319.90	5,698.0	770.1	583.7	-509.2	772.8	0.67	0.00	-0.67
6,269.0	89.40	319.20	5,698.1	770.2	607.3	-529.3	803.7	3.43	-2.58	-2.26
6,301.0	89.60	319.30	5,698.4	770.5	631.5	-550.2	835.6	0.70	0.63	0.31
6,332.0	89.30	319.20	5,698.7	770.8	655.0	-570.4	866.5	1.02	-0.97	-0.32
6,364.0	88.90	319.70	5,699.2	771.3	679.3	-591.2	898.4	2.00	-1.25	1.56
6,395.0	89.60	321.00	5,699.6	771.7	703.2	-611.0	929.2	4.76	2.26	4.19
6,426.0	91.00	320.60	5,699.4	771.5	727.2	-630.6	960.1	4.70	4.52	-1.29
6,457.0	90.60	319.70	5,699.0	771.1	751.0	-650.5	991.0	3.18	-1.29	-2.90
6,489.0	90.70	320.20	5,698.6	770.7	775.5	-671.1	1,022.8	1.59	0.31	1.56
6,519.0	89.60	319.90	5,698.5	770.6	798.5	-690.3	1,052.7	3.80	-3.67	-1.00

Company:	Resolute Natural Resources	Local Co-ordinate Reference:	Well 29-33H
Project:	Ratherford Unit (Nad 27)	TVD Reference:	RKB @ 4927.9ft (D&J 1)
Site:	Ratherford Unit 29-33	MD Reference:	RKB @ 4927.9ft (D&J 1)
Well:	29-33H	North Reference:	Grid
Wellbore:	Hz	Survey Calculation Method:	Minimum Curvature
Design:	Final	Database:	EDM 5000.1 Single User Db

Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	Subsea (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
6,550.0	89.70	319.80	5,698.7	770.8	822.2	-710.3	1,083.6	0.46	0.32	-0.32
6,581.0	89.50	319.10	5,698.9	771.0	845.8	-730.5	1,114.5	2.35	-0.65	-2.26
6,612.0	89.50	319.00	5,699.2	771.3	869.2	-750.8	1,145.4	0.32	0.00	-0.32
VS 1175'										
6,638.4	89.41	318.82	5,699.5	771.6	889.1	-768.1	1,171.8	0.75	-0.33	-0.67
6,642.0	89.40	318.80	5,699.5	771.6	891.8	-770.5	1,175.4	0.75	-0.33	-0.67
6,672.0	90.70	318.60	5,699.5	771.6	914.3	-790.3	1,205.3	4.38	4.33	-0.67
6,702.0	90.80	318.40	5,699.1	771.2	936.8	-810.2	1,235.2	0.75	0.33	-0.67
6,734.0	90.70	319.60	5,698.7	770.8	960.9	-831.2	1,267.1	3.76	-0.31	3.75
6,765.0	90.30	318.40	5,698.4	770.5	984.3	-851.5	1,298.1	4.08	-1.29	-3.87
6,796.0	89.60	318.10	5,698.4	770.5	1,007.4	-872.1	1,329.0	2.46	-2.26	-0.97
6,827.0	90.40	318.30	5,698.4	770.5	1,030.6	-892.8	1,360.0	2.66	2.58	0.65
6,858.0	91.80	317.80	5,697.8	769.9	1,053.6	-913.5	1,390.9	4.80	4.52	-1.61
6,889.0	91.70	319.30	5,696.9	769.0	1,076.8	-934.0	1,421.8	4.85	-0.32	4.84
6,921.0	91.00	319.90	5,696.1	768.2	1,101.2	-954.8	1,453.7	2.88	-2.19	1.88
6,952.0	91.20	320.50	5,695.5	767.6	1,125.0	-974.6	1,484.6	2.04	0.65	1.94
6,983.0	90.90	320.00	5,695.0	767.1	1,148.8	-994.4	1,515.5	1.88	-0.97	-1.61
7,014.0	90.20	319.80	5,694.7	766.8	1,172.5	-1,014.4	1,546.3	2.35	-2.26	-0.65
7,045.0	89.90	319.50	5,694.6	766.7	1,196.2	-1,034.5	1,577.2	1.37	-0.97	-0.97
7,076.0	89.80	319.70	5,694.7	766.8	1,219.8	-1,054.6	1,608.1	0.72	-0.32	0.65
7,107.0	89.70	319.90	5,694.8	766.9	1,243.5	-1,074.6	1,639.0	0.72	-0.32	0.65
7,138.0	89.80	320.20	5,695.0	767.1	1,267.2	-1,094.5	1,669.9	1.02	0.32	0.97
7,170.0	89.70	320.20	5,695.1	767.2	1,291.8	-1,115.0	1,701.8	0.31	-0.31	0.00
7,199.0	89.30	319.80	5,695.4	767.5	1,314.0	-1,133.6	1,730.6	1.95	-1.38	-1.38
7,231.0	89.60	319.90	5,695.7	767.8	1,338.5	-1,154.2	1,762.5	0.99	0.94	0.31
7,262.0	89.90	320.20	5,695.8	767.9	1,362.2	-1,174.1	1,793.4	1.37	0.97	0.97
7,293.0	90.60	320.90	5,695.7	767.8	1,386.2	-1,193.8	1,824.3	3.19	2.26	2.26
7,325.0	89.80	320.10	5,695.6	767.7	1,410.9	-1,214.2	1,856.1	3.54	-2.50	-2.50
7,355.0	89.90	319.50	5,695.6	767.7	1,433.8	-1,233.5	1,886.0	2.03	0.33	-2.00
7,387.0	90.00	319.80	5,695.7	767.8	1,458.2	-1,254.3	1,917.9	0.99	0.31	0.94
7,418.0	90.00	319.60	5,695.7	767.8	1,481.8	-1,274.3	1,948.8	0.65	0.00	-0.65
7,448.0	89.70	319.00	5,695.8	767.9	1,504.6	-1,293.9	1,978.7	2.24	-1.00	-2.00
7,479.0	89.00	318.70	5,696.1	768.2	1,527.9	-1,314.3	2,009.6	2.46	-2.26	-0.97
7,511.0	88.70	318.60	5,696.7	768.8	1,551.9	-1,335.4	2,041.6	0.99	-0.94	-0.31
7,542.0	88.70	319.10	5,697.4	769.5	1,575.3	-1,355.8	2,072.5	1.61	0.00	1.61
7,573.0	89.50	318.60	5,697.9	770.0	1,598.6	-1,376.2	2,103.4	3.04	2.58	-1.61
7,605.0	89.50	319.00	5,698.2	770.3	1,622.7	-1,397.3	2,135.3	1.25	0.00	1.25
VS 2158'										
7,621.7	90.09	318.62	5,698.3	770.4	1,635.3	-1,408.3	2,152.0	4.21	3.55	-2.26
7,636.0	90.60	318.30	5,698.2	770.3	1,645.9	-1,417.8	2,166.3	4.21	3.55	-2.26
7,667.0	90.60	317.70	5,697.9	770.0	1,669.0	-1,438.5	2,197.2	1.94	0.00	-1.94
7,696.0	90.30	317.40	5,697.6	769.7	1,690.4	-1,458.1	2,226.2	1.46	-1.03	-1.03
7,727.0	90.30	317.30	5,697.5	769.6	1,713.2	-1,479.1	2,257.2	0.32	0.00	-0.32

Company:	Resolute Natural Resources	Local Co-ordinate Reference:	Well 29-33H
Project:	Ratherford Unit (Nad 27)	TVD Reference:	RKB @ 4927.9ft (D&J 1)
Site:	Ratherford Unit 29-33	MD Reference:	RKB @ 4927.9ft (D&J 1)
Well:	29-33H	North Reference:	Grid
Wellbore:	Hz	Survey Calculation Method:	Minimum Curvature
Design:	Final	Database:	EDM 5000.1 Single User Db

Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	Subsea (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
7,758.0	90.70	317.70	5,697.2	769.3	1,736.0	-1,500.0	2,288.1	1.82	1.29	1.29
7,788.0	90.20	318.40	5,697.0	769.1	1,758.3	-1,520.1	2,318.1	2.87	-1.67	2.33
7,819.0	91.50	319.50	5,696.5	768.6	1,781.7	-1,540.4	2,349.0	5.49	4.19	3.55
7,854.0	91.70	319.70	5,695.5	767.6	1,808.4	-1,563.1	2,383.9	0.81	0.57	0.57
7,884.0	91.90	319.30	5,694.6	766.7	1,831.2	-1,582.6	2,413.8	1.49	0.67	-1.33
7,915.0	92.50	319.70	5,693.4	765.5	1,854.7	-1,602.7	2,444.7	2.33	1.94	1.29
7,945.0	93.50	319.80	5,691.8	763.9	1,877.6	-1,622.1	2,474.5	3.35	3.33	0.33
7,976.0	93.20	319.10	5,690.0	762.1	1,901.1	-1,642.2	2,505.4	2.45	-0.97	-2.26
8,007.0	93.20	319.10	5,688.3	760.4	1,924.5	-1,662.4	2,536.2	0.00	0.00	0.00
8,038.0	92.50	318.80	5,686.7	758.8	1,947.8	-1,682.8	2,567.1	2.46	-2.26	-0.97
8,064.0	91.60	318.50	5,685.8	757.9	1,967.3	-1,699.9	2,593.0	3.65	-3.46	-1.15
8,095.0	90.00	318.00	5,685.4	757.5	1,990.5	-1,720.6	2,624.0	5.41	-5.16	-1.61
8,125.0	89.20	317.10	5,685.6	757.7	2,012.6	-1,740.8	2,654.0	4.01	-2.67	-3.00
8,156.0	89.30	315.00	5,686.0	758.1	2,034.9	-1,762.3	2,684.9	6.78	0.32	-6.77
8,188.0	91.00	315.50	5,685.9	758.0	2,057.6	-1,784.9	2,716.9	5.54	5.31	1.56
8,218.0	91.80	316.60	5,685.2	757.3	2,079.2	-1,805.7	2,746.9	4.53	2.67	3.67
8,248.0	91.70	317.00	5,684.3	756.4	2,101.1	-1,826.2	2,776.9	1.37	-0.33	1.33
8,279.0	91.40	318.00	5,683.4	755.5	2,123.9	-1,847.1	2,807.9	3.37	-0.97	3.23
8,311.0	92.10	318.00	5,682.4	754.5	2,147.7	-1,868.5	2,839.8	2.19	2.19	0.00
8,342.0	91.90	319.50	5,681.4	753.5	2,171.0	-1,889.0	2,870.7	4.88	-0.65	4.84
8,372.0	92.20	319.80	5,680.3	752.4	2,193.9	-1,908.4	2,900.6	1.41	1.00	1.00
8,402.0	91.60	320.40	5,679.3	751.4	2,216.9	-1,927.6	2,930.5	2.83	-2.00	2.00
8,432.0	91.40	320.40	5,678.5	750.6	2,240.0	-1,946.7	2,960.3	0.67	-0.67	0.00
8,462.0	92.20	319.90	5,677.6	749.7	2,263.0	-1,965.9	2,990.2	3.14	2.67	-1.67
8,493.0	92.30	319.90	5,676.4	748.5	2,286.7	-1,985.9	3,021.0	0.32	0.32	0.00
VS 3057'										
8,521.0	90.72	320.43	5,675.6	747.7	2,308.2	-2,003.8	3,048.9	5.93	-5.62	1.88
8,525.0	90.50	320.50	5,675.6	747.7	2,311.3	-2,006.4	3,052.9	5.93	-5.63	1.87
8,556.0	90.90	320.50	5,675.2	747.3	2,335.2	-2,026.1	3,083.7	1.29	1.29	0.00
8,588.0	90.70	320.30	5,674.7	746.8	2,359.8	-2,046.5	3,115.6	0.88	-0.63	-0.63
8,619.0	88.10	319.90	5,675.1	747.2	2,383.6	-2,066.4	3,146.5	8.49	-8.39	-1.29
8,650.0	88.60	319.60	5,676.0	748.1	2,407.3	-2,086.4	3,177.3	1.88	1.61	-0.97
8,682.0	89.20	319.30	5,676.6	748.7	2,431.6	-2,107.2	3,209.2	2.10	1.88	-0.94
8,714.0	89.30	319.10	5,677.0	749.1	2,455.8	-2,128.1	3,241.2	0.70	0.31	-0.63
8,744.0	88.50	319.20	5,677.6	749.7	2,478.5	-2,147.7	3,271.1	2.69	-2.67	0.33
8,775.0	87.80	318.40	5,678.6	750.7	2,501.8	-2,168.1	3,302.0	3.43	-2.26	-2.58
8,806.0	88.20	318.30	5,679.7	751.8	2,524.9	-2,188.7	3,332.9	1.33	1.29	-0.32
8,838.0	89.10	318.40	5,680.4	752.5	2,548.8	-2,210.0	3,364.8	2.83	2.81	0.31
8,869.0	90.00	318.40	5,680.7	752.8	2,572.0	-2,230.6	3,395.8	2.90	2.90	0.00
8,901.0	89.10	317.90	5,680.9	753.0	2,595.9	-2,251.9	3,427.7	3.22	-2.81	-1.56
8,932.0	89.10	317.90	5,681.4	753.5	2,618.9	-2,272.7	3,458.7	0.00	0.00	0.00
8,961.0	90.50	318.30	5,681.5	753.6	2,640.4	-2,292.0	3,487.6	5.02	4.83	1.38
8,991.0	90.70	318.50	5,681.2	753.3	2,662.9	-2,312.0	3,517.6	0.94	0.67	0.67
Extrap to Bit; 9006' MD										

Company:	Resolute Natural Resources	Local Co-ordinate Reference:	Well 29-33H
Project:	Ratherford Unit (Nad 27)	TVD Reference:	RKB @ 4927.9ft (D&J 1)
Site:	Ratherford Unit 29-33	MD Reference:	RKB @ 4927.9ft (D&J 1)
Well:	29-33H	North Reference:	Grid
Wellbore:	Hz	Survey Calculation Method:	Minimum Curvature
Design:	Final	Database:	EDM 5000.1 Single User Db

Survey										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	Subsea (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
9,006.0	90.89	318.59	5,681.0	753.1	2,674.1	-2,321.9	3,532.6	1.40	1.25	0.62
9,023.0	91.10	318.70	5,680.7	752.8	2,686.9	-2,333.1	3,549.5	1.40	1.25	0.63
9,055.0	91.50	318.60	5,679.9	752.0	2,710.9	-2,354.3	3,581.4	1.29	1.25	-0.31
9,086.0	91.20	318.50	5,679.2	751.3	2,734.1	-2,374.8	3,612.4	1.02	-0.97	-0.32
9,089.0	91.20	318.50	5,679.2	751.3	2,736.4	-2,376.8	3,615.4	0.00	0.00	0.00
Toe (29-33)										
9,134.0	90.70	318.50	5,678.4	750.5	2,770.1	-2,406.6	3,660.3	1.11	-1.11	0.00

Survey Annotations					
Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates		Comment	
		+N/-S (ft)	+E/-W (ft)		
5,161.5	5,161.5	0.0	0.0	Top of Window; 5161.5' MD	
5,169.0	5,169.0	0.1	-0.1	Btm of Window; 5169' MD	
9,006.0	5,681.2	2,674.2	-2,321.8	Extrap to Bit; 9006' MD	

Checked By: _____ Approved By: _____ Date: _____

Mezintel

Measured Depth Log 5"=100ft

Feet

Oil Co: **Resolute Natural Resources**
Well Name: **RU 29-33H**
LSD: **SEC S29-T41S-R24E**
State/Prov: **UT**
Country: **USA**
Job #: **MWDTECH1318**

Oil Company: **Resolute Natural Resources**
Well Name: **RU 29-33H**
LSD: **SEC S29-T41S-R24E**
State/Prov: **UT**
Country: **USA**
Job #: **MWDTECH1318**
Drilling Co. **D & J Drilling**
Rig #: **D & J 1**
Co Rep 1: **Dee Gillis**
Co Rep 2: **Art Velasquez**
Geologist 1: **David Westbrook**
Geologist 2: **Shane Sloigar**
DD 1: **Ron Alexus**
DD 2: **Chuck Tripp**
MWD 1: **Chuck Tripp**
MWD 2: **Chuck Tripp**
MWD Kit: **P105**

Well Lic: **API/UWI: 43-037-30932**
AFE #: **10013781**

Casing Depths			MD	Depth	Date		KB#927.90	
Surface:			Start:	8500	7/6/13		GL: 4911.4	
Intermediate:			End:	9134.04			DF: 16.50	
Run #	Hole Size (in)	Gamma Offset	Survey Offset	Depth Start	Depth End	Date Start	Date End	
01	6 1/4	38.00	45.00	5176.00	5783.00	Jul 06, 13	Jul 10, 13	
02	6 1/4	40.00	46.00	5783.00	7865.00	Jul 10, 13	Jul 17, 13	
03	6 1/4	40.30	46.00	7865.00	8076.00	Jul 17, 13	Jul 19, 13	
04	6 1/4	38.10	45.00	8076.00	9134.80	Jul 19, 13	Jul 24, 13	

Mezintel uses its best efforts to provide customers with accurate information on services performed but will not be held liable or responsible for accuracy of information or interpretation.

Client: **Resolute Natural Resources**

Well Name: **RU 29-33H**

Well Lic:

API/UWI: **43-037-30932**

Surface LSD: **SEC S29-T41S-R24E** KB: **4927.90**

State/Prov: **UT** Job #: **MWDTECH1318** L: **4911.4**


Country: **USA** MWD Kit: **P105** DF: **16.50**

Mezintel


0 Gamma [API] 150
150 Gamma [API] 300

Feet
5":100'
MD

0 ROP [ft per hr] 100




8500
8510
8520



RECEIVED
MD=8525.0 INC=90.5
AZM=328.5 TVD=5675.6
2013

APT Well Number: 43037309

320000



MD=8556.0 INC=90.9
AZM=320.5 TVD=5675.2

MD=8588.0 INC=90.7
AZM=320.3 TVD=5674.8

MD=8619.0 INC=88.1
AZM=319.9 TVD=5675.1

MD=8650.0 INC=88.6
AZM=319.6 TVD=5676.0

MD=8682.0 INC=89.2
AZM=319.3 TVD=5676.6


MD=8713.0 INC=89.3
AZM=319.1 TVD=5677.0

MD=8744.0 INC=88.5
AZM=319.2 TVD=5677.6

RECEIVED

API Well Number: 43037309

320000



MD=8775.0 INC=87.8
AZM=318.4 TVD=5678.6

MD=8806.0 INC=88.2
AZM=318.3 TVD=5679.7

MD=8838.0 INC=89.1
AZM=318.4 TVD=5680.5


MD=8869.0 INC=90.0
AZM=318.4 TVD=5680.7

MD=8901.0 INC=89.1
AZM=317.9 TVD=5681.0

MD=8932.0 INC=89.1
AZM=317.9 TVD=5681.5

MD=8961.0 INC=90.5
AZM=318.3 TVD=5681.6

API Well Number: 43037309320000



0 Gamma [API] 150
150 Gamma [API] 300

Feet
5":100'
MD

0 ROP [ft per hr] 100

Client: **Resolute Natural Resources**

Well Name: **RU 29-33H**

Well Lic: _____

API/IWT: **43-037-30932**

RECEIVED: Aug. 27, 2013

Mezintel

API Well Number: 430673093000	API/OWI: 430673093000	SEC S29-T41S-R24E	KB:	4927.90
State/Prov:	UT	Job #:	MWDTECH1318	GL: 4911.4
Country:	USA	MWD Kit:	P105	DF: 16.50

Mezintel

TVD Log

**5"=100ft
Feet**

Oil Co: **Resolute Natural Resources**
Well Name: **RU 29-33H**
LSD: **SEC S29-T41S-R24E**
State/Prov: **UT**
Country: **USA**
Job #: **MWDTECH1318**

Oil Company: **Resolute Natural Resources**
Well Name: **RU 29-33H**
LSD: **SEC S29-T41S-R24E**
State/Prov: **UT**
Country: **USA**
Job #: **MWDTECH1318**
Drilling Co. **D & J Drilling**
Rig #: **D & J 1**
Co Rep 1: **Dee Gillis**
Co Rep 2: **Art Velasquez**
Geologist 1:
Geologist 2:
DD 1:
DD 2:
MWD 1: **David Westbrook**
MWD 2: **Shane Sloigar**
MWD Kit: **Ron Alexus**
Chuck Tripp
P105

Well Lic:
API/UWI: **43-037-30932**
AFE #: **10013781**

Casing Depths				TVD	Depth	Date	
Surface: Intermediate:				Start:	5178	7/6/13	
				End:	5699.71		
Run #	Hole Size (in)	Gamma Offset	Survey Offset	Depth Start	Depth End	Date Start	Date End
01	6 1/4	38.00	45.00	5176.00	5783.00	Jul 06, 13	Jul 10, 13
02	6 1/4	40.00	46.00	5783.00	7865.00	Jul 10, 13	Jul 17, 13
03	6 1/4	40.30	46.00	7865.00	8076.00	Jul 17, 13	Jul 19, 13
04	6 1/4	38.10	45.00	8076.00	9134.80	Jul 19, 13	Jul 24, 13

Client: **Resolute Natural Resources**

Well Name: **RU 29-33H**

Well Lic:

API/UWI: **43-037-30932**

Surface LSD: **SEC S29-T41S-R24E** KB: **4927.90**

State/Prov: **UT** Job #: **MWDTECH1318** L: **4911.4**


Country: **USA** MWD Kit: **P105** DF: **16.50**

Mezintel


0 Gamma [API] 150
150 Gamma [API] 300

Feet
5":100'
TVD

0 ROP [ft per hr] 100




5170
5180
5190



MD=5191.0 INC=2.6
AZM=327.4 TVD=5191.0
RECEIVED: Aug. 27, 2013

APT Well Number: 43037309

320000



- 5210 -

- 5220 -

- 5230 -

- 5240 -

- 5250 -

- 5260 -

- 5270 -

- 5280 -

- 5290 -

- 5300 -

- 5310 -

- 5320 -

- 5330 -

- 5340 -

- 5350 -

- 5360 -

- 5370 -

- 5380 -

- 5390 -

- 5400 -

- 5410 -

- 5420 -

MD=5221.0 INC=6.0
AZM=331.0 TVD=5220.9

MD=5251.0 INC=9.2
AZM=315.6 TVD=5250.6

MD=5283.0 INC=13.3
AZM=313.5 TVD=5282.0

MD=5314.0 INC=17.7
AZM=311.9 TVD=5311.9

MD=5344.0 INC=21.5
AZM=312.6 TVD=5340.1

MD=5375.0 INC=25.7
AZM=314.4 TVD=5368.5

MD=5406.0 INC=29.1
AZM=316.5 TVD=5396.0

API Well Number: 43037309

320000

MD=5438.0 INC=29.5
AZM=318.4 TVD=5424.0

- 5430 -

- 5440 -

- 5450 -

MD=5469.0 INC=31.8
AZM=319.9 TVD=5450.6

- 5460 -

- 5470 -

MD=5499.0 INC=35.9
AZM=320.1 TVD=5475.5

- 5480 -

- 5490 -

- 5500 -

MD=5530.0 INC=39.4
AZM=320.4 TVD=5500.1

- 5510 -

- 5520 -

MD=5561.0 INC=42.2
AZM=320.3 TVD=5523.5

- 5530 -

- 5540 -

MD=5593.0 INC=45.8
AZM=319.2 TVD=5546.6

- 5550 -

- 5560 -

MD=5624.0 INC=50.8
AZM=317.7 TVD=5567.2

- 5570 -

- 5580 -

MD=5654.0 INC=55.4
AZM=317.6 TVD=5585.2

- 5590 -

- 5600 -

MD=5685.0 INC=57.2
AZM=318.4 TVD=5602.4

- 5610 -

- 5620 -


MD=5716.0 INC=59.6
AZM=318.8 TVD=5618.6

- 5630 -

MD=5741.0 INC=61.6
AZM=318.6 TVD=5630.9


RECEIVED: Aug. 27, 2013

API Well Number: 43-037-3093



320000


5640
- 5650
- 5660
- 5670
- 5680
- 5690
- 5700



MD=5772.0 INC=65.4
AZM=318.6 TVD=5644.7

MD=5804.0 INC=69.4
AZM=319.4 TVD=5657.0

MD=5834.0 INC=70.8
AZM=319.4 TVD=5667.2



0 Gamma [API] 150
150 Gamma [API] 300

Feet
5":100'
TVD

0 ROP [ft per hr] 100

Mezintel

Client: **Resolute Natural Resources**

Well Name: **RU 29-33H**

Well Lic:

API/UWI: **43-037-30932**

Surface LSD: **SEC S29-T41S-R24E**

KB: **4927.90**

State/Prov: **UT**

Job #: **MWDTECH1318**

L: **4911.4**



Country: **USA**

MWD Kit: **P105**

DF: **16.50**

RECEIVED: Aug. 27, 2013

R. 24 E., T. 41 S.



SCALE: 1" = 1000'

GEO. SURFACE VALUES

LATITUDE (NAD 83)
NORTH 37.1911711°
LONGITUDE (NAD 83)
WEST 109.3026332°
LATITUDE (NAD 27)
NORTH 37.1911725°
LONGITUDE (NAD 27)
WEST 109.3019637°

NORTHING
198502.47
EASTING
2640246.94

GEO. BOTTOM HOLE LOCATION 2 VALUES

LATITUDE (NAD 83)
NORTH 37.1883417°
LONGITUDE (NAD 83)
WEST 109.2984831°
LATITUDE (NAD 27)
NORTH 37.1883431°
LONGITUDE (NAD 27)
WEST 109.2978137°

NORTHING
197501.00
EASTING
2641479.79

DATUM
UTAH SP SOUTH (1927)

SURVEYOR'S STATEMENT:

I, John A. Vukonich, of Farmington, New Mexico, hereby state: This plat was made from notes taken during an actual survey under my direct supervision on FEBRUARY 8, 2013, and it correctly shows the location of RATHERFORD UNIT WELL NO. 29-33.

LEGEND

- ◆ SURFACE WELL LOCATION
- BOTTOM HOLE LOCATION
- CALCULATED POSITION
- FOUND MONUMENT
- L DENOTES 90° TIE
- (C) CALCULATED

I certify this plat to reflect the one lateral drilled, to the best of my knowledge at this time.

Sherry Glass 10-23-13
Sr. Regulatory Technician, Resolute Aneth, LLC




PLAT OF PROPOSED WELL LOCATION FOR RESOLUTE NATURAL RESOURCES COMPANY


P.O. BOX 3651
FARMINGTON, N.M.
(505) 334-0408

SCALE: 1" = 1000'
JOB No. 10445
DATE: 03/01/13

**SURFACE: 1859' F/NL & 1836' F/EL,
BOTTOM HOLE 1: 544' F/NL & 1069' F/WL,
BOTTOM HOLE 2: 829' F/SL & 628' F/EL, SECTION 29,
T. 41 S, R. 24 E, SLM., SAN JUAN COUNTY, UTAH**



CUT	FILL	NET
5350 Cu. Yd.	19457 Cu. Yd.	14107 Cu. Yd. (FILL)



HORIZONTAL: 1"=100'
VERTICAL: 1"=50'

EXHIBIT 1A

ELEVATION: 4911


RESOLUTE
NATURAL RESOURCES

FILE NAME: 10445C01



UNITED
FIELD SERVICES INC.

**P.O. BOX 3651
FARMINGTON, NM 87499
OFFICE: (505) 334-0408**



STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-603-407			
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NAVAJO			
2. NAME OF OPERATOR: RESOLUTE NATURAL RESOURCES		7. UNIT or CA AGREEMENT NAME: RATHERFORD			
3. ADDRESS OF OPERATOR: 1700 Lincoln Street, Suite 2800 , Denver, CO, 80203 4535		8. WELL NAME and NUMBER: 29-33			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1859 FSL 1836 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 29 Township: 41.0S Range: 24.0E Meridian: S		9. API NUMBER: 43037309320000			
9. FIELD and POOL or WILDCAT: GREATER ANETH		COUNTY: SAN JUAN			
STATE: UTAH					
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 3/17/2015 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	TYPE OF ACTION <table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Replace ESP with Rod Pump </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Replace ESP with Rod Pump
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Replace ESP with Rod Pump			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Resolute Natural Resources respectfully submits this sundry as notice that we will be removing the ESP pump and replacing with a Rod Pump. See attached procedures and before and after schematics					
Accepted by the Utah Division of Oil, Gas and Mining Date: April 02, 2015 By:					
NAME (PLEASE PRINT) Erin Joseph		PHONE NUMBER 303 573-4886			
SIGNATURE N/A		TITLE Sr. Regulatory Analyst			
DATE 3/10/2015					

Resolute

Natural Resources

RU 29-33H Pull Failed ESP & Replace with Rod Pump

Horsley Witten: YES - Chinle isolated by surface casing - no remedial cement isolation required.

Procedure:

1. PRODUCTION/ICE: Change electric service from ESP to Lufkin 228-246-86 beam pump; Move & set up used Lufkin 228 unit from RU 30-32 (TA'd April 2014).
2. MIRU WSU, LOTO.
3. Pressure test the tubing against check valve at top of ESP. Shift 2-7/8 sliding sleeve open at 5009' KB.
4. Pump in & kill well as necessary.
5. ND WH, NU BOP; cut cable. PU tubing & test packer, test BOP. LD packer.
6. MIRU ESP cable spooler & capillary string spooler. Note: plan to re-run 60' cap string if condition is OK after trip out & PT is good. If not, run new 1/4" x 60' cap string.
7. POOH with failed ESP, cable, cap string, & 2-7/8 tubing. Stand back tubing. Call and notify Bill Albert (970) 371-9682 for inspection. If unavailable, contact Tech Support: Virgil Holly or Nate Dee. Tubing to be used for bit & scraper run, then replaced, if inspection dictates, with 2-7/8 YB.
8. TIH with extra joints and bit & scraper to top of window @ 5161' KB.
9. TOOH with bit & scraper laying down tbg. Pending inspection, tbg may be sent for inspection/recond.
10. RIH with rod pumping BHA & 2-7/8 tubing as follows: 3-1/2" MA joint, crossover, 2-7/8 carbon steel SN, 3-1/2" blast joint with crossovers, 3 jts 2-7/8 tubing, 7" TAC, and 2-7/8 tubing to surface, including cap string to 60'. NOTE: cap string may be run deeper pending tubing inspection results.
11. Set TAC at ~4980'; MA/EOT to ~ 5141' KB. Land tubing. NDBOP, NUWH.
12. RIH with reconditioned 7/8 x 3/4 rod string & 1.75" insert pump, seat the pump. Contact Tech Support for pump & rod details.
13. Long stroke pump to test for good pump action.
14. Leave enough polish rod for operators to correctly space pump as required.
15. Notify the Area Production Supervisor Alfred Redhouse (435) 619-7227 that well is ready to return to production.
16. RDMOL. Hook up appropriate chemical treatment.

RATHERFORD UNIT # 29-33H

GREATER ANETH FIELD

1860' FSL & 1820' FEL

SEC 29-T41S-R24E


SAN JUAN COUNTY, UTAH

API 43-037-30932

PRISM 0043140

PRODUCER

Existing Wellbore



RATHERFORD UNIT # 29-33H

GREATER ANETH FIELD

1860' FSL & 1820' FEL

SEC 29-T41S-R24E


SAN JUAN COUNTY, UTAH

API 43-037-30932

PRISM 0043140

PRODUCER

Proposed Wellbore



STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-603-407
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NAVAJO
2. NAME OF OPERATOR: RESOLUTE NATURAL RESOURCES		7. UNIT or CA AGREEMENT NAME: RATHERFORD
3. ADDRESS OF OPERATOR: 1700 Lincoln Street, Suite 2800 , Denver, CO, 80203 4535		8. WELL NAME and NUMBER: 29-33
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1859 FSL 1836 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 29 Township: 41.0S Range: 24.0E Meridian: S		9. API NUMBER: 43037309320000
9. FIELD and POOL or WILDCAT: GREATER ANETH		COUNTY: SAN JUAN
STATE: UTAH		
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 8/30/2015	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input checked="" type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input checked="" type="checkbox"/> OTHER OTHER: Pull pump and BHA	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Resolute Natural Resources respectfully submits this sundry as notice of the well work below. Plan to pull pump, tubing and BHA and re-run according to attached procedures.		
Accepted by the Utah Division of Oil, Gas and Mining		
Date: August 17, 2015		
By:		
NAME (PLEASE PRINT) Erin Joseph	PHONE NUMBER 303 573-4886	TITLE Sr. Regulatory Analyst
SIGNATURE N/A	DATE 8/12/2015	

Resolute

Natural Resources

Re: RU 29-33H Workover for Stuck TAC

Horsley Witten: NO.

Procedure:

1. MIRU WSU, LOTO.
2. Pressure test tubing to 1000 psig.
3. Kill well as necessary.
4. POOH with rods and pump, standing back rods. Call and notify Bill Albert (970) 371-9682 to inspect rods. If unavailable, contact Tech Support: Virgil Holly (435) 444-0020 or Nate Dee. **Check for paraffin on rods; history of paraffin: Be prepared to pump paraffin solvent down tubing past the rod string before rods are all pulled if paraffin is heavy.**
5. Inspect rod string & pump for cause of sticking plunger. NU BOPE to pull tubing.
6. Release the TAC @ 4981.7' KB. Install a packer & pressure test BOPE. LD packer.
7. PU tag joints & tag bottom to check for fill; PBD at 5269' KB, below window at 5161-5169'. Tally out of hole & stand back tbg.
8. Call and notify Bill Albert 970-371-9682 to inspect tubing. If unavailable, contact Virgil Holly or Nate Dee.
9. If needed, run bit only for cleanout to 5269' PBD; consider bailer before nitrogen. No cleanout past the window on last pull in Mar2015.
10. TOOH with tubing & bit, standing back.
11. RIH/POH & LD or re-run tbg per inspection results. New 2-7/8 FBNAU tbg was run 8-15-2013; re-run 3-31-2015.
12. TIH with 3-1/2" SMA joint, changeover, 2-7/8 carbon steel SN, 3-1/2" blast joint w/changeovers, 3 jts tubing, TAC and tubing to surface.
13. Set bottom of SMA at ~ 5146' KB as before; set TAC at ~4985' KB.
14. ND BOP, NUWH. Change over for rods.
15. RIH with 1-1/4" x 16' gas anchor, new 1-3/4" insert pump, and rods. Contact Tech Support to confirm pump & rod details.
16. Long stroke pump to test for good pump action.
17. Leave enough polished rod for operators to correctly space pump as required.
18. Notify the Area Production Supervisor Alfred Redhouse (435) 619-7227 that well is ready.
19. RDMOL. Hook up appropriate chemical treatment.

RATHERFORD UNIT # 29-33H

GREATER ANETH FIELD

1860' FSL & 1820' FEL


SEC 29-T41S-R24E

SAN JUAN COUNTY, UTAH

API 43-037-30932

PRISM 0043140

PRODUCER



J. S. 8-10-2015

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-603-407
		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NAVAJO
		7. UNIT or CA AGREEMENT NAME: RATHERFORD
1. TYPE OF WELL Oil Well		8. WELL NAME and NUMBER: 29-33
2. NAME OF OPERATOR: RESOLUTE NATURAL RESOURCES		9. API NUMBER: 43037309320000
3. ADDRESS OF OPERATOR: 1700 Lincoln Street, Suite 2800 , Denver, CO, 80203 4535		9. FIELD and POOL or WILDCAT: GREATER ANETH
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1859 FSL 1836 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 29 Township: 41.0S Range: 24.0E Meridian: S		COUNTY: SAN JUAN
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input type="text" value="Replace pump"/>
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 4/3/2015			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input type="checkbox"/> DRILLING REPORT Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Resolute Natural Resources respectfully submits this sundry as notice that the ESP Pump on the above well was replaced by a Rod Pump on 4/3/2015

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 December 17, 2015

NAME (PLEASE PRINT) Erin Joseph	PHONE NUMBER 303 573-4886	TITLE Sr. Regulatory Analyst
SIGNATURE N/A		DATE 12/17/2015

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-603-407
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NAVAJO
2. NAME OF OPERATOR: RESOLUTE NATURAL RESOURCES		7. UNIT or CA AGREEMENT NAME: RATHERFORD
3. ADDRESS OF OPERATOR: 1700 Lincoln Street, Suite 2800 , Denver, CO, 80203 4535		8. WELL NAME and NUMBER: 29-33
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1859 FSL 1836 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 29 Township: 41.0S Range: 24.0E Meridian: S		9. API NUMBER: 43037309320000
PHONE NUMBER: 303 534-4600 Ext		9. FIELD and POOL or WILDCAT: GREATER ANETH
COUNTY: SAN JUAN		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION	<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <div style="border: 1px solid black; padding: 2px; display: inline-block;">9/5/2015</div> <input type="checkbox"/> SPUD REPORT Date of Spud:
<input type="checkbox"/> DRILLING REPORT Report Date:	<input checked="" type="checkbox"/> OTHER			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Resolute Natural Resources respectfully submits this sundry as notice that the pump and bottom hole assembly were successfully pulled out of the above well as outlined in previously approved procedures.

**Accepted by the
Utah Division of
Oil, Gas and Mining**

FOR RECORD ONLY

January 06, 2016

NAME (PLEASE PRINT) Erin Joseph	PHONE NUMBER 303 573-4886	TITLE Sr. Regulatory Analyst
SIGNATURE N/A	DATE 1/6/2016	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-603-407			
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NAVAJO			
2. NAME OF OPERATOR: RESOLUTE NATURAL RESOURCES		7. UNIT or CA AGREEMENT NAME: RATHERFORD			
3. ADDRESS OF OPERATOR: 1700 Lincoln Street, Suite 2800 , Denver, CO, 80203 4535		8. WELL NAME and NUMBER: 29-33			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1859 FSL 1836 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 29 Township: 41.0S Range: 24.0E Meridian: S		9. API NUMBER: 43037309320000			
9. FIELD and POOL or WILDCAT: GREATER ANETH		COUNTY: SAN JUAN			
STATE: UTAH					
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 3/20/2016 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	TYPE OF ACTION <table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Workover for stuck Pump </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Workover for stuck Pump
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: Workover for stuck Pump			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Resolute Natural Resources respectfully submits this sundry as notice of a workover on the above well. See attached procedures and schematic					
Accepted by the Utah Division of Oil, Gas and Mining Date: March 24, 2016 By:					
NAME (PLEASE PRINT) Erin Joseph		PHONE NUMBER 303 573-4886			
SIGNATURE N/A		TITLE Sr. Regulatory Analyst			
DATE 3/14/2016					

Resolute

Natural Resources

Re: RU 29-33H Producer - Workover for Stuck Pump

Horsley Witten: NO.

Procedure:

1. MIRU WSU, LOTO.
2. Pressure test tubing to 1000 psig.
3. Kill well as necessary.
4. POOH with rods and pump, standing back rods; perform backoff of rods if necessary. Call and notify Bill Albert (970) 371-9682 to inspect rods. If unavailable, contact Tech Support: Virgil Holly (435) 444-0020 or Nate Dee. **Check for paraffin on rods; history of paraffin so be prepared to pump paraffin solvent down tubing after rods are pulled if paraffin is heavy.**
5. Inspect rod string & pump for cause of sticking plunger. If rods & plunger are recovered without backing off rods, pump down tubing w/returns up csg to see if tubing is clear. Shut in returns & continue pumping to see if the well remains bridged off. If no bridge, go to step 17.
6. If wellbore remains bridged off, NU BOPE & prepare to pull tubing.
7. Release the TAC @ 4888.9' KB. Install a packer & pressure test BOPE. LD packer. POOH w/bha & tbg, standing back.
8. Call Bill Albert 970-371-9682 to inspect tubing. If unavailable, contact Virgil Holly or Nate Dee.
9. PU tag joints & 6-1/8" bit, RIH to clean out fill to PBD in vertical section at 5744', = 575' below window at 5161-5169'. POOH.
10. PU off bottom & close pipe rams, pump in PW to check injection rate into lateral + perfs 5640-5726'. If lateral appears to be open, POOH & go to step 13. NOTE: injection rate into the open lateral during Aug 2015 work was 1 bpm @ 100 psi (PW) before the CIBP above the perfs was milled up.
11. If lateral remains bridged off, TOO H with bit, standing back. Evaluate (1) running tbg & pkr to swab, or (2) using Basic CTU or (3) using WSU & 2-7/8 tbg for lateral cleanout.
12. After swabbing or lateral cleanout, pump in to check injection rate to confirm the lateral is open.
13. RIH/POH & LD or re-run tbg per inspection results. New 2-7/8 FBNAU tbg was run 8-15-2013; re-run 3-31-2015 and 9-3-15.
14. TIH with 3-1/2" SMA joint, changeover, 2-7/8 carbon steel SN, 3-1/2" blast joint w/changeovers, 3 jts tubing, 7" TAC and tubing to surface.
15. Set bottom of SMA at ~ 5023' KB = 2 jts higher than previous; set TAC at ~4858' KB.
16. ND BOP, NUWH. Change over for rods.
17. RIH with 1-1/4" x 16' gas anchor, new 1-3/4" insert pump, and rods. Contact Tech Support to confirm pump & rod details.
18. Long stroke pump to test for good pump action.
19. Leave enough polished rod for operators to correctly space pump as required.
20. Notify the Area Production Supervisor Alfred Redhouse 435-619-7227 that well is ready.
21. RDMOL. Hook up appropriate chemical treatment.

RATHERFORD UNIT # 29-33H

GREATER ANETH FIELD

1860' FSL & 1820' FEL


SEC 29-T41S-R24E

SAN JUAN COUNTY, UTAH

API 43-037-30932

PRISM 0043140

PRODUCER



STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-603-407			
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NAVAJO			
2. NAME OF OPERATOR: RESOLUTE NATURAL RESOURCES		7. UNIT or CA AGREEMENT NAME: RATHERFORD			
3. ADDRESS OF OPERATOR: 1700 Lincoln Street, Suite 2800 , Denver, CO, 80203 4535		8. WELL NAME and NUMBER: 29-33			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1859 FSL 1836 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 29 Township: 41.0S Range: 24.0E Meridian: S		9. API NUMBER: 43037309320000			
9. FIELD and POOL or WILDCAT: GREATER ANETH		COUNTY: SAN JUAN			
STATE: UTAH					
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 4/3/2016 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	TYPE OF ACTION <table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Resolute Natural Resources respectfully submits this sundry as notice of workover #2 to retrieve a Stuck Pump in the above wellbore. Attached are the procedures and schematic					
Accepted by the Utah Division of Oil, Gas and Mining Date: April 05, 2016 By: <i>[Signature]</i>					
NAME (PLEASE PRINT) Erin Joseph		PHONE NUMBER 303 573-4886			
SIGNATURE N/A		TITLE Sr. Regulatory Analyst			
DATE 3/31/2016					

Resolute

Natural Resources

Re: RU 29-33H Producer - Workover #2 for Stuck Pump

Horsley Witten: NO.

Procedure:

1. MIRU WSU, LOTO.
2. Pressure test tubing to 1000 psig.
3. Kill well as necessary.
4. POOH with rods and pump, standing back rods; perform backoff of rods if necessary. No rod inspection will be done this time unless something that warrants attention is noted on the trip out with the rods.
5. Inspect rod string & pump for cause of sticking plunger. If rods & plunger are recovered without backing off rods, pump down tubing w/returns up csg to see if tubing is clear. If tbg is clear, shut in returns & continue pumping to see if the csg or lateral remains bridged off. If lateral is open, go to 6.
6. If wellbore remains bridged off, NU BOPE & prepare to pull tubing.
7. Release the TAC @ 4863' KB. Install a packer & pressure test BOPE. LD packer. POOH w/bha & tbg, standing back.
8. No tbg inspection required this trip; previous inspection done on 3/22/16 with tbg OK for re-run.
9. PU tag joints & 6-1/8" bit, RIH & tag fill in vertical section - previous tag at 5617' on 3/22. Pump in to see if the lateral is bridged off; then perform cleanout to PBD at 5744', = 575' below window at 10.
10. PU off bottom & close pipe rams, pump in to confirm injection into lateral + perfs 5640-5726'. If lateral appears to be open, POOH & go to step 13. NOTE: injection rate into the open lateral during Aug 2015 work was 1 bpm @ 100 psi (PW) before the CIBP above the perfs was milled up.
11. If lateral remains bridged off, TOO H with bit, standing back. Evaluate (1) running tbg & pkr to swab, or (2) using Basic CTU or (3) using WSU & 2-7/8 tbg for lateral cleanout.
12. After swabbing or lateral cleanout, pump in to check injection rate to confirm the lateral is open. Flow back from the well can also confirm this if the volume is significant.
13. POOH & re-run tbg & bha. New 2-7/8 FBNAU tbg was run 8-15-2013; re-run 3-31-2015, 9-3-15, and 3-23-16.
14. TIH with 3-1/2" SMA joint, changeover, 2-7/8 carbon steel SN, 3-1/2" blast joint w/changeovers, 3 jts tubing, 7" TAC and tubing to surface.
15. Set bottom of SMA at ~ 4964' KB = 2 jts shallower than previous depth; set TAC at ~4800' KB.
16. ND BOP, NUWH. Change over for rods.
17. RIH with 1-1/4" x 16' gas anchor, new 1-3/4" insert pump with **0.007 clearance, grooved plunger**, and rods. Contact Tech Support to confirm pump & rod details.
18. Long stroke pump to test for good pump action.
19. Leave enough polished rod for operators to correctly space pump as required.
20. Notify the Area Production Supervisor Alfred Redhouse 435-619-7227 that well is ready.
21. RDMOL. Hook up appropriate chemical treatment.

RATHERFORD UNIT # 29-33H

GREATER ANETH FIELD

1860' FSL & 1820' FEL


SEC 29-T41S-R24E

SAN JUAN COUNTY, UTAH

API 43-037-30932

PRISM 0043140

PRODUCER



J. Syler 9-4-2015

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-603-407
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NAVAJO
2. NAME OF OPERATOR: RESOLUTE NATURAL RESOURCES		7. UNIT or CA AGREEMENT NAME: RATHERFORD
3. ADDRESS OF OPERATOR: 1700 Lincoln Street, Suite 2800 , Denver, CO, 80203 4535		8. WELL NAME and NUMBER: 29-33
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1859 FSL 1836 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 29 Township: 41.0S Range: 24.0E Meridian: S		9. API NUMBER: 43037309320000
PHONE NUMBER: 303 534-4600 Ext		9. FIELD and POOL or WILDCAT: GREATER ANETH
COUNTY: SAN JUAN		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 3/24/2016	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input checked="" type="checkbox"/> OTHER	
	OTHER: Workover/ pump replacement	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Resolute Natural Resources respectfully submits this sundry as notice that the workover was completed on the above well to replace the failed ESP pump with a Rod pump		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY April 11, 2016		
NAME (PLEASE PRINT) Erin Joseph	PHONE NUMBER 303 573-4886	TITLE Sr. Regulatory Analyst
SIGNATURE N/A	DATE 3/30/2016	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-603-407
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NAVAJO
2. NAME OF OPERATOR: RESOLUTE NATURAL RESOURCES		7. UNIT or CA AGREEMENT NAME: RATHERFORD
3. ADDRESS OF OPERATOR: 1700 Lincoln Street, Suite 2800 , Denver, CO, 80203 4535		8. WELL NAME and NUMBER: 29-33
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1859 FSL 1836 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 29 Township: 41.0S Range: 24.0E Meridian: S		9. API NUMBER: 43037309320000
PHONE NUMBER: 303 534-4600 Ext		9. FIELD and POOL or WILDCAT: GREATER ANETH
COUNTY: SAN JUAN		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION	<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 4/16/2016 <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:
		<input checked="" type="checkbox"/> OTHER	OTHER: Retrieve stuck pump	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

 Resolute Natural Resources respectfully submits this sundry as notice that the stuck pump was recovered 4/16/16 according to previously approved procedures.

Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY
 May 13, 2016

NAME (PLEASE PRINT) Erin Joseph	PHONE NUMBER 303 573-4886	TITLE Sr. Regulatory Analyst
SIGNATURE N/A	DATE 5/13/2016	

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9																														
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-603-407																														
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NAVAJO																														
2. NAME OF OPERATOR: RESOLUTE NATURAL RESOURCES		7. UNIT or CA AGREEMENT NAME: RATHERFORD																														
3. ADDRESS OF OPERATOR: 1700 Lincoln Street, Suite 2800 , Denver, CO, 80203 4535		8. WELL NAME and NUMBER: 29-33																														
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1859 FSL 1836 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 29 Township: 41.0S Range: 24.0E Meridian: S		9. API NUMBER: 43037309320000																														
9. FIELD and POOL or WILDCAT: GREATER ANETH		COUNTY: SAN JUAN																														
STATE: UTAH																																
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA																																
TYPE OF SUBMISSION <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 10/27/2016 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	TYPE OF ACTION <table style="width: 100%;"> <tr> <td><input type="checkbox"/> ACIDIZE</td> <td><input type="checkbox"/> ALTER CASING</td> <td><input type="checkbox"/> CASING REPAIR</td> </tr> <tr> <td><input type="checkbox"/> CHANGE TO PREVIOUS PLANS</td> <td><input type="checkbox"/> CHANGE TUBING</td> <td><input type="checkbox"/> CHANGE WELL NAME</td> </tr> <tr> <td><input type="checkbox"/> CHANGE WELL STATUS</td> <td><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS</td> <td><input type="checkbox"/> CONVERT WELL TYPE</td> </tr> <tr> <td><input type="checkbox"/> DEEPEN</td> <td><input type="checkbox"/> FRACTURE TREAT</td> <td><input type="checkbox"/> NEW CONSTRUCTION</td> </tr> <tr> <td><input type="checkbox"/> OPERATOR CHANGE</td> <td><input type="checkbox"/> PLUG AND ABANDON</td> <td><input type="checkbox"/> PLUG BACK</td> </tr> <tr> <td><input type="checkbox"/> PRODUCTION START OR RESUME</td> <td><input type="checkbox"/> RECLAMATION OF WELL SITE</td> <td><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION</td> </tr> <tr> <td><input type="checkbox"/> REPERFORATE CURRENT FORMATION</td> <td><input type="checkbox"/> SIDETRACK TO REPAIR WELL</td> <td><input type="checkbox"/> TEMPORARY ABANDON</td> </tr> <tr> <td><input type="checkbox"/> TUBING REPAIR</td> <td><input type="checkbox"/> VENT OR FLARE</td> <td><input type="checkbox"/> WATER DISPOSAL</td> </tr> <tr> <td><input type="checkbox"/> WATER SHUTOFF</td> <td><input type="checkbox"/> SI TA STATUS EXTENSION</td> <td><input type="checkbox"/> APD EXTENSION</td> </tr> <tr> <td><input type="checkbox"/> WILDCAT WELL DETERMINATION</td> <td><input checked="" type="checkbox"/> OTHER</td> <td>OTHER: <input type="text" value="Repair a Stuck Pump"/></td> </tr> </table>		<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input checked="" type="checkbox"/> OTHER	OTHER: <input type="text" value="Repair a Stuck Pump"/>
<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR																														
<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME																														
<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE																														
<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION																														
<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK																														
<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION																														
<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON																														
<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL																														
<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION																														
<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input checked="" type="checkbox"/> OTHER	OTHER: <input type="text" value="Repair a Stuck Pump"/>																														
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Resolute Natural Resources respectfully submits this sundry as notice of a repair on a stuck pump on the above well. Attached are the procedures and schematics																																
Accepted by the Utah Division of Oil, Gas and Mining Date: November 09, 2016 By: <u>Derek Duff</u>																																
NAME (PLEASE PRINT) Erin Joseph		PHONE NUMBER 303 573-4886																														
SIGNATURE N/A		TITLE Sr. Regulatory Analyst																														
DATE 10/27/2016																																

Procedure

Horsley Witten: No.

1. MIRU WSU, LOTO,
2. Evaluate polish rod and stuck pump position. No failure report has been completed.
3. Kill well as necessary.
4. POOH with rods X pump. Fish or strip as necessary. Stand back in derrick. Contact Tech Support: Virgil Holly or Nate Dee for rod inspection.
5. ND WH. NU BOPE.
6. Release the TAC @ ~4798' KB. Install a packer. Pressure test BOPE.
7. TOOH with tubing. Stand back in derrick.
8. Call and notify Virgil Holly or Nate Dee to inspect tubing.
9. If tubing needs replaced, run YB , as necessary.
10. PU bit. Clean out to PBTD of 5744. Bottom perf at 5726'. Window at 5161 - 5169. Use N2 as necessary. It is not planned to attempt a lateral cleanout. Do not pump into the lateral. POOH.
11. TIH with 2-7/8" orange peel joint; Four ft (4') perf sub, SN, one joint 70XT 2-7/8", TAC, and 2-7/8 tubing to surface. Set TAC at ~4000 ft or 1000 ft above window. **Note: Change in BHA and setting**
12. NDBOP, NUWH.
13. RIH with rods & insert pump. Contact Tech Support for pump and rod questions.
14. Long stroke pump to test for good pumping action.
15. Leave enough polished rod for operators to correctly space pump as required.
16. Notify the Area Production Supervisor Terry Lee or Alfred Redhouse that well is ready to return to production.
17. RDMOL. Hook up appropriate chemical treatment.

RATHERFORD UNIT # 29-33H

GREATER ANETH FIELD


1860' FSL & 1820' FEL

SEC 29-T41S-R24E

SAN JUAN COUNTY, UTAH

API 43-037-30932

PRODUCER



J. Styler 9-4-2015

Resolute

Schematic - Current

WellView®

Well Name: RU 29-33


API Number 4303730932	Gr/Gr SE	Field Name Rutherford Unit	State/Province Utah	Wellbore Conf Vertical	Energy ID# 0857.01
Ground Elevation (ft) 4911	Casing Flange Elevation (ft)	KB-Ground Distance (ft) 16.90	KB-Casing Flange Distance (ft)	Regulatory Spud Date 12/26/1983 00:00	Rig Release Date/Time 1/28/1984 00:00

Most Recent Job

Job Category Workover	Primary Job Type Pump Repair	Secondary Job Type	Start Date 3/17/2016	End Date 4/15/2016
--------------------------	---------------------------------	--------------------	-------------------------	-----------------------

Schematic

Vertical - Rutherford U 2933, 10/26/2016 8:30:05 AM



STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-603-407
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: NAVAJO
2. NAME OF OPERATOR: RESOLUTE NATURAL RESOURCES		7. UNIT or CA AGREEMENT NAME: RATHERFORD
3. ADDRESS OF OPERATOR: 1700 Lincoln Street, Suite 2800 , Denver, CO, 80203 4535		8. WELL NAME and NUMBER: 29-33
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1859 FSL 1836 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 29 Township: 41.0S Range: 24.0E Meridian: S		9. API NUMBER: 43037309320000
PHONE NUMBER: 303 534-4600 Ext		9. FIELD and POOL or WILDCAT: GREATER ANETH
COUNTY: SAN JUAN		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 11/10/2016	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input checked="" type="checkbox"/> OTHER	
	<input type="checkbox"/> CASING REPAIR	
	<input type="checkbox"/> CHANGE WELL NAME	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> APD EXTENSION	
	OTHER: <input type="text" value="Pump Repair"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Resolute Natural Resources respectfully submit this sundry as notice that the pump repair on the above well was completed on 11/10/2016 according to previously approved procedures		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY November 29, 2016		
NAME (PLEASE PRINT) Erin Joseph	PHONE NUMBER 303 573-4886	TITLE Sr. Regulatory Analyst
SIGNATURE N/A	DATE 11/22/2016	